

007

40013 32673

FIML Natural Resources, LLC

September 2, 2004

Mr. Ed Forsman
Bureau of Land Management
Vernal Field Office
170 South 500 East
Vernal, UT 84078


RE: Notice of stakings

Dear Mr. Forsman:

Enclosed in this fax are three notices of staking. They are for the Ute Tribal 7-13-54 well located in the SW/4 NE/4 of Section 13, T-5S, R-4W, the Ute Tribal 2-30-55 well located in the NW/4 NE/4 of Section 30, T-5S, R-5W, and the Ute Tribal 8-31-55 well located in the SE/4 NE/4 of Section 31, T-5S, R-5W. All three wells have been tentatively set up for an on-site with the BIA at 9:00 a.m., Wednesday, September 8, 2004. Please call me at (303) 893-5081 if you have any questions concerning this matter.

Sincerely,

FIML Natural Resources, LLC



Rick L. Parks
Operations Manager


RECEIVED

SEP 08 2004

DIV. OF OIL, GAS & MINING

NOTICE OF STAKING		6. Lease Number <i>EDA # 14-20-H62-5032</i>	
1. Oil Well <u> X </u> Gas Well <u> </u> Other <u> </u> (Specify):		7. If Indian, Allottee or Tribe Name: <i>Ute Tribe</i>	
2. Name of Operator <i>FIML Natural Resources, LLC</i>		8. Unit Agreement Name	
3. Name of Specific Contact Person <i>Rick L. Parks</i>		9. Farm or Lease Name <i>Ute Tribal</i>	
4. Address & Phone Number of Operator or Agent <i>410 17th St., Suite 570, Denver, CO 80202 (303) 893-5073</i>		10. Well Number <i>8-31-55</i>	
5. Surface Location of Well: <i>1,980' FNL 660' FEL</i>		11. Field or Wildcat Name <i>Brundage Canyon</i>	
		12. Sec., T., R., M., or Blk and Survey or Area <i>31, T-5S, R-5W U.S.B. & M.</i>	
15. Production Objective(s) <i>Green River/Wasatch</i>	16. Estimated Well Depth <i>6,231</i>	13. County, Parish, or Borough <i>Duchesne</i>	14. State <i>Utah</i>
17. Additional Information (as appropriate; shall include surface owner's name) <i>Ute Indian Tribe</i>			

18. Signed



Title: Senior Vice President

Date: 9/02/2004

RECEIVED
SEP 08 2004

DIV. OF OIL, GAS & MINING

FIML NATURAL RESOURCES, LLC

September 15, 2004

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, UT 84114-5801

Attn.: Ms. Diana Whitney

RE: Ute Tribal #8-31-55
SENE Sec 31 T-5-S R-5-W
~~Brundage Canyon Field~~ Undersigned
Duchesne County, Utah

Dear Ms. Whitney:

Enclosed are an original and one copy of an application to drill concerning the referenced proposed well. This information was submitted to the Bureau of Land Management on September 15, 2004.

FIML (FNR) Natural Resources, LLC is requesting the Utah Division of Oil, Gas and Mining to hold this application and all future information as confidential.

If any questions arise or need additional information, please contact the undersigned at 303-893-5081.

Sincerely,



Rick L. Parks
Operations Manager

RECEIVED
SEP 20 2004
DIV. OF OIL, GAS & MINING

/ps
Enclosures:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0136
Expires January 31, 2004

001



APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 14-20-H62-5060
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name Ute Tribe
2. Name of Operator FIML Natural Resources, LLC		7. If Unit or CA Agreement, Name and No.
3a. Address 410 17th St., Suite 570, Denver CO 80202	3b. Phone No. (include area code) 303-893-5073	8. Lease Name and Well No. Ute Tribal 8-31-55
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SENE 1,980' FNL 660' FEL 544178X 40.00503 At proposed prod. zone Same as above 4428234Y -110.48243		9. API Well No. 43-013-32673
14. Distance in miles and direction from nearest town or post office* 32.15 miles southwest of Myton, Utah		10. Field and Pool, or Exploratory Brundage Canyon undesignated
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 660'		11. Sec., T., R., M., or Blk. and Survey or Area Sec 31, T-5S, R-5W U.S.B.&M.
16. No. of Acres in lease 624	17. Spacing Unit dedicated to this well 40	12. County or Parish Duchesne
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. N/A	19. Proposed Depth 6,211'	13. State Utah
20. BLM/BIA Bond No. on file 8191-82-71	21. Elevations (Show whether DF, KDB, RT, GL, etc.) 7,823' GL (Ungraded)	22. Approximate date work will start* October 29, 2004
23. Estimated duration Seven days		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature 	Name (Printed/Typed) Mark D. Bingham	Date 9/15/04
Title Senior Vice President		
Approved by (Signature) 	Name (Printed/Typed) BRADLEY G. HILL	Date 09-22-04
Title ENVIRONMENTAL SCIENTIST III		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

CONFIDENTIAL

RECEIVED

SEP 20 2004

DIV. OF OIL, GAS & MINING

Federal Approval of this
Action is Necessary



T5S, R5W, U.S.B.&M.

FIML NATURAL RESOURCES, LLC,
UTE/FNR LLC.

Well location, UTE TRIBAL #8-31-55, located as shown in the SE 1/4 NE 1/4 of Section 31, T5S, R5W, U.S.B.&M. Duchesne County, Utah.

BASIS OF ELEVATION

BENCH MARK (M67) LOCATED IN THE SW 1/4 OF SECTION 9, T5S, R4W, U.S.B.&M. TAKEN FROM THE DUCHESNE SE QUADRANGLE, UTAH, DUCHESNE COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED ON CAP AS BEING 6097 FEET.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 1161319
STATE OF UTAH

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.
(AUTONOMOUS NAD 83)
LATITUDE = 40°00'18.30" (40.005083)
LONGITUDE = 110°28'58.52" (110.482922)

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 4-27-04	DATE DRAWN: 6-1-04
PARTY G.S. M.B. C.G.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE	FIML NATURAL RESOURCES, LLC, UTE/FNR LLC.


SELF CERTIFICATION STATEMENT

The following self-certification statement is provided per federal requirements dated June 15, 1988.

Please be advised that FIML Natural Resources, LLC is considered to be the operator of the following well.

Ute Tribal 8-31-55
SE/4 NE/4 1,980' FNL 660' FEL, Section 31 T-5S, R-5W U.S.B. & M.
Lease BIA: #14-20-H62-5060
Duchesne County, Utah

FIML Natural Resources, LLC is responsible under the terms of this lease for the operations conducted upon lease lands.



Rick L. Parks
Operations Manager
FIML Natural Resources, LLC
410 17th Street
Suite 570
Denver, Colorado 80202
(303) 893-5081

FIML NATURAL RESOURCES, LLC

Ute Tribal 8-31-55
 SENE 1,980' FNL 660' FEL Sec 31, T-5S, R-5W, U.S.B. & M.
 Duchesne County, Utah
 BIA Lease Number 14-20-H62-5060

DRILLING PROGRAM

1. Estimated Tops of Geological Markers:

Formation	Depth
Uinta	surface
Green River	1,531'
Mahogany	2,931'
TGR3 Marker	3,656'
Douglas Creek	4,359'
Castle Peak	5,281'
Uteland Butte Ls.	5,706'
Wasatch	5,881'
Total Depth	6,211'

2. Estimated Depths of Anticipated Water, Oil, Gas, or Other Minerals:

Substance	Formation	Depth
Oil/Gas	Douglas Creek	4,344'
Oil/Gas	Castle Peak	5,266'
Oil/Gas	Uteland Butte	5,706'
Oil/Gas	Wasatch	5,881'
Other Mineral Zones	N/A	

3. Pressure Control Equipment:

Please refer to FIML Natural Resources, LLC Standard Operating Procedure (SOP Version: November 17, 2003).

4. Proposed Casing and Cementing Program:

Please refer to FIML Natural Resources, LLC Standard Operating Procedure (SOP Version: November 17, 2003).

5. Drilling Fluids Program:

Please refer to FIML Natural Resources, LLC Standard Operating Procedure (SOP Version: November 17, 2003).

6. **Evaluation Program:**

Please refer to FIML Natural Resources, LLC Standard Operating Procedure (SOP Version: November 17, 2003).

7. **Abnormal Conditions:**

Please refer to FIML Natural Resources, LLC Standard Operating Procedure (SOP Version: November 17, 2003).

8. **Anticipated Starting Dates and Notification of Operations:**

Please refer to FIML Natural Resources, LLC Standard Operating Procedure (SOP Version: November 17, 2003).

9. **Other Information:**

Please refer to FIML Natural Resources, LLC Standard Operating Procedure (SOP Version: November 17, 2003).

FIML NATURAL RESOURCES, LLC

Ute Tribal 8-31-55

Surface Location: SE/NE 1,980' FNL 660' FEL Sec 31, T-5S, R-5W, U.S.B. & M.

Duchesne County, Utah

BIA Lease Number 14-20-H62-5060

Onshore Order No. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads

- A. Start in Myton, Utah. Proceed west on US Highway 40, 8.8 miles to the Antelope Creek/Sowers Canyon Road at the Bridgeland turnoff. Turn south and proceed 16.5 miles on the Sowers Canyon Road. Turn north for approximately 0.2 miles and then proceed southwest for approximately 5.3 miles, going through the Berry Petroleum Company Ute Tribal 4-33-55 and the Ute Tribal 2-32-55 locations. After the road turns north for approximately 0.2 miles, turn southwest, west, and then north for approximately 1.25 miles on the new access road to the Ute Tribal 8-31-55 well site.
- B. The proposed well site is located approximately 32.15 miles southwest of Myton, Utah – See attached Topographic Map “A”.
- C. Refer to attached Topographic Map “B”.
- D. Existing roads will be maintained and repaired as necessary. No off lease Right-of-Way will be required.

2. Planned Access Roads

See Topographic Map “B” for the location of the proposed access road.

Access roads and surface disturbing activities will conform to standards outlined in the BLM and Forest Service publication, Surface Operating Standards for Oil and Gas Exploration and Development, Third Edition, 1989.

The proposed access road will be centerline staked and flagged during the initial staking process to ensure proper placement of the access road. New access roads will be constructed to the required specifications of the Right-of-Way Agreement. Any additional surface disturbance, not included in the APD, will be approved prior to such disturbance.

New access roads will have a usable surface of eighteen (18) feet to provide enough area for vehicles to meet and pass safely. They will be crowned, ditched, and constructed with a maximum disturbed width of thirty (30) feet. If necessary, all snow will be removed and the area allowed to dry prior to any construction. Rock and/or gravel will be used as necessary to construct safe, all-weather roads.

Generally, unless specifically noted in an individual APD, the maximum road grade will be ten (10) percent. If existing gas gathering lines are to be crossed, the gas gathering line will be cased and buried at least one (1) foot below the surface of the road.

There will be no turn-out areas unless necessary for safety reasons.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings will be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading will not be allowed during muddy conditions. Should mud holes develop, they will be filled and detours around them avoided.

There will be no major cuts and fills, culverts, or bridges unless specifically noted in the individual APD. If road construction determines the need for a culvert or bridge or if future weather conditions change the road topography and create the need for a culvert or bridge, FIML Natural Resources, LLC will request and receive permission from the surface owner for the necessary road change. FIML Natural Resources, LLC will also submit a Sundry Notice for approval to the BLM/VFO Authorized Officer outlining the need for and description of the necessary road changes. No road construction work will occur prior to receipt of approval.

Rock and/or gravel will be purchased and hauled in from private sources should additional surface material be needed.

Unless specifically noted in the APD, there will be no gates, cattle guards, fence cuts, or modifications to existing facilities.

All travel will be confined to the new and existing access road Rights-of Way.

Snow will be removed from the road to areas where snowmelt will occur away from the road. If holes or depressions occur due to heavy traffic, snow removal, or muddy conditions, said holes will be filled promptly with rock and/or gravel to ensure safe traffic flow.

The disturbed area of the access road will be frequently policed to ensure any type of trash is removed promptly.

There may be areas of the road which need to be wider due to the size of the necessary equipment used in the drilling and completion processes. Intersections, sharp curves, and switch-backs, as well as their respective construction areas, will be noted on the APD. Necessary approval from the surface owner and the BLM/VFO Authorized Officer will be obtained prior to any construction.

3. Location of existing wells within a one mile radius of proposed well location

See Topographic Map "C" for the location of existing wells within a one-mile radius.

4. Location of Existing and /or Proposed Facilities

All permanent (on site for six (6) months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six (6) months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and

Health Act) will be excluded. The required paint color is desert brown (10YR 6/4).

A fluid containment berm will surround the production tank(s), water tank(s), separator(s), treater(s), and line heater(s). The berm will consist of compacted subsoil, not topsoil. The berm shall be capable of containing, at a minimum, the entire contents of the largest single tank, separator, treater, or line heater in use, plus ten (10%) freeboard for precipitation.

A copy of the written Spill Prevention, Control, and Countermeasure (SPCC) Plan will be maintained in the nearest field office and will be available for Agency review during normal business hours.

See Topographic Map "D" for the proposed pipeline route. If possible, the meter run will be within one-hundred (100) feet of the wellhead. For safety reasons, the gas line will be anchored from the wellhead to the meter run. The meter run will be enclosed or fenced.

The guidelines identified in Federal regulation 43 CFR 3162.7 concerning site security will be followed to ensure the proper protection of all produced oil from site specific locations.

5. Location and Type of Water Supply

- A. The water supply will be from East Duchesne County Water District, Arcadia Utah, from a line located in Section 28, T-3S, R-3W, Duchesne County, Utah. #43-10152
- B. Water will be hauled by Ute Tribal Water Service.
- C. No water well will be drilled on the lease.

6. Source of Construction Materials

The access road will be constructed by using material from the approved access road area. Should the road need to be improved after construction, rock and/or gravel will be hauled from private sources.

The location will be constructed by using material from the approved site specific area. Should additional material be needed, it will be obtained from a private source.

If there are materials that could be used for either road or location construction under BLM jurisdiction, FIML Natural Resources, LLC will follow all guidelines within 43 CFR 3610.2-3.

7. Method of Handling Waste Materials

The reserve pit will be constructed in such a manner to prevent damage or failure of the reserve pit walls from surface runoff caused by rain or snowmelt. The walls will be constructed in a manner to prevent any type of leakage from the reserve pit.

The reserve pit will be lined with a synthetic reinforced liner, a minimum of 12 millimeters thick, with sufficient bedding, either straw or dirt, to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place.

No trash or other debris that could puncture the liner will be disposed of in the pit.

Any reserve pit leak of any kind will be immediately reported to the BLM/VFO Authorized Officer, the BIA, and the Ute Indian Tribe.

All drilling cuttings, including shale, will be contained and buried in the reserve pit.

All drilling fluids, including salts and chemicals, will be contained in the reserve pit. After drilling operations are completed, fluid from the reserve pit will either be hauled to the next drilling location or allowed to dry within the reserve pit. Any and all hydrocarbons will be removed from the reserve pit immediately after a well has been completed in accordance with regulation 43 CFR 3 162.7-1.

As per Onshore Oil and Gas Order No. 7, produced water will either be stored in the approved reserve pit or in some type of on-site storage tank for a period not to exceed ninety (90) days. During said ninety (90) day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with the required water analysis, will be submitted to the BLM/VFO Authorized Officer.

Produced oil and water will be stored in tanks. All produced water will be disposed of at the permanent disposal facility authorized by the BLM/VFO Authorized Officer. No produced water will be used for dust or weed control of any kind.

Should spills of any type occur, the area of the spill will be re-mediated and impacted soil will be hauled to an approved disposal facility.

A portable toilet will be on location during the drilling of the well.

All garbage, trash, and any other non-human waste materials will be stored in a portable, self-contained, fully enclosed trash container during all drilling operations. There will be no burning of trash on location at any time. After drilling operations are completed, all trash of any kind will be picked up and removed from location and hauled to an approved disposal facility.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of wells.

8. Ancillary Facilities

There are no ancillary facilities planned for at this time, and none are foreseen in the future.

9. Well Site Layout

The attached Location Layout diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, pipe racks, trailer parking, spoil dirt stockpile(s) and top soil stockpile(s).

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).

The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Distance between any two posts shall be no greater than sixteen (16) feet.

All wire shall be stretched using a stretching device before it is attached to corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the drilling rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. Plans for Restoration of the Surface

The dirt contractor will be provided with an approved copy of the Surface Use Plan prior to construction activities.

Prior to the construction of the location, at a maximum, the top twelve (12) inches of soil material will be stripped and stockpiled. Topsoil will be stockpiled separately from subsoil materials. Topsoil salvaged from the reserve pit will be stockpiled separately near the reserve pit. When all drilling and completion activities have been completed, the unused portion of the location not needed for well servicing or re-completion activities will be re-contoured and topsoil spread over the area.

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, and trash not required for production operations.

All pit fencing shall be removed prior to restoration operations. Prior to backfilling the reserve pit, the pit liner will be cut off at the water or mud line and disposed of at an approved landfill site. The pit liner will be torn and perforated after the pit dries.

The reserve pit and that portion of the location not needed for production facilities/operations will be re-contoured to the approximate natural contours. The

reserve pit will be reclaimed within one-hundred eighty (180) days, weather permitting, from the date of well completion. Prior to any restoration dirt work, the reserve pit will be completely dry and free of cans, barrels, pipe, etc. Reclamation activities will be completed within sixty (60) days of the date those activities are commenced.

After reserve pit reclamation, no depressions in the soil covering the reserve pit will be allowed. The objective will be to keep seasonal rainfall and runoff from seeping into the soil used to cover the reserve pit. Diversion ditches and water bars will be used to divert runoff as needed.

The Authorized Officer of the appropriate surface management agency shall be contacted for the required seed mixture. Seed will be drilled on the contour to an appropriate depth. If broadcast seeded, the amount of seed mixture per acre will be doubled, and a harrow or some other implement will be dragged over the seeded area to ensure seed coverage.

On lands administered by the BLM, abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions may include the re-establishment of appropriate soil contours and the re-establishment of vegetation as specified.

All disturbed areas will be re-contoured to approximate the natural contours.

Any drainage re-routed during the construction activities shall be restored to its original line of flow or as near as possible

Topsoil that is stored for more than one year shall be:

Windrowed, where possible, to a depth of three (3) to four (4) feet at a specified location near the edge of the site.

Broadcast seeded with the prescribed seed mixture immediately after windrowing. The Authorized Officer of the appropriate surface management agency shall be contacted for the required seed mixture. Seed will be drilled on the contour to an appropriate depth.

The stockpile shall be "walked" with a dozer to cover the seed.

Mulching may be one method considered to enhance the re-establishment of desired native plant communities. If straw or hay mulch is used, the straw and hay will be certified to be weed-free and the documentation submitted to the Authorized Officer prior to usage.

When restoration activities have been completed, the location site and access road cuts and shoulders shall be reseeded. Prior to reseeding, all disturbed areas will be scarified and left with a rough surface.

At final abandonment, all casing shall be cut off at the base of the cellar or three (3) feet below final restored ground level, whichever is deeper. The casing will be capped with a metal plate a minimum of 0.25 inch thick. The cap will be welded in place and the well location and identity will be permanently inscribed on the cap. The cap also will be constructed with a weep hole.

11. Surface Ownership

Access Road: Ute Indian Tribe

Location: Ute Indian Tribe

12. Other Information

All personnel will refrain from collecting artifacts and from disturbing any significant cultural resources in the area. FIML Natural Resources, LLC is responsible for informing all persons in the area who are associated with this project that they may be subject to prosecution for knowingly disturbing historic or archaeological sites or for collecting artifacts. All vehicular traffic, personnel movement, construction, and restoration activities shall be confined to the areas examined, as referenced in the archaeological report, and to the existing roadways and/or evaluated access routes. If historic or archaeological materials are uncovered during construction, FIML Natural Resources, LLC will immediately stop work that might further disturb such materials and contact the BLM/VFO Authorized Officer and/or the Ute Tribe Energy and Mineral Department.

Within five working days, the Authorized will inform the Operator as to:

The materials that appear eligible for the National Historic Register of Historic Places;

The mitigation measures FIML Natural Resources, LLC will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and,

A time frame for the BLM/VFO Authorized Officer to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the BLM/VFO Authorized Officer is correct and that mitigation is appropriate.

If FIML Natural Resources, LLC wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the BLM/VFO Authorized Officer and/or the surface owner will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, FIML Natural Resources, LLC will be responsible for mitigation costs. The BLM/VFO Authorized Officer and/or the surface owner will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the BLM/VFO Authorized Officer that required mitigation has been completed, FIML Natural Resources, LLC will then be allowed to resume construction.

FIML Natural Resources, LLC will control noxious weeds along Rights-of Way for roads, pipelines, well sites, and other applicable facilities. A list of noxious weeds will be obtained from the BLM or the appropriate County Extension Office. A Pesticide Use Proposal will be submitted and approved prior to the application of herbicides or other pesticides or possibly hazardous chemicals.

Drilling rigs and/or equipment used during drilling operations will not be stacked or

stored on BLM administered lands after the conclusion of drilling operations or at any other time without BLM/VFO Authorized Officer authorization. If BLM authorization is obtained, such storage will be only a temporary measure.

Travel is restricted to approved travel routes.

All Surface Use Conditions of Approval associated with the BIA Concurrence letter and Environmental Analysis Mitigation Stipulations will be adhered to, including:

All contractors used by FIML Natural Resources, LLC will have in their possession a Ute Indian Tribal Business License and associated access permits prior to entering Ute Indian Tribal Lands.

Upon completion of the APD and Right-of-Way construction, the Ute Tribe Energy and Mineral Department will be notified so that a Tribal Technician can verify an Affidavit of Completion.

FIML Natural Resources, LLC employees, including all subcontractors, will not gather firewood along roads constructed by FIML Natural Resources, LLC.

All roads constructed by FIML Natural Resources, LLC on the Uinta and Ouray Indian Reservation will have appropriate signs. Signs will be neat and of sound construction. The sign will state: (a) the land is owned by the Ute Indian Tribe, (b) the name of the Operator, (c) firearms are prohibited as to all non-Ute Tribal members, (d) permits must be obtained from the BIA before cutting firewood or other timber products, and (e) only authorized personnel are permitted.

The well site will have appropriate signs indicating the name of the Operator, the lease serial number, the well name and number, the survey description of the well (footages or the quarter/quarter section, the section, township, and range).

13. Operator's Representative and Certification

A. Representative:

Name: Rick L. Parks

Address: FIML Natural Resources, LLC
410 17th Street, Suite 570
Denver CO 80202


Phone: (303) 893-5081
Cellular: (303) 229-7689

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

FIML Natural Resources, LLC is fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" and the Standard Operating Procedures will be furnished to the field representative(s) to ensure compliance and will be on location during all construction and drilling operations.

B. Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge and belief, true and correct; and that the work associated with the operations proposed herein will be performed by FIML Natural Resources, LLC and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.



Rick L. Parks
Operations Manager
FIML Natural Resources, LLC

9/15/04
Date

EPA's LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide waste
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids

FIML NATURAL RESOURCES, LLC, UTE/FNR LLC
UTE TRIBAL #8-31-55
LOCATED IN DUCHESNE COUNTY, UTAH
SECTION 31, T5S, R5W, U.S.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: WESTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

05 **27** **04**
MONTH DAY YEAR

PHOTO

TAKEN BY: G.S.


DRAWN BY: P.M.

REVISED: 00-00-00

FIML NATURAL RESOURCES, LLC, UTE/FNR LLC.



LOCATION LAYOUT FOR

UTE TRIBAL #8-31-55
SECTION 31, T5S, R5W, U.S.B.&M.
1980' FNL 660' FEL



SCALE: 1" = 50'
DATE: 6-1-04
DRAWN BY: C.G.

NOTE:
Flare Pit is to
be located a min.
of 100' from the
Well Head.




Elev. Ungraded Ground at Location Stake = 7822.6'
Elev. Graded Ground at Location Stake = 7821.4'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah, 84078 * (435) 789-1017

UML NATURAL RESOURCES, LLC,
UTE/FNR LLC.





TYPICAL CROSS SECTIONS FOR

UTE TRIBAL #8-31-55
SECTION 31, T5S, R5W, U.S.B.&M.
1980' FNL 660' FEL



1" = 20'
X-Section
Scale
1" = 50'

DATE: 6-1-04
DRAWN BY: C.G.




* NOTE:
FILL QUANTITY INCLUDES
5% FOR COMPACTION

APPROXIMATE YARDAGES

CUT
(12") Topsoil Stripping = 2,660 Cu. Yds.
Remaining Location = 5,720 Cu. Yds.
TOTAL CUT = 8,380 CU.YDS.
FILL = 4,030 CU.YDS.

EXCESS MATERIAL = 4,350 Cu. Yds.
Topsoil & Pit Backfill = 4,350 Cu. Yds.
(1/2 Pit Vol.)
EXCESS UNBALANCE = 0 Cu. Yds.
(After Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



LEGEND:

○ PROPOSED LOCATION

N



FIML NATURAL RESOURCES, LLC, UTE/FNR LLC

UTE TRIBAL #8-31-55

SECTION 31, T5S, R5W, U.S.B.&M.

1980' FNL 660' FEL




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

05 27 04
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: P.M. REVISED: 00-00-00





LEGEND:

— EXISTING ROAD
 - - - PROPOSED ACCESS ROAD



FIML NATURAL RESOURCES, LLC, UTE/FNR LLC

UTE TRIBAL #8-31-55
SECTION 31, T5S, R5W, U.S.B.&M.
1980' FNL 660' FEL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP

SCALE: 1" = 2000' DRAWN BY: P.M. REVISED: 00-00-00

B
TOPO



**PROPOSED LOCATION:
UTE TRIBAL #8-31-55**

**T5S
T6S**

LEGEND:

- | | |
|-------------------|-------------------------|
| ○ DISPOSAL WELLS | ○ WATER WELLS |
| ● PRODUCING WELLS | ● ABANDONED WELLS |
| ● SHUT IN WELLS | ● TEMPORARILY ABANDONED |

FIML NATURAL RESOURCES, LLC, UTE/FNR LLC

**UTE TRIBAL #8-31-55
SECTION 31, T5S, R5W, U.S.B.&M.
1980' FNL 660' FEL**



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813




**TOPOGRAPHIC
MAP**

05 27 04
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: P.M. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 2,900' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- - - - PROPOSED PIPELINE



FIML NATURAL RESOURCES, LLC, UTE/FNR LLC

UTE TRIBAL #8-31-55
SECTION 31, T5S, R5W, U.S.B.&M.
1980' FNL 660' FEL




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP
05 27 04
MONTH DAY YEAR
SCALE: 1" = 1000' DRAWN BY: P.M. REVISED: 00-00-00




BOP AND PRESSURE CONTAINMENT DATA

1. BOP EQUIPMENT SHALL CONSIST OF A DOUBLE GATE, HYDRAULICALLY OPERATED PREVENTER WITH PIPE & BLIND RAMS OR TWO SINGLE RAM TYPE PREVENTERS, ONE EQUIPPED WITH PIPE RAMS, THE OTHER EQUIPPED WITH BLIND RAMS.
2. BOP'S ARE TO BE WELL BRACED WITH HAND CONTROLS EXTENDED CLEAR OF THE SUBSTRUCTURE.
3. ACCUMULATOR TO PROVIDE CLOSING PRESSURE IN EXCESS OF THAT REQUIRED WITH SUFFICIENT VOLUME TO OPERATE ALL COMPONENTS.
4. AUXILIARY EQUIPMENT: LOWER KELLY COCK, FULL OPENING STABBING VALVE, 2" CHOKE MANIFOLD, PIT LEVEL INDICATOR &/OR FLOW SENSORS WITH ALARMS.
5. ALL BOP EQUIPMENT, AUXILIARY EQUIPMENT, STAND PIPE, VALVES, & ROTARY HOSE TO BE TESTED TO THE RATE PRESSURE OF THE BOP'S AT THE TIME OF INSTALLATION & EVERY 30 DAYS THEREAFTER. BOP'S TO BE MECHANICALLY CHECKED DAILY.
6. MODIFICATION OF HOOK-UP OR TESTING PROCEDURE MUST BE APPROVED IN WRITING ON TOUR REPORTS BY WELLSITE REPRESENTATIVE.



3000 PSI CHOKE MANIFOLD EQUIPMENT



005

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 09/20/2004

API NO. ASSIGNED: 43-013-32673

WELL NAME: UTE TRIBAL 8-31-55

OPERATOR: FIML NATURAL RESOURCES (N2530)

CONTACT: MARK BINGHAM

PHONE NUMBER: 303-893-5073

PROPOSED LOCATION:

SENE 31 050S 050W

SURFACE: 1980 FNL 0660 FEL

BOTTOM: 1980 FNL 0660 FEL

DUCHESNE

UNDESIGNATED (2)

LEASE TYPE: 2 - Indian

LEASE NUMBER: 14-20-H62-5060

SURFACE OWNER: 2 - Indian

PROPOSED FORMATION: WSTC

COALBED METHANE WELL? NO

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LATITUDE: 40.00503

LONGITUDE: -110.4824

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[2] Sta[] Fee[]
(No. 8191-82-71)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. 43-10152)
☒ RDCC Review (Y/N)
(Date:)
☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

R649-2-3.

Unit


☒ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
☐ R649-3-3. Exception
☐ Drilling Unit
Board Cause No: _____
Eff Date: _____
Siting: _____
☐ R649-3-11. Directional Drill

COMMENTS:

See Separate file

STIPULATIONS:

1- Spacing Slip
2- FEDERAL APPROVAL




OPERATOR: FIML NATURAL RES LLC (N2530)

SEC. 31 T.5S R.5W

FIELD: UNDESIGNATED (002)

COUNTY: DUCHESNE

SPACING: R649-3-2 / GENERAL SITING



Utah Oil Gas and Mining

Wells	Units.shp	Fields.shp
⚡ GAS INJECTION	EXPLORARY	ABANDONED
⊛ GAS STORAGE	GAS STORAGE	ACTIVE
× LOCATION ABANDONED	NF PP OIL	COMBINED
⊕ NEW LOCATION	NF SECONDARY	INACTIVE
⬢ PLUGGED & ABANDONED	PENDING	PROPOSED
* PRODUCING GAS	PI OIL	STORAGE
● PRODUCING OIL	PP GAS	TERMINATED
⊛ SHUT-IN GAS	PP GEOTHERML	
⊛ SHUT-IN OIL	PP OIL	
× TEMP. ABANDONED	SECONDARY	
○ TEST WELL	TERMINATED	
▲ WATER INJECTION		
◆ WATER SUPPLY		
⚡ WATER DISPOSAL		



PREPARED BY: DIANA WHITNEY
DATE: 20-SEPTEMBER-2004



State of Utah

Department of
Natural Resources

ROBERT L. MORGAN
Executive Director

Division of
Oil, Gas & Mining

LOWELL P. BRAXTON
Division Director

OLENE S. WALKER
Governor

GAYLE F. McKEACHNIE
Lieutenant Governor

September 22, 2004

FIML Natural Resources, LLC
410 17th St., Suite 570
Denver, CO 80202

Re: Ute Tribal 8-31-55 Well, 1980' FNL, 660' FEL, SE NE, Sec. 31, T. 5 South,
R. 5 West, Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-32673.

Sincerely,

A handwritten signature in black ink, appearing to read "John R. Baza".

John R. Baza
Associate Director

pab
Enclosures

cc: Duchesne County Assessor
Bureau of Land Management, Vernal District Office

Operator: FIML Natural Resources, LLC
Well Name & Number Ute Tribal 8-31-55
API Number: 43-013-32673
Lease: 14-20-H62-5060

Location: SE NE Sec. 31 T. 5 South R. 5 West

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

008 APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0136
Expires January 31, 2004



1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 14-20-H62-5060
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name Ute Tribe
2. Name of Operator FIML Natural Resources, LLC		7. If Unit or CA Agreement, Name and No.
3a. Address 410 17th St., Suite 570, Denver CO 80202	3b. Phone No. (include area code) 303-893-5073	8. Lease Name and Well No. Ute Tribal 8-31-55
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SENE 1,980' FNL 660' FEL At proposed prod. zone Same as above		9. API Well No. 43.013.32673
14. Distance in miles and direction from nearest town or post office* 32.15 miles southwest of Myton, Utah	10. Field and Pool, or Exploratory Brundage Canyon	11. Sec., T., R., M., or Blk. and Survey or Area Sec 31, T-5S, R-5W U.S.B.&M.
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 660'	16. No. of Acres in lease 624	17. Spacing Unit dedicated to this well 40
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. N/A	19. Proposed Depth 6,211'	20. BLM/BIA Bond No. on file 8191-82-71
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 7,823' GL (Ungraded)	22. Approximate date work will start* October 29, 2004	23. Estimated duration Seven days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 	Name (Printed/Typed) Mark D. Bingham	Date 9/15/04
Title Senior Vice President		
Approved by (Signature) 	Name (Printed/Typed) Assistant Field Manager	Date 11/18/2004
Title Mineral Resources	Office	

Application approval does not warrant or certify that the applicant holds legal or equitable title to these rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

CONDITIONS OF APPROVAL ATTACHED

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: FIML Natural Resources LLC

Well Name & Number: UTE TRIBAL 8-31-55

API Number: 43-013-32673

Lease Number: 14-20-H62-5060

Location: SENE Sec. 31 TWN: 05S RNG: 05W

Agreement: N/A

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease, which would entitle the applicant to conduct operations thereon.

Submit an electronic copy of all logs run on this well in LAS format. This submission will replace the requirement for submittal of paper logs to the BLM.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Casing Program and Auxiliary Equipment

As a minimum, the usable water and other valuable resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the Green River Formation, identified at ± 1460 ft.

2. Other Information

In the event after-hours approvals are necessary, please contact one of the following individuals:

Ed Forsman (435) 828 -7874 (CELL)
Petroleum Engineer

Kirk Fleetwood (435) 828 -7875 (CELL)
Petroleum Engineer

BLM FAX Machine (435) 781-4410

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

FIML Natural Resources, LLC (FIML) will assure the Ute Tribe that any/all contractors and subcontractors have acquired a current Tribal Business License and have updated "Access Permits" prior to construction. All FIML personnel, contractors and subcontractors will have these permits in their vehicles at all times. Companies that have not complied with this COA will be in violation of the Ute Tribal Business License Ordinance, and will be subject to fines and penalties.

FIML employees, representatives, and/or authorized personnel (subcontractors) shall not carry firearms on their person or in their vehicles while working on the Uintah and Ouray Indian Reservation.

FIML employees and/or authorized personnel (subcontractors) in the field will have approved applicable APDs and/or ROW permits/authorizations on their person(s) during all phases of construction.

FIML will notify the Ute Tribe and Bureau of Indian Affairs (BIA) in writing of any requested modification of APDs or Rights-Of Way (ROW). FIML shall receive written notification of authorization or denial of the requested modification. Without authorization, FIML will be subject to fines and penalties.

The Ute Tribe Energy & Minerals Department shall be notified in writing 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday. A Tribal Technician is to routinely monitor construction. FIML shall make arrangements with the Ute Energy & Minerals Department for all monitoring that will exceed regular working hours for Tribal Technicians. A qualified Archaeologist accompanied by a Tribal Technician will monitor any trenching construction involved in the pipeline construction. FIML is to inform contractors to maintain construction of the pipelines within the approved right of ways.

A corridor ROW, 30 feet wide and 4261 feet long, shall be granted for the pipeline and an overlapping ROW, 30 feet wide and 4153 feet long, shall be granted for the new and existing access roads associated with the Ute Tribal 2-30-55 well. An additional corridor of 2191 feet length for the proposed pipeline and access roads is located on private land. Actual new road construction is 91 feet on the private lands and 474 feet on Tribal Lands within the previously mentioned road Rights of Way.

A corridor ROW, 30 feet wide and 6,915 feet, shall be granted for the pipeline and new access road for the Ute Tribal 8-31-55 well. About 4,000 feet of that corridor would be shared with two proposed Berry Wells, both located in Section 32, which have not been built yet even though their APDs were approved September 29, 2003 and are authorized for two years. It is likely that if Berry Petroleum drills those two wells an additional pipeline will be located in that part of the corridor for them.

The constructed travel width of the new access roads shall be limited to 18 feet. Upon authorization by the Ute Tribe Energy & Minerals Department, the ROW may be wider where sharp curves; deep cuts and fills occur; or, where intersections with other roads are required.

Culverts and diversion ditches will be placed and constructed where needed.

Upon completion of the pertinent APD and ROWs construction, FIML will notify the Ute Tribe Energy & Minerals Department for a Tribal Technician to verify the Affidavit of Completion.

Production waters, oil, and other byproducts shall not be placed on access roads or the well pad.

All vehicular traffic, personnel movement, construction and restoration operations will be confined to the areas examined and approved and to the existing roadways and/or evaluated access routes.

FIML will implement "Safety and Emergency Plan" and ensure plan compliance.

FIML shall stop construction activities and notify personnel from the Ute Tribe Energy & Minerals Department and BIA if cultural remains including paleontology resources (vertebrate fossils) are exposed or identified during construction. The Ute Tribe Department of Cultural Rights and Protection and the BIA will provide mitigation measures prior to allowing construction.

FIML employees and/or authorized personnel (subcontractors) will not be allowed to collect artifacts and paleontology fossils. No significant cultural resources shall be disturbed.

FIML will control noxious weeds on the well site and ROWs. FIML will be responsible for noxious weed control if weeds spread from the project area onto adjoining land.

Reserve pits will be lined with an impervious synthetic liner. A fence will be constructed around the reserve pit until it is backfilled. Prior to backfilling the reserve pit, all fluids will be pumped from the pit into trucks and hauled to approved disposal sites or shall be used to drill other wells.

When the reserve pits are backfilled, the pit liner remnants, the surplus oil and mud, etc., will be buried a minimum of 3.0 feet below the surface of the soil.

A closed system will be used during production. This means that production fluids will be contained in leak-proof tanks. All production fluids will be disposed of at approved disposal sites.

Surface pipelines will be constructed to lay on the soil surface. The pipeline ROW will not be bladed or cleared of vegetation without authorization of the BIA. Surface pipelines shall be welded in place at well sites or on access roads and on other existing roads then pulled into place with suitable equipment. The pipeline portion of the ROW will not be bladed or cleared of vegetation without authorization of the BIA.

Buried pipelines shall be buried a minimum of 3 feet below the soil surface. After construction is completed the disturbed area shall be contoured to blend into the natural landscape and be reseeded between September 15 and November 1 of the year following construction with perennial vegetation seed mixture provided by the BIA or Ute Tribe.

Before the site is abandoned, FIML will be required to restore the well site and ROWs to near their original state. The disturbed areas will be reseeded with desirable perennial vegetation.

Soil erosion will be mitigated, by reseeding all areas of disturbance.

CONFIDENTIAL

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: FIML NATURAL RESOURCES

Well Name: UTE TRIBAL 8-31-55

Api No: 43-013-32673 Lease Type: INDIAN

Section 31 Township 05S Range 05W County DUCHESNE

Drilling Contractor CRAIG'S ROUSTABOUT SERV RIG # RATHOLE

SPUDDED:

Date 11/26/2004

Time _____

How DRY

Drilling will commence: _____

Reported by CRAIG OVERMILLER

Telephone # 1-435-828-7151

Date 11/30/2004 Signed CHD

010

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

RECEIVED

NOV 30 2004

FORM 6

DIV. OF OIL, GAS & MINING

ENTITY ACTION FORM

Operator: FIML Natural Resources, LLC
Address: 410 17th Street, Suite 570
city Denver
state CO zip 80202

Operator Account Number: N 2530Phone Number: 303-893-5083

Well 1

API Number	Well Name	QC	Sec	Twp	Rng	County
43-013-32673	Ute Tribal #8-31-55	SENE	31	5S	5W	Duchesne
Action Code	Current Entity Number	New Entity Number	Start Date	Entity Assignment Effective Date		
A	99999	14407	Nov 26, 2004	11/30/04	K	
Comments: <u>WSTC</u> CONFIDENTIAL						

Well 2

API Number	Well Name	QC	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Start Date	Entity Assignment Effective Date		
Comments:						

Well 3

API Number	Well Name	QC	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Start Date	Entity Assignment Effective Date		
Comments:						

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Phyllis Sobotik

Name (Please Print)

Phyllis Sobotik

Signature

Regulatory Specialist

Nov 30, 2004

Title

Date

FIML NATURAL RESOURCES, LLC

November 30, 2004

CONFIDENTIAL

RECEIVED
DEC 06 2004
DIV. OF OIL, GAS & MINING

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, UT 84114-5801

Attn.: Ms. Carol Daniels

RE: Ute Tribal #8-31-55
SENE Sec 31 T-5S R-5W
Duchesne County, Utah


Dear Ms. Daniels:

Enclosed is the following information concerning the referenced well.

Sundry Notice – Spud; Setting Conductor & Surface Casing

If any questions arise or additional information is required, please contact me at 303-893-5083.

Sincerely,



Phyllis Sobotik
Regulatory Specialist

/ps
Enclosures:

RECEIVED
DEC 06 2004
DIV. OF OIL, GAS & MINING

DEC 06 2004

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator **FIML Natural Resources, LLC**3a. Address
410 17th Street, Suite 570 Denver, CO 802023b. Phone No. (include area code)
303-893-50834. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Spud & set Surf
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	csg
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The Ute Tribal #8-31-55 surf hole spud @ 08:30 hrs (MST) on November 26, 2004.

MIRU Craig's rathole machine. Drld mouse hole & rat hole. Drld 16" hole to 10' (GLM). Set 14" conductor csg @ 6' (GLM). Drld 12-1/4" hole f/ 10' to 330' (GLM). Ran 7 jts (311.10') 8-5/8" 24.0# J-55 ST&C cond "A" Newport csg. Set csg @ 311' (GLM). RU Big 4 Cementers. Pumped 20 bbls FW followed w/ 20 bbls 8.5 gelled wtr. Cmt w/ 180 sx (36.9 bbls) Premium cmt containing 2.0% CaCl₂ & 0.25% flocele. Displ cmt w/ 16.5 bbls FW. Full circ through out the job. Circ 7.0 bbls (34.2 sx) cmt to surf. CIP @ 19:30 hrs. (MST) 11/26/04. RDMO Big 4 Cementers & Craig's Rathole Drilling. WORT

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

RECEIVED
DEC 06 2004
DIV. OF OIL, GAS & MINING14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)**Phyllis Sobotik**Title **Regulatory Specialist**

Signature

Date

Nov 30 2004**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

FIML NATURAL RESOURCES, LLC

December 2, 2004

CONFIDENTIAL

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, UT 84114-5801

Attn.: Ms. Carol Daniels

RE: Ute Tribal #8-31-55
SENE Sec 31 T-5S R-5W
Duchesne County, Utah


Dear Ms. Daniels:

Enclosed is the following information concerning the referenced well.

Sundry Notice – Resume Drilling Operations

If any questions arise or additional information is required, please contact me at 303-893-5083.

Sincerely,



Phyllis Sobotik
Regulatory Specialist

/ps
Enclosures:

RECEIVED
DEC 06 2004
DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator **FIML Natural Resources, LLC**3a. Address
410 17th Street, Suite 570 Denver, CO 802023b. Phone No. (include area code)
303-893-5083

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Resume Drilg
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Operations
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Union Drilling Company Rig #14 resumed drilling operations on December 2, 2004.

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

RECEIVED
DEC 06 2004
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)**Phyllis Sobotik**Title **Regulatory Specialist**

Signature

Date

Dec 2 2004**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

FIML NATURAL RESOURCES, LLC

December 14, 2004

CONFIDENTIAL

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, UT 84114-5801

Attn.: Ms. Carol Daniels

RE: Ute Tribal #8-31-55
SENE Sec 31 T-5S R-5W
Duchesne County, Utah


Dear Ms. Daniels:

Enclosed is the following information concerning the referenced well.

Sundry Notice with Attached Composite Drilling Operations Report

If any questions arise or additional information is required, please contact me at 303-893-5083.

Sincerely,



Phyllis Sobotik
Regulatory Specialist

/ps
Enclosures:

RECEIVED
DEC 27 2004
DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator
FIML Natural Resources, LLC3a. Address
410 17th Street, Suite 570 Denver, CO 802023b. Phone No. (include area code)
303-893-50834. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Drig Operations
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Composite Report
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Attached is the composite drilling operations report.

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

RECEIVED
DEC 27 2004
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Phyllis Sobotik

Title Regulatory Specialist

Signature

Date

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBSD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

11/26/04 Days since spud: 1

Total Depth: 330'

24 hr. footage: 330'

Present Operation: WORT

MW:

Surveys:

Current Activity: 14 hrs-MIRU Craig's rathole machine. Drld mouse hole & rat hole. Drld 16" hole to 10' (GLM). Set 14" conductor csg @ 6' (GLM). Drld 12-1/4" hole f/ 10' to 330' (GLM). Ran 7 jts (311.10') 8-5/8" 24.0# J-55 ST&C cond "A" Newport csg. Set csg @ 311' (GLM). RU Big 4 Cementers. Pumped 20 bbls FW followed w/ 20 bbls 8.5 gelled wtr. Cmt w/ 180 sx (36.9 bbls) Premium cmt containing 2.0% CaCl₂ & 0.25% flocele. Wt: 15.8 ppg. Yield: 1.15 ft³/sk. MWR: 5.0 gps. Displ cmt w/ 16.5 bbls FW. Full circ through out the job. Circ 7.0 bbls (34.2 sx) cmt to surf. CIP @ 19:30 hrs. (MST) 11/26/04. RDMO Big 4 Cementers & Craig's Rathole Drilling. Spud @ 08:30 hrs (MST) 11/26/04.

12/02/04 Days since spud: 2

Total Depth: 339'

24 hr. footage: 9'

Present Operation: Rig Repair

MW:

Surveys:

Current Activity: 12 hrs-MIRU Union Rig #14. Called State of Utah (Carol Daniels). Called BLM (Ed Forsman). Told them we would be tstg @ 18:00 hrs on 12/01/04. 3 hrs-Tst pipe & blind rams, upper kelly valve, kill line, chk, manifold & annular preventer to 2000 psi for 10 min. Tst 8-5/8" 24# J-55 ST&C csg to 1500 psi for 30 min. 2-1/2 hrs-Mud pump & mud lines froze. Hook up steam lines to thaw out pump. 1-1/2 hrs-PU straight dnhole motor & make up bit. RIH w/ DCs. Tag cmt @ 290'. 1/2 hr-Chain BOPE in place. 3 hrs-RU kelly to tst BHA. Standpipe froze. Hook up steam lines to thaw standpipe & valves. 1/2 hr-Tag cmt @ 290'. Drl shoe @ 320' KB. 1/2 hr-Drl 7-7/8" hole f/ 321-339'. 1/2 hr-Work on mud lines. Drld out f/under surf @ 05:00 hrs (MST) 12/2/04.

12/03/04 Days since spud: 3

Total Depth: 1387'

24 hr. footage: 1048'

Present Operation: Drlg @ 1387'

MW: 8.3; Vis: 27; pH: 10.5; Chl: 3100; Calc: 100; % Solids: 0.1; Pf/Mf: .7/1.4

Surveys: 1.34° @ 358', 1.97° @ 748', 2.84° @ 1191', 2.40° @ 1286'

Current Activity: 2-1/2 hrs-Drl 7-7/8" hole f/ 339-428'. 1/2 hr-WLS @ 358'. 1/2 hr-Rig service. 1/2 hr-Drl f/ 428-457' w/ 18-20k wob. 2-1/2 hrs-Work on mud pump fuel system & rod oilers. 5-1/2 hrs-Drl f/ 457-818' w/ 18-20k wob. 1/2 hr-WLS @ 748'. 7-1/2 hrs-Drl f/ 818-1261' w/ 15k wob. 1/2 hr-WLS @ 1191'. 2-1/2 hrs-Drl f/ 1261-1356' w/ 10-12k wob. 1/2 hr-WLS @ 1286'. 1/2 hr-Drl f/ 1356-1387' w/ 10-12k wob.

12/04/04 Days since spud: 4

Total Depth: 2527'

24 hr. footage: 1140'

Present Operation: Drlg @ 2527'

MW: 8.3; Vis: 27; pH: 11.3; Chl: 3900; Calc: 220; % Solids: 0.1; Pf/Mf: 1.2/1.7

Surveys: 2.35° @ 1634', 1.56° @ 2013', 2.06° @ 2393'

Current Activity: 6 hrs-Drl 7-7/8" hole f/ 1387-1704'. 1/2 hr-WLS @ 1634'. 2 hrs-Drl f/ 1704-1798' w/ 10-12k wob.

RECEIVED
DEC 27 2004

DIV. OF OIL, GAS & MINING

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

10-12k wob. 1/2 hr-Rig service. Change rotating head rubber. 6 hrs-Drl f/ 1798-2083' w/ 10-12k wob. Started losing returns @ 2030'. Mix gel / sawdust & sweep hole. 1/2 hr-WLS @ 2013'. 7 hrs-Drl f/ 2083-2463' w/ 22-24k wob. Cont to mix sweeps, lost approx 1500 bbls. 1/2 hr-WLS @ 2393'. 1 hr-Drl f/ 2463-2527' w/ 22-24k wob. No volume loss in last hr.

12/05/04 Days since spud: 5

Total Depth: 3552'

24 hr. footage: 1026'

Present Operation: Drlg @ 3552'

MW: 8.3; **Vis:** 27; **pH:** 11.2; **Chl:** 4000; **Calc:** 210; **% Solids:** 0.1; **Pf/Mf:** 1.1/1.6

Surveys: 2.84° @ 2805', 2.31° @ 3217'

Current Activity: 6 hrs-Drl 7-7/8" hole f/ 2527-2875' w/ 25k wob. 1/2 hr-WLS @ 2805'. Rig service. 6 hrs-Drl f/ 2875-3129' w/ 18-20k wob. 1/2 hr-@ 3129' lost complete returns. Circ & mix LCM. 4 hrs-Drl f/ 3129-3287' w/ 20-22k wob. Cont to mix LCM & sweep hole. 1/2 hr-WLS @ 3217'. 6-1/2 hrs-Drl f/ 3287-3552' w/ 22-28k wob. Cont to mix LCM, lost approx 2000 bbls. Have mud system closed in until get circ under control.

12/06/04 Days since spud: 6

Total Depth: 4108'

24 hr. footage: 556'

Present Operation: Lost returns, mix LCM & bld volume

MW: 8.5; **Vis:** 32; **pH:** 10; **Chl:** 3700; **Calc:** 100; **% Solids:** 1.1; **Pf/Mf:** .6/1.1

Surveys: 2.60° @ 3628'

Current Activity: 1-1/2 hrs-Drl 7-7/8" hole f/ 3552-3607' w/ 25k wob. 1 hr-Lost all returns @ 3607'. Mix LCM & bld vol. 1/2 hr-Repair rotary table drive line. 3 hrs-Drl f/ 3607-3698' w/ 30k wob. MW: 8.4; Vis: 32. No vol loss. 1/2 hr-WLS @ 3628'. 15 hrs-Drl f/ 3698-4108' w/ 32-34k wob. MW: 8.5; Vis: 34. 1/2 hr-Lost all returns @ 4106'. Mix LCM & bld vol. 1/2 hr-Full circ, bld vol, work string up & dn. Lost returns. 1-1/2 hrs-No returns. Mix LCM & bld vol.

12/07/04 Days since spud: 7

Total Depth: 4614'

24 hr. footage: 506'

Present Operation: Drlg @ 4614'

MW: 8.7; **Vis:** 39; **pH:** 9.7; **Chl:** 2000; **Calc:** 90; **% Solids:** 1.9; **Pf/Mf:** .15/.5

Surveys: 2.82° @ 4101'

Current Activity: 1 hr-No returns. Mix LCM & bld vol. 1/2 hr-Full circ. Pump LCM pill & prep to trip pipe. 1-1/2 hrs-POOH for bit #2. 1/2 hr-Circ & pump LCM sweep @ 2400'. 1-1/2 hrs-Cont POOH for bit #2. SLM-no correction made. 1/2 hr-Change out bit & rig service. 2-1/2 hrs-TIH. 1/2 hr-Kelly up & wash 40' to btm-4' fill. 2 hrs-Drl f/ 4108-4171'. 1/2 hr-WLS @ 4101'. 13 hrs-Drl f/ 4171'-4614'. No vol loss.

12/08/04 Days since spud: 8

Total Depth: 5279'

24 hr. footage: 765'

Present Operation: Drlg @ 5279'

MW: 8.8; **Vis:** 35; **pH:** 9.0; **Chl:** 900; **Calc:** 50; **% Solids:** 3.0; **Pf/Mf:** .1/.4

Surveys: 2.93° @ 4513', 2.59° @ 5019'

Current Activity: 1/2 hr-WLS @ 4513'. 7-1/2 hrs-Drl f/ 4614-4835' w/ 35k wob. 1/2 hr-Rig service. 8 hrs-Drl f/ 4835-5089' w/ 35k wob. 1/2 hr-WLS @ 5019'. 7 hrs-Drl f/ 5089-5279' w/ 40k wob.

RECEIVED
DEC 27 2004
DIV. OF OIL, GAS & MINING

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

12/09/04 Days since spud: 9

Total Depth: 5660'

24 hr. footage: 381'

Present Operation: Drlg @ 5660'

MW: 8.7; Vis: 37; pH: 9.3; Chl: 600; Calc: 60; % Solids: 3.0; Pf/Mf: .1/.5

Surveys: 2.25° @ 5494'

Current Activity: 5-1/2 hrs-Drl f/ 5279-5455' w/ 8.7 MW; 34 Vis. 1 hr-Lost returns. Mix LCM sweeps. 4-1/2 hrs-Drl f/ 5455-5564'. 1 hr-Lost returns. Mix LCM sweeps. 1-1/2 hrs-TOH to 4100'. 1/2 hr-Pump LCM sweep. 1-1/2 hrs-Bld vol in mud tanks. Rotate string w/o pump. 1 hr-TIH to 4900'. 1/2 hr-Full returns, Mix LCM & sweep hole. 1 hr-Fin TIH. 1 hr-Drl f/ 5564-5598'. 1 hr-WLS @ 5494'. Rig service. 1 hr-Drl g/ 5598-5621' w/ 8.8 MW; 35 Vis. 2 hrs-Lost 8" in mud tanks. Bld vol back & hold 8.7 MW; 38 Vis. 1 hr-Drl f/ 5621-5660' 8.8 MW; 37 Vis; 114 Pump strokes. No fluid loss.

12/10/04 Days since spud: 10

Total Depth: 6204'

24 hr. footage: 544'

Present Operation: Drlg @ 6204'

MW: 8.7; Vis: 40; pH: 9.2; Chl: 600; Calc: 60; % Solids: 4.0; Pf/Mf: .1/.5

Surveys: 3.15° @ 6000'

Current Activity: 4-1/2 hrs-Drl f/ 5660-5785' w. 8.8 MW; 43 Vis. 1/2 hr-Rig service. 11 hrs-Drl f/ 5785-6070' w/ 8.7 MW; 41 Vis. Lost 100 bbls drlg mud while drlg in last 11 hrs. Mix LCM sweep while drlg. 1/2 hr-WLS @ 6000'. 7-1/2 hrs-Drl f/ 6070-6204' w/ 8.7 MW; 40 Vis. No fluid loss in last 8 hrs.

12/11/04 Days since spud: 11

Total Depth: 6292'

24 hr. footage: 88'

Present Operation: Circ & cond hole

MW: 8.8; Vis: 41; pH: 8.9; Chl: 400; Calc: 80; % Solids: 3.0; Pf/Mf: .05/.5

Surveys:

Current Activity: 5 hrs-Drl 7-7/8" hole f/ 6204-6292' TD. 1 hr-Circ & cond hole. 1-1/2 hrs-POOH wet pipe. 1/2 hr-Mix & pump dry job. 2 hrs-POOH wet pipe, bit or motor plugged. 1/2 hr-Work on cellar pump. 2-1/2 hrs-POOH. 1 hr-LD bit & motor. HSM & RU Halliburton loggers. 3-1/2 hrs-Run Halliburton triple combo log. LTD: 6277'. 1 hr-LD loggers. TIH w/ DCs. 1-1/2 hrs-WOO. 3-1/2 hrs-TIH. No tight spots. Had 2' of fill. 1/2 hr-Circ & cond hole.

12/12/04 Days since spud: 12

Total Depth: 6277'

24 hr. footage: 0

Present Operation: Rlse Rig

MW:

Surveys:

Current Activity: 1-1/2 hrs-Bld vol & pump sweep. 1 hr-Repair hydraulic line & air leak. 1/2 hr-HSM & RU Caliper LD machine. 4-1/2 hrs-LD 4-1/2" DP & 6" DCs. 1/2 hr-Change out 4-1/2" pipe rams for 5-1/2" & tst. 1/2 hr-RU Caliper csg tongs. HSM. Prepare floor for running 5-1/2" csg. 5 hrs-Run 146 jts. (6271.46') 5-1/2" 15.5# J-55 LT&C cond. "A" Newport csg. Make up circ head & wash dn & land 5-1/2" csg. Set @ 6281' KBM. FC @ 6236'. Marker jt f/ 4211.71-4201.11'. 1 hr-RD csg tongs. Circ. WO Halliburton cementers. RU cementers. HSM w/ Halliburton cementers & drlg crew. Tst lines to 3000 psi for 5 min. 2 hrs-Cmt 5-1/2" 15.5# csg. Lead slurry: Pumped 10 bbls oil based surfactant wtr @ 8.34 ppg

RECEIVED
DEC 27 2004

DIV. OF OIL, GAS & MINING

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673

SENE Sec 31 T-5S,R-5W

Brundage Canyon Field

Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:

Spud Date: November 26, 2004

Gr Elev: 7823' KB: 7833'

Drlg Contractor: Union Drilling Company Rig #14

& 20 bbls Super flush @ 9.20 ppg followed w/ 10 bbl FW spacer 8.34 ppg. Cmt'd w/ 250 sx (191 bbls) standard CBM lite. Wt: 10.5 ppg. Yield: 4.29 ft³/sk. MWR: 27.97 gps. 25% excess. Tail slurry: Pumped 430 sx (134 bbls) Halliburton light prem plus cmt containing 3% KCl, 1% econolite, 0.6% Halad-322 & 0.2% HR-5. Wt: 13.0 ppg. Yield: 1.75 ft³/sk. MWR: 9.05 gps. 25% excess. Drop plug. Displ w/ 149 bbls 2% KCl wtr. Bump plug @ 1560 psi (1000 over). Pump cmt & displ csg @ 6-8 bpm. Bump plug @ 1/2 bpm. Final circ psi was 560 psi. Float held. Lost circ. No cmt returns to surf. Reciprocate pipe 15' while circ & cmtg. CIP @ 22:00 hrs (MST) 12/11/04. 1 hr-ND BOP. Set slips. 2 hrs-RD. Clean mud pits. 19-1/2 hrs-Rlse Union #14 @ 01:30 hrs (MST) 12/12/04

RECEIVED
DEC 27 2004
DIV. OF OIL, GAS & MINING

FIML NATURAL RESOURCES, LLC

April 12, 2005

014

Bureau of Land Management
Vernal Field Office
170 South 500 East
Vernal, UT 84078

43.03.32673
Re: Ute Tribal #8-31-55
SENE Sec 31 T-5S R-5W
Undesignated Field
Duchesne County, Utah

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

Dear Sir or Madam:

Enclosed is the following information concerning the referenced well.

Site Security Diagram

If any questions arise or additional information is required, please contact me at 303-893-5081.

Sincerely,



Rick L. Parks
Operations Manager

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

/ps
Enclosures:

RECEIVED

APR 15 2005


DIV. OF OIL, GAS & MINING



NORTH



SLOPE



1. Sales by tank gauge – to tank truck

2. Seal Requirements:

a. Production Phase

1. Valves 1 – 5 Open
2. Valves 6 – 10 Closed, Sealed
3. Valves 11 & 12 Open

b. Sales Phase

1. Valves 1 – 5 & 9 - 10 Closed
2. Valves 6 or 7 & 8 Open
3. Valves 11 & 12 Open

Site Security Diagram



MERIDIAN
ENVIRONMENTAL • LLC

UTE TRIBAL NO. 8-31-55
SENE SEC 30, T5S, R5W
DUCHESNE COUNTY, UTAH
LEASE NO. 14-20-H62-5036

FIML NATURAL RESOURCES, LLC
410 17TH STREET, SUITE 570
DENVER, CO 80202
303.893.5081

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

015

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well ☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator **FIML Natural Resources, LLC**

3a. Address **410 17th Street, Suite 570 Denver, CO 80202**

3b. Phone No. (include area code) **303-893-5081**

CONFIDENTIAL

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.
14-20-H62-5060

6. If Indian, Allottee or Tribe Name
Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
Ute Tribal # 8-31-55

9. API Well No.
43-013-32673

10. Field and Pool, or Exploratory Area
Undesignated

11. County or Parish, State
Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Requesting Approval
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	for an Electronic
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	Flow Meter

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

FIML Natural Resources, LLC requests the use of a Ferguson Beauregard electronic flow meter for gas measurement on this well. Please refer to the electronic flow meter paperwork which was submitted an

RECEIVED

APR 15 2005

DIV. OF OIL, GAS & MINING

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) **Rick L. Parks** Title **Operations Manager**

Signature *[Signature]* Date **4/12/05**

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by _____ Title **Utah Division of Oil, Gas and Mining** Date _____ Federal Approval Of This Action Is Necessary

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

COPY SENT TO OPERATOR
DATE: **04-22-05**
NAME: **CHD**

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

016

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator **FIML Natural Resources, LLC**

3a. Address
410 17th Street, Suite 570 Denver, CO 80202

3b. Phone No. (include area code)
303-893-5081

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Produced water from teh Ute Tribal 8-31-55 will be hauled to R.N. Industries Bluebell facility located in Section 4, T-02S, R-02W, Duchesne County, Utah.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

RECEIVED

APR 15 2005

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93


DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Rick L. Parks

Title **Operations Manager**

Signature



Date

4/12/05

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

017

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator **FIML Natural Resources, LLC**

3a. Address
410 17th Street, Suite 570 Denver, CO 80202

3b. Phone No. (include area code)
303-893-5081

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- | | | | |
|---|---|---|---|
| <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input checked="" type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input type="checkbox"/> Other |
| <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug and Abandon | <input type="checkbox"/> Temporarily Abandon | |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The Ute Tribal #8-31-55 began producing on April 9, 2005.

RECEIVED

APR 15 2005

DIV. OF OIL, GAS & MINING

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Rick L. Parks

Title **Operations Manager**

Signature

Date

4/12/05

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

FIML NATURAL RESOURCES, LLC

April 12, 2005

CONFIDENTIAL

Bureau of Land Management
Vernal Field Office
170 South 500 East
Vernal, UT 84078

Re: Ute Tribal #8-31-55
SENE Sec 31 T-5S R-5W
Undesignated Field
Duchesne County, Utah

Dear Sir or Madam:

Enclosed is the following information concerning the referenced well.

Notice of Start of Production
Notice of Request for Approval for an Electronic Flow Meter
Notice of Water Disposal

If any questions arise or additional information is required, please contact me at 303-893-5081.

Sincerely,



Rick L. Parks
Operations Manager

RECEIVED

APR 15 2005

DIV. OF OIL, GAS & MINING

/cp
Enclosures:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

018

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator
FIML Natural Resources, LLC

3a. Address
410 17th Street, Suite 570 Denver, CO 80202

3b. Phone No. (include area code)
303-893-5081

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Requesting Approval
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	for an Electronic
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	Flow Meter

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

FIML Natural Resources, LLC requests the use of a Ferguson Beauregard electronic flow meter for gas measurement on this well. Please refer to the electronic flow meter paperwork which was submitted an

COPIES TO OPERATOR
4-25-05
CHD

RECEIVED

APR 22 2005

DIV. OF OIL, GAS & MINING

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Rick L. Parks

Title Operations Manager

Signature

Date

4/12/05

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title Accepted by the
Utah Division of
Oil, Gas and Mining
Date 4/12/05

Federal Approval Of This
Action Is Necessary

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

By:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

019

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator **FIML Natural Resources, LLC**3a. Address
410 17th Street, Suite 570 Denver, CO 802023b. Phone No. (include area code)
303-893-5081

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Produced water from teh Ute Tribal 8-31-55 will be hauled to R.N. Industries Bluebell facility located in Section 4, T-02S, R-02W, Duchesne County, Utah.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

RECEIVED

APR 22 2005

DIV. OF OIL, GAS & MINING

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Rick L. ParksTitle **Operations Manager**

Signature

Date

4/12/05**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

FIML NATURAL RESOURCES, LLC

WELL HISTORY

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

09/10/04 **Current Activity:** Location access and pipeline route approved during onsite.

09/11-30/04 **Current Activity:** WO APD Approval

10/01-31/04 **Current Activity:** WO APD Approval

11/01-21/04 **Current Activity:** WO APD Approval

11/22/04 **Present Operation:** WORT

Current Activity: Received approved APD. Craig's Roustabout Service fin bldg loc, 100% completed.

11/23-24/04 **Current Activity:** WORT

11/25/04 **Current Activity:** WORT

11/26/04 Days since spud: 1

Total Depth: 330'

24 hr. footage: 330'

Present Operation: WORT

MW:

Surveys:

Current Activity: 14 hrs-MIRU Craig's rathole machine. Drld mouse hole & rat hole. Drld 16" hole to 10' (GLM). Set 14" conductor csg @ 6' (GLM). Drld 12-1/4" hole f/ 10' to 330' (GLM). Ran 7 jts (311.10') 8-5/8" 24.0# J-55 ST&C cond "A" Newport csg. Set csg @ 311' (GLM). RU Big 4 Cementers. Pumped 20 bbls FW followed w/ 20 bbls 8.5 gelled wtr. Cmt d w/ 180 sx (36.9 bbls) Premium cmt containing 2.0% CaCl₂ & 0.25% flocele. Wt: 15.8 ppg. Yield: 1.15 ft³/sk. MWR: 5.0 gps. Displ cmt w/ 16.5 bbls FW. Full circ through out the job. Circ 7.0 bbls (34.2 sx) cmt to surf. CIP @ 19:30 hrs. (MST) 11/26/04. RDMO Big 4 Cementers & Craig's Rathole Drilling. Spud @ 08:30 hrs (MST) 11/26/04.

Est. DC - \$41,897

Est. CC - \$41,897

11/27-30/04 **Current Activity:** WORT

12/01/04 **Current Activity:** WORT

12/02/04 Days since spud: 2

Total Depth: 339'

24 hr. footage: 9'

Present Operation: Rig Repair

MW:

Surveys:

Current Activity: 12 hrs-MIRU Union Rig #14. Called State of Utah (Carol Daniels). Called BLM (Ed Forsman). Told them we would be tstg @ 18:00 hrs on 12/01/04. 3 hrs-Tst pipe & blind rams, upper kelly valve, kill line, chk, manifold & annular preventer to 2000 psi for 10 min. Tst 8-5/8" 24# J-55 ST&C csg to 1500 psi for 30 min. 2-1/2 hrs-Mud pump & mud lines froze. Hook up steam lines to thaw out pump.

CONFIDENTIAL

RECEIVED

MAY 23 2005

DIV. OF OIL, GAS & MINING

FIML NATURAL RESOURCES, LLC

WELL HISTORY

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

1-1/2 hrs-PU straight dnhole motor & make up bit. RIH w/ DCs. Tag cmt @ 290'. 1/2 hr-Chain BOPE in place. 3 hrs-RU kelly to tst BHA. Standpipe froze. Hook up steam lines to thaw standpipe & valves. 1/2 hr-Tag cmt @ 290'. Drl shoe @ 320' KB. 1/2 hr-Drl 7-7/8" hole f/ 321-339'. 1/2 hr-Work on mud lines. Drld out f/under surf @ 05:00 hrs (MST) 12/2/04.

2 men short on rig up

CONFIDENTIAL

Est. DC - \$24,764

Est. CC - \$66,661

12/03/04 Days since spud: 3

Total Depth: 1387'

24 hr. footage: 1048'

Present Operation: Drlg @ 1387'

MW: 8.3; **Vis:** 27; **pH:** 10.5; **Chl:** 3100; **Calc:** 100; **% Solids:** 0.1; **Pf/Mf:** .7/1.4

Surveys: 1.34° @ 358', 1.97° @ 748', 2.84° @ 1191', 2.40° @ 1286'

Current Activity: 2-1/2 hrs-Drl 7-7/8" hole f/ 339-428'. 1/2 hr-WLS @ 358'. 1/2 hr-Rig service. 1/2 hr-Drl f/ 428-457' w/ 18-20k wob. 2-1/2 hrs-Work on mud pump fuel system & rod oilers. 5-1/2 hrs-Drl f/ 457-818' w/ 18-20k wob. 1/2 hr-WLS @ 748'. 7-1/2 hrs-Drl f/ 818-1261' w/ 15k wob. 1/2 hr-WLS @ 1191'. 2-1/2 hrs-Drl f/ 1261-1356' w/ 10-12k wob. 1/2 hr-WLS @ 1286'. 1/2 hr-Drl f/ 1356-1387' w/ 10-12k wob.

HSM. Full crews. No accidents

Est. DC - \$22,927

Est. CC - \$89,588

12/04/04 Days since spud: 4

Total Depth: 2527'

24 hr. footage: 1140'

Present Operation: Drlg @ 2527'

MW: 8.3; **Vis:** 27; **pH:** 11.3; **Chl:** 3900; **Calc:** 220; **% Solids:** 0.1; **Pf/Mf:** 1.2/1.7

Surveys: 2.35° @ 1634', 1.56° @ 2013', 2.06° @ 2393'

Current Activity: 6 hrs-Drl 7-7/8" hole f/ 1387-1704'. 1/2 hr-WLS @ 1634'. 2 hrs-Drl f/ 1704-1798' w/ 10-12k wob. 1/2 hr-Rig service. Change rotating head rubber. 6 hrs-Drl f/ 1798-2083' w/ 10-12k wob. Started losing returns @ 2030'. Mix gel / sawdust & sweep hole. 1/2 hr-WLS @ 2013'. 7 hrs-Drl f/ 2083-2463' w/ 22-24k wob. Cont to mix sweeps, lost approx 1500 bbls. 1/2 hr-WLS @ 2393'. 1 hr-Drl f/ 2463-2527' w/ 22-24k wob. No volume loss in last hr.

HSM. Full crews. No accidents

Maximum: 0 units; Background: 2-4 units; Connection: 0-10 units; Survey 0 units; Dntime: 0 units; Trip: 0 units.

Est. DC - \$37,220

Est. CC - \$126,808

12/05/04 Days since spud: 5

Total Depth: 3552'

24 hr. footage: 1026'

Present Operation: Drlg @ 3552'

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

MW: 8.3; Vis: 27; pH: 11.2; Chl: 4000; Calc: 210; % Solids: 0.1; Pf/Mf: 1.1/1.6

Surveys: 2.84° @ 2805', 2.31° @ 3217'

Current Activity: 6 hrs-Drl 7-7/8" hole f/ 2527-2875' w/ 25k wob. 1/2 hr-WLS @ 2805'. Rig service. 6 hrs-Drl f/ 2875-3129' w/ 18-20k wob. 1/2 hr-@ 3129' lost complete returns. Circ & mix LCM. 4 hrs-Drl f/ 3129-3287' w/ 20-22k wob. Cont to mix LCM & sweep hole. 1/2 hr-WLS @ 3217'. 6-1/2 hrs-Drl f/ 3287-3552' w/ 22-28k wob. Cont to mix LCM, lost approx 2000 bbls. Have mud system closed in until get circ under control.

HSM. Full crews. No accidents

Maximum: 0 units; Background: 2-4 units; Connection: 8-10 units; Survey 0 units; Dntime: 0 units; Trip: 0 units.

Est. DC - \$18,708

Est. CC - \$145,516

12/06/04 Days since spud: 6

Total Depth: 4108'

24 hr. footage: 556'

Present Operation: Lost returns, mix LCM & bld volume

MW: 8.5; Vis: 32; pH: 10; Chl: 3700; Calc: 100; % Solids: 1.1; Pf/Mf: .6/1.1

Surveys: 2.60° @ 3628'

Current Activity: 1-1/2 hrs-Drl 7-7/8" hole f/ 3552-3607' w/ 25k wob. 1 hr-Lost all returns @ 3607'. Mix LCM & bld vol. 1/2 hr-Repair rotary table drive line. 3 hrs-Drl f/ 3607-3698' w/ 30k wob. MW: 8.4; Vis: 32. No vol loss. 1/2 hr-WLS @ 3628'. 15 hrs-Drl f/ 3698-4108' w/ 32-34k wob. MW: 8.5; Vis: 34. 1/2 hr-Lost all returns @ 4106'. Mix LCM & bld vol. 1/2 hr-Full circ, bld vol, work string up & dn. Lost returns. 1-1/2 hrs-No returns. Mix LCM & bld vol.

HSM. Full crews. No accidents

Maximum: 0 units; Background: 2-4 units; Connection: 0-10 units; Survey 0 units; Dntime: 0 units; Trip: 0 units.

Est. DC - \$23,726

Est. CC - \$169,242

12/07/04 Days since spud: 7

Total Depth: 4614'

24 hr. footage: 506'

Present Operation: Drlg @ 4614'

MW: 8.7; Vis: 39; pH: 9.7; Chl: 2000; Calc: 90; % Solids: 1.9; Pf/Mf: .15/.5

Surveys: 2.82° @ 4101'

Current Activity: 1 hr-No returns. Mix LCM & bld vol. 1/2 hr-Full circ. Pump LCM pill & prep to trip pipe. 1-1/2 hrs-POOH for bit #2. 1/2 hr-Circ & pump LCM sweep @ 2400'. 1-1/2 hrs-Cont POOH for bit #2. SLM-no correction made. 1/2 hr-Change out bit & rig service. 2-1/2 hrs-TIH. 1/2 hr-Kelly up & wash 40' to btm-4' fill. 2 hrs-Drl f/ 4108-4171'. 1/2 hr-WLS @ 4101'. 13 hrs-Drl f/ 4171'-4614'. No vol loss.

HSM. Full crews. No accidents

Maximum: 0 units; Background: 2-4 units; Connection: 8-10 units; Survey 0 units; Dntime: 0 units; Trip: 40 units.

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

Est. DC - \$27,920

Est. CC - \$197,162

12/08/04 Days since spud: 8

Total Depth: 5279'

24 hr. footage: 765'

Present Operation: Drlg @ 5279'

MW: 8.8; Vis: 35; pH: 9.0; Chl: 900; Calc: 50; % Solids: 3.0; Pf/Mf: .1/.4

Surveys: 2.93° @ 4513', 2.59° @ 5019'

Current Activity: 1/2 hr-WLS @ 4513'. 7-1/2 hrs-Drl f/ 4614-4835' w/ 35k wob. 1/2 hr-Rig service. 8 hrs-Drl f/ 4835-5089' w/ 35k wob. 1/2 hr-WLS @ 5019'. 7 hrs-Drl f/5089-5279' w/ 40k wob.

HSM. Full crews. No accidents

Maximum: 0 units; Background: 2-4 units; Connection: 0-10 units; Survey 6-10 units; Dntime: 0 units;
Trip: 0 units.

Est. DC - \$22,423

Est. CC - \$219,585

12/09/04 Days since spud: 9

Total Depth: 5660'

24 hr. footage: 381'

Present Operation: Drlg @ 5660'

MW: 8.7; Vis: 37; pH: 9.3; Chl: 600; Calc: 60; % Solids: 3.0; Pf/Mf: .1/.5

Surveys: 2.25° @ 5494'

Current Activity: 5-1/2 hrs-Drl f/ 5279-5455' w/ 8.7 MW; 34 Vis. 1 hr-Lost returns. Mix LCM sweeps. 4-1/2 hrs-Drl f/ 5455-5564'. 1 hr-Lost returns. Mix LCM sweeps. 1-1/2 hrs-TOH to 4100'. 1/2 hr-Pump LCM sweep. 1-1/2 hrs-Bld vol in mud tanks. Rotate string w/o pump. 1 hr-TIH to 4900'. 1/2 hr-Full returns, Mix LCM & sweep hole. 1 hr-Fin TIH. 1 hr-Drl f/ 5564-5598'. 1 hr-WLS @ 5494'. Rig service. 1 hr-Drl g/ 5598-5621' w/ 8.8 MW; 35 Vis. 2 hrs-Lost 8" in mud tanks. Bld vol back & hold 8.7 MW; 38 Vis. 1 hr-Drl f/ 5621-5660' 8.8 MW; 37 Vis; 114 Pump strokes. No fluid loss.

HSM. Full crews. No accidents

Show	Before	During	After
5278-5288'	4 units	40-70 units	8 units

Maximum: 440 units; Background: 4-6 units; Connection: 440 units; Survey 0 units; Dntime: 0 units;
Trip: 28 units.

Est. DC - \$21,820

Est. CC - \$241,405

12/10/04 Days since spud: 10

Total Depth: 6204'

24 hr. footage: 544'

Present Operation: Drlg @ 6204'

MW: 8.7; Vis: 40; pH: 9.2; Chl: 600; Calc: 60; % Solids: 4.0; Pf/Mf: .1/.5

Surveys: 3.15° @ 6000'

Current Activity: 4-1/2 hrs-Drl f/ 5660-5785' w. 8.8 MW; 43 Vis. 1/2 hr-Rig service. 11 hrs-Drl f/ 5785-6070' w/ 8.7 MW; 41 Vis. Lost 100 bbls drlg mud while drlg in last 11 hrs. Mix LCM sweep while drlg. 1/2 hr-WLS @ 6000'. 7-1/2 hrs-Drl f/ 6070-6204' w/ 8.7 MW; 40 Vis. No fluid loss in last 8 hrs.

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

HSM. Full crews. No accidents

Maximum: 0 units; Background: 4-6 units; Connection: 8-10 units; Survey 0 units; Dntime: 0 units;
Trip: 0 units.

Est. DC - \$19,222

Est. CC - \$260,627

12/11/04 Days since spud: 11

Total Depth: 6292'

24 hr. footage: 88'

Present Operation: Circ & cond hole

MW: 8.8; Vis: 41; pH: 8.9; Chl: 400; Calc: 80; % Solids: 3.0; Pf/Mf: .05/.5

Surveys:

Current Activity: 5 hrs-Drl 7-7/8" hole f/ 6204-6292' TD. 1 hr-Circ & cond hole. 1-1/2 hrs-POOH wet pipe. 1/2 hr-Mix & pump dry job. 2 hrs-POOH wet pipe, bit or motor plugged. 1/2 hr-Work on cellar pump. 2-1/2 hrs-POOH. 1 hr-LD bit & motor. HSM & RU Halliburton loggers. 3-1/2 hrs-Run Halliburton triple combo log. LTD: 6277'. 1 hr-LD loggers. TIH w/ DCs. 1-1/2 hrs-WOO. 3-1/2 hrs-TIH. No tight spots. Had 2' of fill. 1/2 hr-Circ & cond hole.

HSM. Full crews. No accidents

Maximum: 0 units; Background: 0 units; Connection: 0 units; Survey 0 units; Dntime: 0 units;
Trip: 0 units.

Est. DC - \$31,929

Est. CC - \$292,556

12/12/04 Days since spud: 12

Total Depth: 6277'

24 hr. footage: 0

Present Operation: Rlse Rig

MW:

Surveys:

Current Activity: 1-1/2 hrs-Bld vol & pump sweep. 1 hr-Repair hydraulic line & air leak. 1/2 hr-HSM & RU Caliper LD machine. 4-1/2 hrs-LD 4-1/2" DP & 6" DCs. 1/2 hr-Change out 4-1/2" pipe rams for 5-1/2" & tst. 1/2 hr-RU Caliper csg tongs. HSM. Prepare floor for running 5-1/2" csg. 5 hrs-Run 146 jts. (6271.46') 5-1/2" 15.5# J-55 LT&C cond. "A" Newport csg. Make up circ head & wash dn & land 5-1/2" csg. Set @ 6281' KBM. FC @ 6236'. Marker jt f/ 4211.71-4201.11'. 1 hr-RD csg tongs. Circ. WO Halliburton cementers. RU cementers. HSM w/ Halliburton cementers & drlg crew. Tst lines to 3000 psi for 5 min. 2 hrs-Cmt 5-1/2" 15.5# csg. Lead slurry: Pumped 10 bbls oil based surfactant wtr @ 8.34 ppg & 20 bbls Super flush @ 9.20 ppg followed w/ 10 bbl FW spacer 8.34 ppg. Cmt w/ 250 sx (191 bbls) standard CBM lite. Wt: 10.5 ppg. Yield: 4.29 ft³/sk. MWR: 27.97 gps. 25% excess. Tail slurry: Pumped 430 sx (134 bbls) Halliburton light prem plus cmt containing 3% KCl, 1% econolite, 0.6% Halad-322 & 0.2% HR-5. Wt: 13.0 ppg. Yield: 1.75 ft³/sk. MWR: 9.05 gps. 25% excess. Drop plug. Displ w/ 149 bbls 2% KCl wtr. Bump plug @ 1560 psi (1000 over). Pump cmt & displ csg @ 6-8 bpm. Bump plug @ 1/2 bpm. Final circ psi was 560 psi. Float held. Lost circ. No cmt returns to surf. Reciprocate pipe 15' while circ & cmtg. CIP @ 22:00 hrs (MST) 12/11/04. 1 hr-ND BOP. Set slips. 2 hrs-RD. Clean mud pits. 19-1/2 hrs-Rlse Union #14 @ 01:30 hrs (MST) 12/12/04

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBDT:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

Est. DC - \$127,819

Est. CC - \$420,375

12/13-31/04 **Current Activity:** Waiting on Completion

01/01-28/05 **Current Activity:** Waiting on Completion

01/29/05 **Present Operation:** Waiting on Frac

Current Activity: MI 11 500 bbl frac tanks. Started filling w/ 3% KCL wtr. Installed reconditioned Wellhead, Inc. 7-1/16" x 5000 psi frac valve & spool. RU Halliburton WL. Run CBL/GR log f/ 6217' (PBDT) to 3500'. Found TOC @ 3450'. Very good cmt bonding except for partial bonding 5420'–5520'. Found short jt @ 4195' to 4206'. RU B & C Quick Test. Tst 5-1/2" csg to 3800 psi. Held good. Perf Wasatch Zn #1 w/ 4" HSC perf gun w/ 120° phased, 22.7 gram charges, .40" EHD & 37.5" TTP as follows:

5940–5944' (4') 8 holes

5928–5932' (4') 8 holes

RD Halliburton. SI well.

Est. DC - \$7512

Est. CC - \$427,887

01/30-31/05 **Current Activity:** Waiting on Frac

02/01/05 **Current Activity:** Waiting on Frac

02/02/05 **Present Operation:** WO completion rig to DO frac plug

Current Activity: Fin filling 9 500 bbl frac tanks w/ 3% KCL wtr. Heated tanks to 110° F (85° @ pump time). MIRU Halliburton frac equip, WL unit & crane. HSM. Press tst lines to 5000 psi. Start @ 8:32 a.m. Frac Zn #1 (Wasatch) perfs 5928' to 5944' via 5-1/2" csg. w/ following:

55 gal Inhibitor; 250 gal 7-1/2% HCL spearhead acid; 1565 gal 3.0% treated spacer; 8015 gal Delta 140 20# pad; 3502 gal Delta 140 20# sd laden fluid w/ 2.0 ppg 16/30 mesh sd; 3507 gal Delta 140 20# sd laden fluid w/ 4.0 ppg 16/30 mesh sd; 3605 gal Delta 140 20# sd laden fluid w/ 5.0 ppg 16/30 mesh sd; 3508 gal Delta 140 20# sd laden fluid w/ 6.0 ppg 16/30 mesh sd; 250 gal 7-1/2% HCL; 5926 gal 3.0% KCL treated flush

Formation broke @ 2760 psi @ 4.7 BPM. Avg rate: 35.0 BPM. Avg press: 1350 psi. Max press: 3011 psi. HHP used: 1158. ISDP: 810 psi. Frac gradient: .58 psi/ft. TLTR: 705.4 bbl. Total sd. pumped: 60,000 lbs 16/30 mesh Brady sd. Set Halliburton 4.370" OD x 28" long x 5000 psi flow-through composite frac plug #1 @ 5900'. Press tsted plug & did not hold. Tried to surge sd off plug. Still did not hold. TIH w/ another plug & could not get past sd @ 5871'. Tried to TOH w/ plug, but it partially set @ 3625'. Surged well from 2700 psi. dn to 600 psi. Plug would not rlse. Set plug @ 3625' & TOOH. RD all Halliburton equip. Left well SI w/ 600 psi.

Est. DC - \$55,582

Est. CC - \$483,469

02/03/05 **Current Activity:** WO completion rig to DO frac plug

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBSD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

Est. DC - \$7030

Est. CC - \$490,499

02/04/05 **Current Activity:** WO completion rig to DO frac plug

Est. DC - \$

Est. CC - \$490,499

02/05/05 **Present Operation:** SI for Weekend

Current Activity: MIRU MD Well Serv. Rig #3 pmp & trk. SICP- 250 psi. Blew off to pit. Removed frac valve & installed 5000 psi double ram hyd. BOP. Unloaded 180 jts new 2- 7/8" 6.5# J-55 EUE 8 rd. tbg. Transferred 31 jts 2 7/8" tbg f/ 4-29-54. TIH w/ 4 3/4" Smith Rock bit on 48 jts. 2 7/8" tbg. Stop @ 1500'.

Est. DC - \$9,652

Est. CC - \$497,748

02/06-07/05 **Current Activity:** Well shut in for week-end.

Est. DC - \$9,652

Est. CC - \$497,748

02/08/05 **Present Operation:** Perf zone #2

Current Activity: SICP- 0 psi. TIH to 1st frac plug @ 3625'. RU power swivel. DO plug. TIH & washed sd f/ 5871' to 2nd frac plug @ 5900' (plug moved downhole 40' while drilling). TIH & washed sd f/ 6112' to PBSD- 6236'. TOH standing back 80 stds. Stop @ 1236'. Lost 15 bbl to formation.

Est. DC - \$7535

Est. CC - \$505,283

02/09/05 **Present Operation:** Prep to frac

Current Activity: SICP-0 psi. Finish TOH standing back tbg. Remove BOP & install frac valve. RU Halliburton WL. Set Halliburton 4.370" OD x 28" long x 5000 psi composite bridge plug #1 @5905'. Pressure tested plug to 3800 psi.

Perf zone #2 (Uteland Butte) w/ 4" HSC csg. Gun @ 2 spf w/ 120 degree phased, 22.7 gram charges, 0.40" EHD, 37.5" TTP as follows:

5878'-5880' (2') 4 holes

5836'-5838' (2') 4 holes

5818'-5820' (2') 4 holes

5774'-5776' (2') 4 holes

5767'-5769' (2') 4 holes

5746'-5748' (2') 4 holes

5721'-5723' (2') 4 holes

Est. DC - \$44,894

Est. CC - \$550,177

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

02/10/05 Present Operation:

Current Activity: Finished filling 9.5-500 bbl frac tanks w/ 3% KCL wtr. Heated tanks to 110° F (82°@ pump time). MIRU Halliburton frac equipment. HSM. Pressure test lines to 5500 psi. Thawed out frac valve. Computers locked up Re-booted 2 times. Start pumping @10:10 a.m. Frac zone #2 (Uteland Butte) perfs 5721' to 5880' via 5 ½ csg. w/ following:

- 55 gal. Inhibitor
- 250 gal. 7 ½% HCL spearhead acid
- 1200 gal. 3.0% treated spacer
- 13,495 gal. Delta 140 20# pad
- 18,035 gal. Delta 140 20# sd. Laden fluid, ramp 16/30 mesh sd. @3.0 -4.0 ppg
- 250 gal. 7 ½% HCL
- 5714 gal. 3.0% KCL treated flush

Formation broke down @ 3060 psi @4.5 BPM. Ave. rate: 29.9 BPM. Avg. press: 1176 psi. Max press: 3060 psi. HHP used: 861. ISDP: 975 psi. Frac gradient: 0.61 psi/ft. TLTR: 1083.8 bbl. Total sd. Pumped: 60,000 lbs. 16/30 mesh Brady sd.

Set Halliburton 4.370" OD x 28" long x 5000 psi flow-through composite frac plug #2 @ 5640'. Pressure tested plug to 1000 psi.

Perf zone #3 (Castle Peak / Lower Black Shale) w/ 4" HSC csg. gun @ 2 spf w/ 120 degree phased, 22.7 gram charges, 0.40" EHD, 37.5" TTP in 2 runs (due to mis-fire) as follows:

- 5576'-5582' (6') 12 holes
- 5536'-5540' (4') 8 holes
- 5515'-5516' (1') 2 holes
- 5503'-5505' (2') 4 holes
- 5395'-5398' (3') 6 holes
- 5273'-5278' (5') 10 holes

Frac zone #3 (Castle Peak / Lower Black Shale) perfs 5273'to 5582' via 5 ½" csg. w/ following:

- 55 gal. Inhibitor
- 1385 gal. 3.0% treated spacer
- 11,074 gal. Delta 140 20# pad
- 5555 gal. Delta 140 20# sd. Laden fluid, w/ 2.0 ppg 16/30 mesh sd.
- 6853 gal. Delta 140 20# sd. Laden fluid, w/ 4.0 ppg 16/30 mesh sd
- 6845 gal. Delta 140 20# sd. Laden fluid, w/ 5.0 ppg 16/30 mesh sd
- 6371 gal. Delta 140 20# sd. Laden fluid, w/ 6.0 ppg 16/30 mesh sd
- 250 gal. 7 ½ % HCL
- 5297 gal. 3.0% KCL treated flush

Formation broke @ 357 psi @ 9.0 BMP. Ave. rate: 33.8 BPM. Ave press: 545 psi. Max press: 941 psi. HHP used: 451. ISDP: 556 psi. Frac gradient: 0.54 psi/ft. TLTR: 1035.2 bbl. Total sd. pumped: 110,000 lbs. 16/30 mesh Brady sd.

Set Halliburton 4.370" OD x 28" long x 5000 psi flow-through composite frac plug #3 @ 5135'. Pressure tested plug to 900 psi.

Perf zone #4 (Lower Douglas Creek / Upper Black Shale) w/ 4" HSC csg. gun @ 2 spf w/ 120 degree phased, 22.7 gram charges, 0.40" EHD, 37.5" TTP in 2 runs as follows:

- 5047'-5053' (6') 12 holes
- 4894'-4902' (8') 16 holes

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBSD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

4868'-4872' (4') 8 holes

4848'-4852' (4') 8 holes

4798'-4802' (4') 8 holes

Frac zone #4 (Lower Douglas Creek/Lower Black Shale) perfs 4798' to 5053' via 5 1/2" csg. w/ following:

55 gal. Inhibitor

640 gal. 3.0% treated spacer

8060 gal. Delta 140 20# pad

3598 gal. Delta 140 20# sd. laden fluid, w/ 2.0 ppg 16/30 mesh sd.

3473 gal. Delta 140 20# sd. laden fluid, w/ 4.0 ppg 16/30 mesh sd. Delta

3523 gal. Delta 140 20# sd. laden fluid, w/ 5.0 ppg 16/30 mesh sd.

4174 gal. Delta 140 20# sd. laden fluid, w/ 2.0 ppg 16/30 mesh sd.

250 gal 7 1/2% HCL

4775 gal. 3.0% KCL treated flush

Formation broke @ 984 psi @ 4.6 BPM. Ave rate: 34.4 BPM. Ave. press : 1471 psi. Max press: 2373 psi.
HHP used: 1240 ISDP: 1734 psi. Frac gradient: 0.79 psi/ft. TLTR: 674.8 bbl. Total sd. pumped: 60,000 lbs.
16/30 mesh Brady sd.

Set Halliburton 4.370" OD x 28" long x 5000 psi flow-through composite frac plug #4 @ 4580'. Pressure tested plug to 1300 psi.

Perf zone #5 (Upper Douglas Creek / Garden Gulch) w/ 4" HSC csg. gun @ 2 spf w/ 120 degree phased, 22.7 gram charges, 0.40" EHD, 37.5" TTP as follows:

4472' - 4474' (2') 4 holes

4464' - 4466' (2') 4 holes

4454' - 4456' (2') 4 holes

4280' - 4292' (12') 24 holes

Frac zone #5 (Upper Douglas Creek / Garden Gulch) perfs 4280' to 4474' via 5 1/2" csg. w/ following:

55 gal. Inhibitor

500 gal. 3.0% treated spacer

8000 gal. Delta 140 20# pad

3500 gal. Delta 140 20# sd. laden fluid, w/ 2.0 ppg 16/30 mesh sd.

3500 gal. Delta 140 20# sd. laden fluid, w/ 4.0 ppg 16/30 mesh sd.

3600 gal. Delta 140 20# sd. laden fluid, w/ 5.0 ppg 16/30 mesh sd.

3500 gal. Delta 140 20# sd. laden fluid, w/ 6.0 ppg 16/30 mesh sd.

4278 gal. Flush.

Formation broke @ 586 psi @ 5.0 BPM. Avg. rate: 35.8 BPM. Avg. press: 781 psi. Max press: 1155 psi.
HHP used: 861. ISDP: 840 psi Frac gradient: 0.63 psi/ft. TLTR: 669.1 bbl Total sd. pumped: 60,200 lbs.
16/30 mesh Brady sd.

TLTR from zones #1, 2, 3, 4, 5 combined is 4168.3 bbl. Total sand pumped into zones #1, 2, 3, 4, 5 combined is 350,200 lbs. 16/30 mesh Brady sd.

Finished pumping @ 6:21 p.m. RD & released all Halliburton equipment. Opened well w/ 310 psi. SICP after 54 min. shut-in on 3/4" positive choke to tank @ 7:15 p.m., MDT, 2/9/2005. Flowed 42 bbl. in 1 hr. & died.

Est. DC - \$160,942

Est. CC - \$711,119

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

02/11/05 Present Operation: DO frac plugs

Current Activity: Well was dead. Removed frac valve. Installed 5000 psi double ram hyd BOP. TIH w/ 4-3/4" Smith rock bit on 2-7/8" tbg. DO very hard sd bridge f/ 4296-4326'. TIH. Wash sd f/ 4495-1ST frac plug @ 4580'. D/o plug. TIH & tag sand @ 4999'. TOH above perfs to 4200'. Lost 510 bbls wtr to perfs TLWTR: 4636.

Est. DC - \$9,683

Est. CC - \$720,201

02/12/05 Present Operation: DO frac plugs

Current Activity: Well was dead. TIH & wash sd f/ 4999' to 2nd frac plug @ 5135'. D/o plug. TIH & tag sand @ 5480'. TOH above perfs to 4200'. Lost 825 bbl wtr to perfs. TLWTR: 5461 bbl. RU Weatherford foam air unit.

Est. DC - \$17,026

Est. CC - \$736,515

02/13/05 Present Operation: SI for weekend

Current Activity: SICP-vacuum. Test Weatherford lines to 2000 psi. Circ hole clean w/ foam air down tbg. TIH and circ sd f/ 5450' to 3rd frac plug @ 5640'. D/o plug. TIH and circ sd f/ 5863' to 4th frac plug @ 5909'. D/o plug. RD Weatherford foam unit. TIH and push nose cone from last plug to pbtd- 6236'. TOH above perfs to 4200'. Recovered 450 bbl. wtr TLWTR: 5011 bbl

Est. DC - \$12,753

Est. CC - \$749,268

02/14/05 Present Operation: SI

02/15/05 Present Operation: Swab back frac load

Current Activity: SICP- 520 psi. SITP- 300 psi. Press. blew off fast. TIH & tag pbtd @ 6234' (2' of fill). Pump 80 bbl. 2% KCL wtr. Dwn csg. & 30 bbl. dwn tbg. TOH. TIH w/ production tbg.:

	<u>Length</u>	<u>Depth</u>
KB	10.00'	10.00'
136 jts. new 2 7/8" J-55 8 rd. 6.5# EUE tbg.	4205.74'	4215.74'
1- 2 7/8" x 5 1/2" TAC (40 K shear)	2.66'	4218.40'
58 jts. new 2 7/8" J-55 8 rd. 6.5# EUE tbg.	1784.62'	6003.02'
1- 2 7/8" SN (I.D.- 2.28")	1.10'	6004.12'
1 jt. new 2 7/8" J-55 8 rd. 6.5# EUE tbg.	30.87'	6034.99'
1- 2 7/8" notched collar	.45'	6035.44'

Remove BOP. Set TAC w/ 10 pts tension. NU WH. RU to swab. IFL- 1000' fs. Made 12 runs & recovered 100 bbl. wtr. TLWTR: 4561 bbl no trace of oil. Small trace of gas. No sd. EFL- 1100' fs. SICP- 120 psi.

Est. DC - \$19,474

Est. CC - \$771,650

02/16/05 Present Operation: Swab back frac load

Current Activity: SICP- 580 psi. SITP-40 psi. IFL-1000' fs. Made 37 runs & recovered 280 BW TLWTR: 4741 bbl. No trace of oil. No gas. No sd. EFL-1400' fs. SICP-910 psi.

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBDT:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

Est. DC - \$7408

Est. CC - \$779,058

02/17/05 Present Operation: Swab back frac load

Current Activity: SICP- 1160 psi. SITP- 0 psi. IFL- 1200' fs. Bled csg. press. down to 300 psi. Made 35 runs & recovered 300 bbl. wtr. TLWTR: 4441 bbl. No trace of oil. Small show of gas. No sd. EFL- 1400' fs. SICP- 875 psi.

Est. DC - \$10,557

Est. CC - \$789,615

02/18/05 Present Operation: Swab back frac load

Current Activity: SICP- 1160 psi SITP- 0 psi IFL- 1400' fs. Bled csg. press. down to 0 psi. Made 38 runs & recovered 320 bbl. wtr. TLWTR: 4121 bbl. Slight trace of oil. Small show of gas. No sand. EFL- 1500' fs. SICP-970 psi.

Est. DC - \$6,710

Est. CC - \$796,325

02/19/05 Present Operation: Swab back frac load

Current Activity: SICP-1200 psi. SITP-light blow. Bled csg. press. Down to 300 psi & started flowing 50% oil up csg. IFL- 1500'fs. Skim oil on top of 1st run. Made 36 runs & recovered 318 bbl. wtr. TLWTR: 3803 bbl. Slight trace of oil. Small show of gas. No sd. EFL- 1600; fs. SICP-1100 psi.

Est. DC - \$5,061

Est. CC - \$801,386

02/20/05 Present Operation: Swab back frac load

Current Activity: SICP- 1200 psi. SITP-light blow. IFL-1300'fs. Trace of oil on top of 1st run. Made 30 runs & recovered 309 bbl. wtr. TLWTR: 3494 bbl. Final oil cut- 4%. Good show of gas. No sd. EFL- 1600' fs. SICP-1225 psi.

Est. DC - \$5,107

Est. CC - \$806,493

02/22/05 Present Operation: Swab back frac load

Current Activity: SICP-1220 psi. SITP-30 psi. IFL-1500' fs. 200' of oil on top of 1st run. Made 37 runs & recovered 326 bbl. wtr. TLWTR: 3168 bbl. Final oil cut-4%. Good show of gas. No sand. EFL- 1700' fs. SICP-1240 psi.

Est. DC - \$5,001

Est. CC - \$811,494

02/23/05 Present Operation: RIH w/pkr; Cont swab back frac load

Current Activity: SICP- 1220 psi. SITP-0 psi. IFL-1400' fs, 300' of oil on top of 1st run. Made 38 runs & recovered 320 bbls wtr TLWTR: 2848 bbl. Final oil cut -1%. Good show of gas. Trace of sand on runs 30 & 31. EFL- 1700' fs. SICP-1220 psi.

Est. DC - \$5,301

Est. CC - \$816,795

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

02/24/05 Present Operation: Swab back frac load

Current Activity: SICP- 1220 psi. SITP-0 psi. Blew dwn csg to 250 psi until it started flowing oil. Pumped 110 bbl 2% KCL down csg. & 20 bbl down tbg. Installed BOP. Released TAC & TOH w/ tbg. L/d TAC & TIH w/ Halliburton 2 7/8" x 5 1/2" RTTS pkr on 191 jts 2 7/8" tbg. Set pkr w/ 8 pts compression @ 5906' to isolate Wasatch zone 5928' -5944'. RU to swab. IFL-800' fs. Made 9 runs & recovered 60 bbl wtr. TLWTR: 2918 bbl. Trace of yellow-green oil & gas. EFL- 3400' fs. SICP- 380 psi. Initial frac load to recover from Wasatch zone was 705.4 bbl.

Est. DC - \$7,200

Est. CC - \$823,995

02/25/05 Present Operation: Swab back frac load

Current Activity: SICP- 1145 psi SITP- 0 psi IFL- 1500' fs. Trace of oil on top of 1st run. Made 22 runs & recovered 252 bbl wtr. TLWTR: 2666 bbl. Final oil cut - 2%. Slight trace of gas. No sd. EFL- 5000' fs SICP- 1220 psi.

Est. DC - \$4,788

Est. CC - \$828,783

02/26/05 Present Operation: Swab back frac load.

Current Activity: SICP-1220 psi. IFL-1300'fs. Trace of oil on top of 1st run. Made 29 runs & recovered 114 bbl wtr. TLWTR: 2552 bbl. Final oil cut-25%. Slight trace of gas. No sand. EFL- 5600'fs. SICP-1220 psi.

Est. DC - \$5,345

Est. CC - \$833,808

02/27/05 Present Operation: Shut in for weekend.

Current Activity: SICP-1220 psi. SITP-10 psi. IFL-2200' fs. 150' (0.90 bbl) oil on top of 1st run. Made 22 runs & recovered 85 bbl wtr. (Total swab from Wasatch zone(5928'*5944') was 511 bbl (72% of frac load). Wasatch oil is dark black in appearance. Oil and water samples have been taken to Halliburton-Vernal, UT for analysis.) & 5 bbl oil. Final swab rate: 10:0-11:0 BPH. Final oil cut- 9%. Slight trace of gas. No sd. EFL-5500' fs. Blew dwn csg to 250 psi. Pump 45 bbl wtr dwn csg & 30 bbl to isolate Uteland Butte(5721'-5880') & Wasatch(5928'-5944'). SN depth is 5620'. RU to final oil cut-36%. Heavy gas. No sd. SICP- 500 psi.

Est. DC - \$6,654

Est. CC - \$840,462

02/28/05 Current Activity: Shut in.

03/01/05 Present Operation: Swab back frac load.

Current Operation: SICP- 1220 psi SITP- 380 psi. IFL- 1300' fs. Made 1 run & recovered 5 bbl oil. Heavy gas. Blew dwn csg to 250 psi. Pump 80 bbl wtr dwn csg & 15 bbl dwn tbg. Release pkr & TOH standing back tbg. RU Halliburton WL & set composite bridge plug @ 5630'. RD Halliburton. Trickle 25 bbl wtr dwn csg while TIH w/ RTTS pkr on 2 7/8" tbg. Set pkr @ 5443' on 176 jts w/ 7 pts tension to isolate Castle Peak (5503' - 5582'). Install Washington head stripper. RU to swab. Made 7 runs & recovered 57 bbl wtr TLWTR: 2490 bbl EFL- 1700'. Trace of oil & gas. No sd.

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBDT:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

Est. DC - \$9,900

Est. CC - \$850,362

03/02/05 **Present Operation:** Swab back frac load.

Current Operation: SICP- 1100 psi. SITP- 0 psi. IFL-1200' fs. 50' of oil on 1st run. Made 35 runs & recovered 320 bbl wtr. Max. oil cut- 1%. No sd. Well kicked off flowing gas @ 200 mcfpd on 16/64" choke @ 125 psi. Died after 30 min. Made 1 more run & recovered 4 bbl. wtr. TLWTR: 2166 bbl. EFL- 1400' fs. SICP- 1220 psi. Total daily wtr recovery: 324.0 bbl. Total wtr recovery f/ Castle Peak perms. 5503-5582: 381.0 bbl.

Est. DC - \$5,411

Est. CC - \$855,773

03/03/05 **Present Operation:** Swab back frac load.

Current Operation: SICP- 1220 psi. SITP- 100 psi. Blew dwn tbq. IFL- 1400' fs. 5' of oil on 1st run. Made 15 runs & recovered 136 bbl wtr. Well kicked off flowing gas @ 175 psi. on 0.68" orifice. Flowed 21 bbl wtr & died after 30 min. Made 7 runs & recovered 56 bbl wtr. Kicked off flowing gas & flowed 46 bbl wtr in 45 min. Died. Made 2 more runs & recovered 16 bbl wtr. Total wtr recovered- 275 bbl. TLWTR: 1891 bbl EFL- 1500' fs. SICP- 1220 psi.

Est. DC - \$5,410

Est. CC - \$861,183

03/04/05 **Present Operation:** Swab back frac load.

Current Operation: SICP-1220 psi. SITP-50 psi. Blew dwn tbq. IFL-1700'fs. No oil on 1st run. Made 8 runs & recovered 63 bbl wtr. Blew off csg press. Pumped 80 bbl dwn csg & 31 bbl dwn tbq to kill well. Released pkr & TOH w/ tbq. RU Weatherford WL & set 5 1/2" Halliburton composite bridge plug @ 5350'. RD Halliburton. TIH w/ RTTS pkr on 2 7/8" tbq. Set pkr @ 5009' on 162 jts w/ 7 pts tension to isolate Black Shale (5047'-5278'). Install Washington head stripper. RU to swab. IFL-1000'fs. Made 2 runs & recovered 16 bbl wtr. TLWTR: 2522 bbl. EFL-2100'fs. No oil & gas. No sd. Total wtr recovered f/ Castle Peak perms (5503'-5582')= 719 bbl.

Est. DC - \$9,593

Est. CC - \$870,776

03/05/05 **Present Operation:** Swab back frac load.

Current Operation: SICP- 700 psi. SITP- 25 psi. Blew dwn tbq. IFL-1600'fs. No oil on 1st run. Made 3 runs & recovered 20 bbl wtr. Made 3 dry runs. EFL- 4800' fs. SICP- 850 psi. Blew dwn csg to 100 psi – flowed 56 bbl wtr up backside. Pump 20 bbl wtr dwn tbq. Release pkr & TOH w/ 3 stands. Set pkr @ 4823' on 156 jts w/ 5 pts compression to isolate Lower Douglas Creek (4848' – 4902') & Upper Black Shale (5047' – 5278'). SN depth is 4793'. SICP- 250 psi. RU to swab. Made 2 runs & recovered 16 bbl wtr. Well started flowing gas. Csg press dropped to 0 psi. Communication w/ csg through perms @ 4798'– 4802'. Pump 15 bbl wtr dwn tbq. Release pkr & TOH w/ 2 stands. Set pkr @ 4700' on 152 jts w/ 5 pts compression to isolate Lower Douglas Creek (4798'– 4902') & Upper Black Shale (5047'– 5278'). SN depth is 4670'. SICP- 0 psi. RU to swab. IFL- 1700' fs. Made 13 runs & recovered 80 bbl wtr from swabbing & flowing (would flow 10–15 min after each run – f.l. was scattered between 1700' to 2600'). TLWTR: 2290 bbl. EFL- 1800'. Trace of oil. Heavy gas. No sand. SICP- 375 psi.

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

Est. DC - \$5,642

Est. CC - \$876,418

03/06/05 **Present Operation:** SI for weekend.

Current Operation: SICP-475 psi. SITP-1300 psi. Blew dwn csg & flowed back 20 bbl wtr. RU to swab. IFL- 1500' fs. Made 27 runs & recovered 171 bbl wtr. TLWTR: 2099 bbl. EFL-1800'fs. Trace of oil. Heavy gas. No sd. SICP-475 psi. Daily wtr recovery: 191.0 bbl. Total wtr recovered f/ Lower Douglas Creek (4798-4902') SWI for week-end.

Est. DC - \$5,312

Est. CC - \$881,730

03/07/05 **Present Operation:**

Current Operation: SI

03/08/05 **Present Operation:** RD Weatherford

Current Operation: SICP- 475 psi. SITP-1350 psi. Blw dwn tbg & flowed back 35 bbl wtr. RU to swab. IFL- 2100'fs. Made 7 runs & recovered 64 bbl wtr. EFL- 1500'fs. Trace of oil. Heavy gas. No sd. SICP- 475 psi. Pumped 20 bbl wtr dwn tbg & 50 bbl dwn csg to kill well. Pumped 75 bbls in 2 hrs getting pkr released. TLWTR: 2145 bbl TOH w/ tbg & l/d pkr RU Weatherford WL. Set 1/2" composite BP @ 4670'. RD Weatherford.

Est. DC - \$7,558

Est. CC - \$883,976

03/09/05 **Present Operation:** RDMO pulling unit

Current Operation: SICP- 25 psi. Pumped 50 bbl wtr dwn csg to kill well. TIH & l/d 49 jts tbg. TIH w/ production tbg.:

	<u>Length</u>	<u>Depth</u>	
KB		10.00'	10.00'
136 jts. new 2 7/8" J-55 8 rd. 6.5# EUE tbg.		4205.74'	4215.74'
1- 2 7/8" x 5 1/2" TAC		2.66'	4218.40'
9 jts. new 2 7/8" J-55 8 rd. 6.5# EUE tbg.		274.88'	4493.28'
1- 2 7/8" SN (I.D.- 2.28")		1.10'	4494.38'
1 jt. new 2 7/8" J-55 8 rd. 6.5# EUE tbg.		30.87'	4525.25'
1- 2 7/8" notched collar		.45'	4525.70'

Pumped 30 bbl dwn csg & 20 bbl dwn tbg to kill well. Remove BOP. Set TAC w/ 10 pts tension. NU WH. TIH w/ production rods:

1	1 1/2" x 22' polish rod & 1 3/4" liner
3	7/8" rod subs (2', 8', 8')
58	7/8" rods w/ rod guides
136	3/4" rods
4	1 1/2" k-bars w/ 5- 3' stabilizers
1	2 1/2" x 1 1/2" x 12' x 15' x 15 1/2' RHAC pump #1668

Space out rods & hang off on WH. Load & tst pump w/ 7 bbl 2% KCL wtr to 800 psi. TLWTR: 2207 bbl W.O. pumpjack. RDMO pulling unit.

FIML NATURAL RESOURCES, LLC

WELL HISTORY

Ute Tribal #8-31-55

API # 43-013-32673
SENE Sec 31 T-5S,R-5W
Brundage Canyon Field
Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:
Spud Date: November 26, 2004
Gr Elev: 7823' KB: 7833'
Drlg Contractor: Union Drilling Company Rig #14

Est. DC - \$30,016

Est. CC - \$913,992

03/10/05 **Present Operation:**

Current Operation: RDMO pulling unit

Est. DC - \$30,016

Est. CC - \$913,992

03/11/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$10,228

Est. CC - \$924,220

03/12-14/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$

Est. CC - \$924,220

03/15/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$

Est. CC - \$924,220

03/16/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$412

Est. CC - \$924,632

03/17/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$1661

Est. CC - \$926,293

03/18-22/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$

Est. CC - \$926,293

03/23/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$10,167

Est. CC - \$936,460

03/30/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

FIML NATURAL RESOURCES, LLC

WELL HISTORY

CONFIDENTIAL

Ute Tribal #8-31-55

API # 43-013-32673

SENE Sec 31 T-5S,R-5W

Brundage Canyon Field

Duchesne Co., UT

PTD: 6211' ATD: 6277' PBTD:

Spud Date: November 26, 2004

Gr Elev: 7823' KB: 7833'

Drlg Contractor: Union Drilling Company Rig #14

Est. DC - \$412

Est. CC - \$939,745

04/01/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$

Est. CC - \$939,745

04/02-04/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$

Est. CC - \$939,745

04/05/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$

Est. CC - \$939,745

04/06/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$854

Est. CC - \$940,599

04/07/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$1,573

Est. CC - \$942,172

04/08/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$

Est. CC - \$942,172

04/09/05 **Present Operation:** Prep to put well on production

Current Activity: Production battery construction

Est. DC - \$7,707

Est. CC - \$949,879

04/10/05 **Present Operation:** Well producing

Current Activity: Started producing @ 12:00pm April 9, 2005. **FINAL REPORT**

Est. DC - \$

Est. CC - \$949,879

FIML NATURAL RESOURCES, LLC

CONFIDENTIAL

May 19, 2005

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, UT 84114-5801

Attn.: Ms. Carol Daniels

RE: Ute Tribal #8-31-55
SENE Sec 31 T-5S R-5W
Duchesne County, Utah

Dear Ms. Daniels:

Enclosed is the following information concerning the referenced well.

Sundry Notice with Attached Composite Completion Operations Report
Well Completion or Recompletion Report and Log
Halliburton Electric Logs (2 originals)
Chief Well Logging Mud Log (1 original)
Halliburton Cement Bond Log (1 original)

FIML (FNR) Natural Resources, LLC is requesting the Utah Division of Oil, Gas and Mining to hold this information as confidential.

If any questions arise or additional information is required, please contact me at 303-893-5083.

Sincerely,



Rick L. Parks
Operations Manager

/cp
Enclosures:

RECEIVED

MAY 23 2005

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well ☒ Oil Well ☐ Gas Well ☐ Other **CONFIDENTIAL**

2. Name of Operator **FIML Natural Resources, LLC**

3a. Address
410 17th Street, Suite 570 Denver, CO 80202

3b. Phone No. (include area code)
303-893-5081

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal #8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Completion
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Operations
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	Composite Report

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Attached is the composite completion operations report.

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-53

RECEIVED
MAY 23 2005
DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Rick L. Parks

Title **Operations Manager**

Signature

Date

5/19/05

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

CONFIDENTIAL

Form 3160-4
(April 2004)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: March 31, 2007

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other		5. Lease Serial No. 14-20-H62-5060	
b. Type of Completion: <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr., Other _____		6. If Indian, Allottee or Tribe Name Ute Tribe	
2. Name of Operator FIML Natural Resources, LLC		7. Unit or CA Agreement Name and No.	
3. Address 410 17th Street, Suite 570 Denver, CO 80202		8. Lease Name and Well No. Ute Tribal #8-31-55	
3a. Phone No. (include area code) 303-893-5081		9. AFI Well No. 43-013-32673	
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface SENE 1980' FNL 660' FEL At top prod. interval reported below Same as above At total depth		10. Field and Pool, or Exploratory Undesignated	
14. Date Spudded 11/26/2004		15. Date T.D. Reached 12/10/2004	
16. Date Completed 03/11/2005 <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod.		17. Elevations (DF, RKB, RT, GL)* 7823' GR KB: 7833;	
18. Total Depth: MD 6217' TVD 6217'		19. Plug Back T.D.: MD 6236' TVD 6236'	
20. Depth Bridge Plug Set: MD 5905' TVD 5905'		21. Type Electric & Other Mechanical Logs Run (Submit copy of each) MUD LOG, Spectral Density/Dual Spaced Neutron; Hi Resolution Induction; Cmt Bond Log	
22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit report) Directional Survey? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit copy)			

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12 1/4"	8-5/8 J55	24	0	311'		180 Prem	137	Circ Surf	0
7 7/8"	5-1/2 J55	15.5	0	6271'		250 CBM	191	3440' CBL	0
						Lite			
						430 Lite	134		
						Prem plus			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8	4252'							

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) Garden Gulch			4292-4474'	.40	36	Open
B) Douglas Creek			4798-5053'	.40	52	Open
C) Castle Peak			5273-5582'	.40	42	Open
D) Uteland Butte			5880-5721'	.40	28	Open

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
Garden Gulch	Frac w/ 28,098 gal gel & 60,200 # mesh Brady sand
Douglas Creek	Frac w/ 28,342 gals gel & 60,000 # 16/30 mesh Brady sand
Castle Peak	Frac w/ 43,478 gals gel & 110,000# 16/30 mesh Brady sand
Uteland Butte	Frac w/ 45,520 gals gel & 60,000 # 16/30 mesh sand

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
04/09/2005	04/15/2005	24	→	0	174	0		0.6085	Pumping
Choke Size	Tbg. Press. Flwg. SI	Csg. Press. N/A	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
N/A			→	0	174	0	174,000	SI waiting on gas line	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

*(See instructions and spaces for additional data on page 2)

RECEIVED

MAY 23 2005

DIV. OF OIL, GAS & MINING

CONFIDENTIAL

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

29. Disposition of Gas (Sold, used for fuel, vented, etc.)

Sold

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
Garden Gulch	3932'	4271'	Sandstone - Oil & Gas	Green River	1353'
Douglas Creek	4558'	4748'	Sandstone - Oil & Gas	Mahogany Bench	2848'
Castle Peak	5370'	5546''	Sandstone - Oil & Gas	Garden Gulch	3473'
Uteland Butte	5708'	5868'	Sandstone - Oil & Gas	Douglas Creek	4357'
Wasatch	6071'	6086'	Sandstone - Oil & Gas	Black Shale	4974'
				Castle Peak	5273'
				Uteland Butte	5704'
				Wasatch	5899'

32. Additional remarks (include plugging procedure):


The Ute Tribal 8-31-55 has not produced any oil and is currently shut-in, waiting on a pipeline.

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☒ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☐ Directional Survey
 ☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Mud Log; E-Log las e-mailed BLM 5/19/05; CBL las e-mailed BLM 5/19/05

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Rick L. Parks Title Operations Manager

Signature  Date 05/19/2005

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007**SUNDRY NOTICES AND REPORTS ON WELLS****Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.****SUBMIT IN TRIPLICATE- Other instructions on reverse side.**1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator **FIML Natural Resources, LLC**3a. Address
410 17th Street, Suite 900 Denver, CO 802023b. Phone No. (include area code)
303-893-5083

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION

TYPE OF ACTION

- | | | | | |
|---|---|---|--|---|
| <input type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Subsequent Report | <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other Workover |
| | <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug and Abandon | <input type="checkbox"/> Temporarily Abandon | Operations |
| | <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | Rpt |


13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Attached is a workover operations report for the Ute Tribal 8-31-55.**BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.****State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93**

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Cassandra ParksTitle **Operations Assistant**

Signature



Date

10/13/2006**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED**OCT 16 2006**

DIV. OF OIL, GAS & MINING

Date	Description
3/9/2005	<p>SICP- 25 psi. Pumped 50 bbl wtr dwn csg to kill well. TIH & l/d 49 jts tbq. TIH w/ production tbq.:</p> <p>Length@Depth</p> <p>KB 10.00' = 10.00'</p> <p>136 jts. new 2 7/8 J-55 8 rd. 6.5# EUE tbq. 4205.74' = 4215.74'</p> <p>1- 2 7/8 x 5 1/2 TAC 2.66' = 4218.40'</p> <p>9 jts. new 2 7/8 J-55 8 rd. 6.5# EUE tbq. 274.88' = 4493.28'</p> <p>1- 2 7/8 SN (I.D.- 2.28) 1.10' = 4494.38'</p> <p>1 jt. new 2 7/8 J-55 8 rd. 6.5# EUE tbq. 30.87' = 4525.25'</p> <p>1- 2 7/8 notched collar .45' = 4525.70'</p> <p>Pumped 30 bbl dwn csg & 20 bbl dwn tbq to kill well. Remove BOP. Set TAC w/ 10 pts tension. NU WH. TIH w/ production rods:</p> <p>1@ 1 1/2 x 22' polish rod & 1 1/4 liner</p> <p>3 @ 7/8 rod subs (2', 8', 8')</p> <p>58 @ 7/8 rods w/ rod guides</p> <p>136 @ 3/4 rods</p> <p>4 @ 1 1/2 k-bars w/ 5- 3' stabilizers</p> <p>1@ 2 1/2 x 1 1/2 x 12' x 15' x 15 1/2' RHAC pump #1668</p> <p>Space out rods & hang off on WH. Load & tst pump w/ 7 bbl 2% KCL wtr to 800 psi. TLWTR: 2207 bbl W.O. pumpjack. RDMO pulling unit.</p> <p>-</p>
3/10/2005	Build tank battery from 3-10-2005 to 4-9-2005
4/10/2005	producing @ 12:00pm April 9, 2005. FINAL REPORT
6/27/2005	Cleaned up extra pipe ROW & hauled to yard.
7/1/2005	Depressured gas line and installed check valve. Hauled treater to location and hooked up to casing on well head and dump line to vertical treater.
7/26/2005	Tightened tank bolts on manway w/ electric impact wrench.
2/9/2006	MIRU Basic 1604 from the Ute Tribal 13-18-54 to Ute Tribal 8-31-55. Rig up. Shut down for night. Left well pumping.
2/10/2006	<p>RU Hot Oil Express. Pumped 35 bbls 2% KCl water heated to 250° down annulus. Unseated pump and pumped 25 bbls 2% KCl water heated to 250° down tubing. TOH with rods and pump. ND Wellhead, release TAC and installed BOP. TOH with 2-7/8" tubing string CIWSDFWE.</p> <p>-</p>
2/13/2006	<p>42 hour SICP: 150 psi. Bled pressure off well. TIH with 4-3/4" bit and 5-1/2" casing scraper on 2-7/8" tubing string to 4504'. TOH and lay down it and scraper. TIH with Halliburton retrievable packer and RBP. Set RBP @ 4510' and CIWSDFN.</p> <p>-</p>

Date	Description
2/14/2006	<p>16 hour SITP: 50 psi. RU Superior Well Services and pressure tested lines to 4000 psi. Acidized Upper Douglas Creek perforations from 4454 to 4474 with 500 gallons (12 bbls) 15% HCl containing 1 gal Al-2 inhibitor, 2.5 gal Super scale inhibitor, .5 gal. Super-100 NE, .5 gal Clay treat PP, 25# IC-100, 5 gal Acetic Acid, 25# PH-8 & (25) 7/8" soluble ball sealers. Flushed with 25 bbls 3% KCl water. AIR: 4.3 BPM, MIR: 4.3 BPM, ATP: 879 psi, MTP: 1205 psi, ISDP: 840 psi (FG = .62 psi/ft) Slight ball action observed. 5 min sip: 403 psi, 10 min sip: 278 psi, 15 min sip: 192 psi. Bled pressure off tubing string, released packer and TIH to RBP. Unable to latch onto RBP due to ball sealers. Pumped 20 bbls 3% KCl water down casing to wash balls off RBP. Latched onto and released RBP. Set RBP @ 4320' and packer at 4265'.</p> <p>Acidized Upper Douglas Creek perforations from 4280 to 4292 with 500 gallons (12 bbls) 15% HCl containing 1 gallon Al-2 inhibitor, 2.5 gal Super Scale Inhibitor, .5 gal Super-100 NE, .5 gal Clay Treat PP, 25# IC-100, 5 gal Acetic Acid and 25# PH-8. Flushed with 29 bbls 3% KCl water. AIR: 5.8 BPM, ATP: 474 psi, ISDP 5 psi. (FG= .44 psi/ft). 5 min sip: 0 psi, TLTR from both zones: 126.8 bbls (24 bbls acid & 102.8 bbls 3% KCl water). Released packer and TIH to RBP. Released RBP and TOH with packer and RBP. TIH with 145 joints 2-7/8" tubing string and landed EOT @ 4508' with SN @ 4476. RU swab, IFL @ 4100'. Made 5 swab runs and recovered 19.5 BL&AW. FFL @ 4100'. TLTR: 107.3 bbls. CIWSDFN.</p>
2/15/2006	<p>SITP/SICP: 0 psi/50 psi. RU Swab, made 2 swab runs from SN @ 4478', no fluid recovered. TOH with 2-7/8" tubing string. TIH with bulldog bailer and 4-3/4" bit on 2-7/8" tubing string. Tagged up at 4597'. Cleaned out from 4597 to 4647 (50') and bailer stopped working. Started TOH and SDFN with EOT @ 4189'.</p>
2/16/2006	<p>14 hour SITP/SICP: 50 psi/50 psi. TOH with bailer and cleaned 277' of frac sand out of 2-7/8" tubing. LD bit and TIH with 2-7/8" tubing string with notched collar below Bulldog bailer. Cleaned out frac sand from 4647 to top of 5-1/2" composite BP at 4670'. TOH and recovered 130' of frac sand. TIH with 4-3/4" bit and bull dog bailer to 4189'. Total 3% KCl water pumped 250 bbls. CIWSDFN.</p>
2/17/2006	<p>14 hour SITP/SICP: 50/50 psi. Finish TIH with 4-3/4" bit and bull dog bailer to top of first composite BP AT 4670'. Drilled/bailed out composite BP at 4670'. Continued TIH and tagged up at 5272'. Drilled/bailed from 5272' - 5292' and became stuck. Backed off safety joint and TOH. Fish in hole consists of bit, bit sub, bailer and 10 joints 2-7/8" tubing. CIWSDFWE. Prep to TIH with jars.</p>
2/20/2006	<p>42 hour SICP: 540 psi. Bled pressure off well and pumped 25 bbls 3% KCl water heated to 250° down casing. TIH with overshot, jars, 4-3-1/2" DC's and accelerator sub on 2-7/8" tubing string to top of fish. Flushed tubing string with 20 bbls 3% KCl water heated to 250°. Latched onto fish, jarred 3 times and fish pulled free. TOH. Laid down fishing tools and fish. Sent safety joint to shop for repairs.</p>
2/21/2006	<p>14 hour SICP: 600 psi. Bled pressure off well. TIH with notched collar and bulldog bailer on 2-7/8" tubing string to 5313'. RU power swivel. Pumped 3% KCl water down annulus and cleaned out fill from 5313 to 5321'. Unable to clean out below 5321'. RD power swivel and TOH. Recovered 62' of formation and frac sand in 2-7/8" tubing. CIWSDFN.</p>
2/22/2006	<p>14 hour SICP: 600 psi. Bled pressure off well. TIH with 4-3/4" bit and bailer on 2-7/8" tubing string. Tagged up at 5311' (10' of fill overnight.) RU power swivel. Attempted to bail/drill, unable to clean out fill. Tbg became stuck, jarred 3 times and tbg pulled free. TOH and laid down bailer. Recovered trace of frac sand in tubing. CIWSDFN.</p>
2/24/2006	<p>28 hour SICP: 650 psi. Bled pressure off well. TIH with 4-3/4" bit, bit sub, 4-3-1/2" DC's and jars on 2-7/8" tubing string to 4189'. CIWSDFWE. Prepare to drill out composite bridge plug with N2.</p>
2/27/2006	<p>43 hour SITP/SICP: 650 psi/650 psi. Bled pressure off well. Finished TIH from 4189 to top of fill at 5311'. RU Swivel and Maverick N2 unit. Cleaned out fill from 5311' to composite BP at 5350'. Drilled out composite BP @ 5350'. TIH and tagged fill @ 6170'. Cleaned out fill to 6170'. Blow hole clean with N2. RD power swivel and TOH with 2-7/8" tubing string. LD DC's, jars and all rental equipment. CIWSDFN.</p>

Date	Description																																							
2/28/2006	<p>SICP 950. Shut in 14 hours. Install choke. Blow well down to 50 psi and pump 30 bbls down casing to kill well. Start in hole with production string. Well started flowing up the casing. Pump 30 bbls of 3% KCl down casing to kill well. Nipple down BOP'S. Set TAC with 10,000# tension. Nipple up wellhead, hot oiler. Clean up BOP at well head. Shut well in for night.</p> <table><tr><td>1</td><td>2-7/8", F/O, notched collar</td><td>.45'</td></tr><tr><td>1 jt</td><td>2-7/8", 6.5#, J-55, EUE, 8rd tubing</td><td>31.68'</td></tr><tr><td>1</td><td>4' 2-7/8" perf sub</td><td>4.08'</td></tr><tr><td>1</td><td>2-7/8" PSN</td><td>1.10'</td></tr><tr><td>57 jts</td><td>2-7/8", 6.5#, J-55, EUE, 8rd tbg</td><td>1770.42'</td></tr><tr><td>1</td><td>2-7/8" x 5-1/2" TAC 30K shear pins</td><td>2.75'</td></tr><tr><td>136 jts</td><td>2-7/8", 6.5#, J-55, EUE, 8rd tbg</td><td>4191.55'</td></tr></table> <table><tr><td>194 jts</td><td>Total</td><td>6002.03'</td></tr><tr><td></td><td>KB correction</td><td>12.00'</td></tr><tr><td></td><td>EOT</td><td>6014.03'</td></tr><tr><td></td><td>SN</td><td>5977.82</td></tr><tr><td></td><td>TAC</td><td>4206.30</td></tr><tr><td>-</td><td></td><td></td></tr></table>	1	2-7/8", F/O, notched collar	.45'	1 jt	2-7/8", 6.5#, J-55, EUE, 8rd tubing	31.68'	1	4' 2-7/8" perf sub	4.08'	1	2-7/8" PSN	1.10'	57 jts	2-7/8", 6.5#, J-55, EUE, 8rd tbg	1770.42'	1	2-7/8" x 5-1/2" TAC 30K shear pins	2.75'	136 jts	2-7/8", 6.5#, J-55, EUE, 8rd tbg	4191.55'	194 jts	Total	6002.03'		KB correction	12.00'		EOT	6014.03'		SN	5977.82		TAC	4206.30	-		
1	2-7/8", F/O, notched collar	.45'																																						
1 jt	2-7/8", 6.5#, J-55, EUE, 8rd tubing	31.68'																																						
1	4' 2-7/8" perf sub	4.08'																																						
1	2-7/8" PSN	1.10'																																						
57 jts	2-7/8", 6.5#, J-55, EUE, 8rd tbg	1770.42'																																						
1	2-7/8" x 5-1/2" TAC 30K shear pins	2.75'																																						
136 jts	2-7/8", 6.5#, J-55, EUE, 8rd tbg	4191.55'																																						
194 jts	Total	6002.03'																																						
	KB correction	12.00'																																						
	EOT	6014.03'																																						
	SN	5977.82																																						
	TAC	4206.30																																						
-																																								
3/1/2006	<p>15 hour SITP/SICP: 0/1000 psi. TIH with pump and rod string. Spaced out and seated pump. Pumped 35 bbls 3% KCl water and loaded tubing. Pressured to 500 psi and pressure dropped to 0 psi. TOH with rods and pump. Pump ok. Dropped standing valve. Pumped 40 bbls 3% KCl water, unable to pressure up tubing string. Probable hole in tubing string. CIWSDFN.</p> <p>-</p>																																							
3/2/2006	<p>14 hour SITP/SICP: 1000/1000 psi. Pumped 30 bbls 3% KCl water down casing. Removed wellhead, released TAC and installed BOP. TOH with 2-7/8" tubing string, found hole in joint 89 (1885' from surface.) Finished TOH. RU Four Star hydrotesters. Internally hydrotested tubing to 5000 psi while TIH, did not find any additional bad tubing. Pumped an additional 50 bbls 3% KCl water down casing to control well. CIWSDFN.</p> <p>-</p>																																							
3/3/2006	<p>SICP 1050. SITP: 0</p> <p>Open csg to flat tank and blow pressure down. RU Hot Oil express and wash floor. Tools down. Well head. Suck collar out, pump 30 bbls 3% KCl water down csg. ND BOPs and set TAC @ 10000 tension. Nipple up wellhead pick pump @ prime. Run 2 1/2 x 1 1/2 x 12 x 15 x 16. Insert pump</p> <p>4 - 1 1/2 x 25 kbars 154 - 3/4 x 25 slick rods 80 - 7/8 x 25 guided rods 2 x 7/8 pony 1 1-1/2 x 25' polish rod w/ 1 3/4 liner</p> <p>Seat pump and space out. Fill hole with 12 bbls of 3% KCl. Stroke tested pump up to 1000. Test ok. Hang well @ 1600 hrs 3/3/06. Turn well over to pumpers. RD rig.</p> <p>-</p>																																							
3/4/2006	Produced 0 BO, 70 BW and 55 MCF in 16 hrs. with the casing on a 12/64" choke flowing at 100#.																																							
3/5/2006	Produced 0 BO, 120 BW and 76 MCF in 24 hrs. with the casing on a 12/64" choke flowing at 125#.																																							

Date	Description
3/6/2006	Produced 0 BO, 110 BW and 85 MCF in 24 hrs with the casing on a 12/64" choke flowing at 140#. Shut well in due to a tie-in being done on Berry's sales line.
4/6/2006	Move in Basic Rig 1604 and rig up. Remove head from pumping unit and unseat pump. Shut well in for night. Will have Hot Oil unit in morning.

Casing

Date In	Type	Hole Diam	Size	Weight	Grade	Top	Set Depth	Total Jts Run	Total Csg Footage	TD
5/4/2004	Intermediate	7.875	5.5	15.50	J-55	0.00	0.00	149	0.00	0.00
11/26/2004	Production	12.25	8.625	24.00	J-55	7,822.00	311.10	7	310.10	330.00
12/8/2004	Conductor	7.725	5.5	15.50	J-55	0.00	6,281.46	150	0.00	6,424.00
12/11/2004	Conductor	7.875	5.5	15.50	J-55	7,822.00	6,271.46	146	6,269.46	6,292.00

Tubing

Tubing Purpose	Date In	Date Out	Tubing Setting Depth	Tubing Size	Tubing Weight	Tubing Grade	Tubing ID
Production	2/15/2005	3/9/2005	4,525.70	2.875	6.5	J-55	0
Production	3/9/2005	2/10/2006	4,525.70	2.875	6.5	J-55	0
Production	2/28/2006		6,014.00	2.875	6.5	J-55	0

Perforations

Date	Formation	Upper	Lower	Status	Gun Size	SPF	Phasing
2/9/2005	Ute Land Butte	5878	5880	Open		2	
2/9/2005	Ute Land Butte	5836	5838	Open		2	
2/9/2005	Ute Land Butte	5818	5820	Open		2	
2/9/2005	Ute Land Butte	5774	5776	Open		2	
2/9/2005	Ute Land Butte	5767	5769	Open		2	
2/9/2005	Ute Land Butte	5746	5748	Open		2	
2/9/2005	Ute Land Butte	5721	5723	Open		2	
2/10/2005	Castle Peak- Lower Black Shale	5576	5582	Open		6	

2/10/2005	Castle Peak- Lower Black Shale	5536	5540	Open	4	
2/10/2005	Castle Peak- Lower Black Shale	5515	5516	Open	1	
2/10/2005	Castle Peak- Lower Black Shale	5503	5505	Open	2	
2/10/2005	Castle Peak- Lower Black Shale	5395	5398	Open	3	
2/10/2005	Castle Peak- Lower Black Shale	5273	5278	Open	5	
2/10/2005	Lower Douglas Creek	5047	5053	Open	6	
2/10/2005	Lower Douglas Creek	4894	4902	Open	8	
2/10/2005	Lower Douglas Creek	4868	4872	Open	4	
2/10/2005	Lower Douglas Creek	4848	4852	Open	4	
2/10/2005	Lower Douglas Creek	4798	4802	Open	4	
2/10/2005	Upper Douglas Creek	4472	4474	Open	2	
2/10/2005	Upper Douglas Creek	4464	4466	Open	2	
2/10/2005	Upper Douglas Creek	4454	4456	Open	2	
2/10/2005	Upper Douglas Creek	4280	4292	Open	12	
1/29/2005	Wasatch	5940	5944	Open	2	120
1/29/2005	Wasatch	5928	5932	Open	2	120

FIML NATURAL RESOURCES, LLC

October 13, 2006

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, UT 84114-5801

Attn.: Ms. Carol Daniels

RE: Sundry-Workover Operations Report

Dear Ms. Daniels:

Enclosed are the Workover Operations Reports for the following wells"

Ute Tribal 11-29-54
Ute Tribal 8-31-55
Ute Tribal 6-24-54
Ute Tribal 13-18-54
Ute Tribal 3-35-54
Ute Tribal 13-22-1319

If any questions arise or additional information is required, please contact me at 303-893-5090.

Sincerely,



Cassandra Parks

/cp

Enclosures:

RECEIVED

OCT 16 2006

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. 14-20-H62-5060
2. Name of Operator FIML Natural Resources, LLC		6. If Indian, Allottee or Tribe Name Ute Tribe
3a. Address 410 17th Street, Suite 900 Denver, CO 80202	3b. Phone No. (include area code) 303-893-5083	7. If Unit or CA/Agreement, Name and/or No.
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W		8. Well Name and No. Ute Tribal # 8-31-55
		9. API Well No. 43-013-32673
		10. Field and Pool, or Exploratory Area Undesignated
		11. County or Parish, State Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Produced water from the Ute Tribal 8-31-55 will be hauled to R.N. Industries Bluebell disposal facility located in Section 4, T-02S, R-02W, Duchesne County, Utah or Water Disposal Inc. Roosevelt disposal facility located in Sec 32 T-01S, R-01W, Duchesne County, Utah.

**BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93**

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

14. I hereby certify that the foregoing is true and correct Name (Printed/Typed) Cassandra Parks		Title Operations Assistant
Signature 		Date 1/23/2007

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Title Office	Date
--	---------------------	------

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED

JAN 24 2007

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007**SUNDRY NOTICES AND REPORTS ON WELLS****Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.****SUBMIT IN TRIPLICATE- Other instructions on reverse side.**1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator **FIML Natural Resources, LLC**3a. Address
410 17th Street, Suite 900 Denver, CO 802023b. Phone No. (include area code)
303-893-50834. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Produced water from the Ute Tribal 8-31-55 will be hauled to R.N. Industries Bluebell disposal facility located in Section 4 T-02S, R-02W, Duchesne County, Utah or Water Disposal Inc. Roosevelt disposal facility located in Sec 32 T-01S, R-01W, Duchesne County, Utah or MC & MC Disposal Vernal disposal facility located in Sec 12 T-06S 19E, Duchesne County, Utah.

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Cassandra ParksTitle **Operations Assistant**

Signature

Date

2/28/2007**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by _____

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

(Instructions on page 2)

MAR 05 2007

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007**SUNDRY NOTICES AND REPORTS ON WELLS****Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.****SUBMIT IN TRIPLICATE- Other instructions on reverse side.**1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator **FIML Natural Resources, LLC**3a. Address
410 17th Street, Suite 900 Denver, CO 802023b. Phone No. (include area code)
303-893-5083

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION

TYPE OF ACTION

☒ Notice of Intent☐ Subsequent Report☐ Final Abandonment Notice☐ Acidize☐ Alter Casing☐ Casing Repair☐ Change Plans☐ Convert to Injection☐ Deepen☐ Fracture Treat☐ New Construction☐ Plug and Abandon☐ Plug Back☐ Production (Start/Resume)☐ Reclamation☐ Recomplete☐ Temporarily Abandon☐ Water Disposal☐ Water Shut-Off☐ Well Integrity☒ Other **Squeeze**

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

FIML Natural Resources, LLC intends to run a cement bond log on the Ute Tribal 8-31-55 to determine top of cement. Top of cement must be above 1897' to meet BLM requirements. If top of cement is not above 1897', FIML will squeeze in order to bring top of cement above 1897'. The proposed procedure is attached.

**BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93**

COPY SENT TO OPERATOR

Date: 10-2-07
Initials: RMAccepted by the
Utah Division of
Oil, Gas and MiningDate: 9/28/07
By: [Signature]Federal Approval Of This
Action Is Necessary

14. I hereby certify that the foregoing is true and correct.
Name (Printed/Typed)

Cassandra ParksTitle **Operations Assistant**

Signature

[Signature]

Date

9/10/2007**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED**SEP 11 2007**

DIV. OF OIL, GAS & MINING

BLM TOC CBL/GR SQUEEZE PROCEDURE

PROPOSAL:

BLM has requested that CBL/GR log be re-run to determine TOC. Well will be squeezed cemented in the 5-1/2" casing annulus in an attempt to bring TOC above 1897' if required. FIML proposes to bring TOC to surface if a squeeze is required. Temperature survey or CBL/GR will be run to verify TOC if squeeze was performed.

PROCEDURE:

1. MIRUCU, pump and tank.
2. Pump 40 bbls. "HOT" 3.0% KCL water containing corrosion Inhibitor and chlorine tablets down 2-7/8" x 5-1/2" annulus. TOH with rods and insert pump. NU 2K-5K psi. double ram BOPE and TOH with 2-7/8", 6.5#, J-55, EUE, 8rd. tubing string (SLM while TOH). Make sand line run to check PBD. Last PBD check @ 6170' (bailer run) on 02/27/06. Inspect all tubular's closely while TOH.
3. Make 4-3/4" bit and 5-1/2" casing scrapper run to approximately 3800'. TIH with RBP on 2 7/8" tubing string and set RBP @ approximately 3770'. Spot 15' of 20/40 mesh sand on top of RBP neck. Pull 60' above 20/40 mesh sand cap and circulate at least 2 surface to surface volumes. TOH with RBP setting/retrieving tool.
4. RU 2K-5K psi. lubricator and wireline unit. Re-run CBL/GR from approximately 3755' to surface and locate TOC (Halliburton Services CBL/GR log ran on 01/28/0 indicated TOC @ 3430' (questionable pick). **TOC MUST BE @ 1897' TO COMPLY WITH BLM REQUIREMENTS. TOC MUST BE VERIFIED WITH VERNAL, UT BLM OFFICE (Mr. Jim Ashley, Office: 435/781-4470. Cell: 435/828-7874) BEFORE CONTINUING ANY ADDITIONAL WORK.**
Proceed to step #5 if TOC meets BLM requirements.
Proceed to CEMENT & SQUEEZE PROCEDURE if TOC does not comply with BLM requirements
5. TIH with RBP retrieving tool and circulate sand cap off RBP. Swab down 5-1/2" casing string to RBP, release RBP and TOH.
6. Run original tubing string (re-torque each connection while TIH), pump and rod string configuration. Replace worn tubing and rods as needed. Run scrapped rods across worn tubing/rod interval(s).
7. Return well to production.

CEMENT SQUEEZE PROCEDURE:

1. Shoot 4 – squeeze holes @ 3400' (unless CBL/GR log indicates a different TOC/formation bridging).
2. TIH with 5-1/2" tension set packer on 2-7/8" tubing string (re-torque each connection while TIH). Set packer at approximately 3150'. Open casing head valve between 5-1/2" x 8-5/8" annulus. Establish an injection rate, monitor returns between 5-1/2" x 8-5/8" annulus.
3. RU Big-4 Cementers (435/789-1735, Blinn Tinney) and pump/squeeze as follows:
 - a) 10.0 bbls. fresh water.

- b) Lead slurry consisting of **265** sx. (180.3 bbls) "Light" cement containing 16% gel, 10.0 pps. gilsonite & 3.0% salt (BWOW). Wt: 11.0 ppg. Yield: 3.82 ft³/sk. MWR: 23.0 gps.
- c) Tail slurry consisting of **50** sx. (10.2 bbls) class "G" cement containing 2.0% CaCl₂. Wt: 15.8 ppg. Yield: 1.15 ft³/sk. MWR: 5.0 gps.
- d) Displace cement with fresh water to within 80' of squeeze perforations.
- e) WOC a minimum of 6 hours. TOH with 2-7/8" tubing string and tension set packer.

NOTE: Gather dry and wet cement samples.

- 4. Make sure hole is full of 3% KCL water. WOC a minimum of 48 hours (as per BLM request) and run CBL/GR log from top of cement plug in 5-1/2" casing to surface to verify TOC. **TOC MUST BE VERIFIED WITH VERNAL, UT BLM OFFICE (Mr. Jim Ashley, Office: 435/781-4470. Cell: 435/828-7874) BEFORE DRILLING OUT CEMENT PLUG.**
- 5. TIH with 4-3/4" tri-cone bit and drill out cement squeeze. Circulate hole clean and pressure test squeeze perforations to 1500 psi. TOH and make bit and 5-1/2" casing scrapper run to approximately 3500'. Circulate hole clean and pressure test squeeze perforations to 1500 psi.
- 6. TIH with RBP retrieving tool and circulate sand cap off RBP. Swab down 5-1/2" casing string to RBP, release RBP and TOH.
- 7. Run original tubing string (re-torque each connection while TIH), pump and rod string configuration. Replace worn tubing and rods as needed. Run scrapped rods across worn tubing/rod interval(s).
- 8. Return well to production.

U.T. 8-31-55 BLM TOC. .DOC
Adb (09/05/07)

FIML NATURAL RESOURCES, LLC

September 10, 2007

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, UT 84114-5801

Attn.: Ms. Carol Daniels

RE: Ute Tribal #8-31-55
SENE Sec 31 T-5S R-5W
Duchesne County, Utah


Dear Ms. Daniels:

Enclosed is the following information concerning the referenced well.

Sundry Notice-Notice of Intent to Squeeze

If any questions arise or additional information is required, please contact me at 303-893-5090.

Sincerely,



Cassandra Parks
Operations Assistant

/cp
Enclosures:

RECEIVED

SEP 11 2007

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007**SUNDRY NOTICES AND REPORTS ON WELLS***Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.***SUBMIT IN TRIPLICATE- Other instructions on reverse side.**1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator **FIML Natural Resources, LLC**3a. Address
410 17th Street, Suite 900 Denver, CO 802023b. Phone No. (include area code)
303-893-5083

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Site Security Diagram
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Attached is an updated site security diagram for the Ute Tribal 8-31-55.

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)**Cassandra Parks**Title **Operations Assistant**

Signature

Date

9/18/2007**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date


Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations or to furnish any information in any manner within its jurisdiction.

(Instructions on page 2)

OCT 10 2007

DIV. OF OIL, GAS & MINING



POSITION OF VALVES AND USE OF SEALS DURING PRODUCTION/BLOWDOWN

Valves	Line Purpose	Position	Seal Installed
D	Drain	Closed	Yes
S	Sales	Closed	Yes
I	Inlet	Open	No
O	Overflow	Open/Closed	No
B	Blowdown	Open/Closed	No

POSITION OF VALVES AND USE OF SEALS DURING SALES

Valves	Line Purpose	Position	Seal Installed
D	Drain	Closed	Yes
S	Sales	Open	No
I	Inlet	Closed	Yes
O	Overflow	Closed	Yes
B	Blowdown	Closed	Yes

POSITION OF VALVES AND USE OF SEALS DURING WATER DRAIN

Valves	Line Purpose	Position	Seal Installed
D	Drain	Open	No
S	Sales	Closed	Yes
I	Inlet	Closed	No
O	Overflow	Closed	No
B	Blowdown	Closed	No

FIML NATURAL RESOURCES, LLC

December 5, 2007

Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, UT 84114-5801

Attn.: Ms. Carol Daniels

RE: Ute Tribal #8-31-55
SENE Sec 31 T-5S R-5W
Duchesne County, Utah

Dear Ms. Daniels:

Enclosed is the following information concerning the referenced well.

Sundry Notice-Subsequent Squeeze Report

If any questions arise or additional information is required, please contact me at 303-893-5090.

Sincerely,



Cassandra Parks
Operations Assistant

/cp
Enclosures:

RECEIVED

DEC 06 2007

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007**SUNDRY NOTICES AND REPORTS ON WELLS****Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.****SUBMIT IN TRIPLICATE- Other instructions on reverse side.**1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator **FIML Natural Resources, LLC**3a. Address
410 17th Street, Suite 900 Denver, CO 802023b. Phone No. (include area code)
303-893-50834. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Squeeze
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Workover operations were performed on this well from 10/31-11/9/2007. The rods & tbg were flushed with 3% KCL water. Then a cement bond log was run to determine TOC. TOC was @ 3290'. 4 squeeze holes were shot @ 3290'. A squeeze job was performed using 265 sks "Light" cmt. Another CBL was run and found TOC @ 637'. This meets BLM requirements. Hot Oil Express then pumped 60 bbl treated 3% KCL water down casing while cutting wax in tby ID w/ sandline & paraffin cutter. It was treated w/ KCL water until the TAC was set and released without any problems. Tubing was set at 6068.68', and well was put back on production. The complete composite report is attached.

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

RECEIVED**DEC 06 2007****DIV. OF OIL, GAS & MINING**

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Cassandra ParksTitle **Operations Technician**

Signature

Date

12/5/2007**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

Date	Description
3/3/2006	<p>SICP 1050. SITP: 0</p> <p>Open csg to flat tank and blow pressure down. RU Hot Oil express and wash floor. Tools down. Well head. Suck collar out, pump 30 bbls 3% KCl water down csg. ND BOPs and set TAC @ 10000 tension. Nipple up wellhead pick pump @ prime. Run 2 1/2 x 1 1/2 x 12 x 15 x 16. Insert pump</p> <p>4 - 1 1/2 x 25 kbars 154 - 3/4 x 25 slick rods 80 - 7/8 x 25 guided rods 2 x 7/8 pony 1 1-1/2 x 25' polish rod w/ 1 3/4 liner</p> <p>Seat pump and space out. Fill hole with 12 bbls of 3% KCl. Stroke tested pump up to 1000. Test ok. Hang well @ 1600 hrs 3/3/06. Turn well over to pumpers. RD rig.</p> <p>-</p>
3/4/2006	Produced 0 BO, 70 BW and 55 MCF in 16 hrs. with the casing on a 12/64" choke flowing at 100#.
3/5/2006	Produced 0 BO, 120 BW and 76 MCF in 24 hrs. with the casing on a 12/64" choke flowing at 125#.
3/6/2006	Produced 0 BO, 110 BW and 85 MCF in 24 hrs with the casing on a 12/64" choke flowing at 140#. Shut well in due to a tie-in being done on Berry's sales line.
4/6/2006	Move in Basic Rig 1604 and rig up. Remove head from pumping unit and unseat pump. Shut well in for night. Will have Hot Oil unit in morning.
10/31/2007	<p>MIRU Leed Energy #693, pmp & tnk. Removed horses head & unseated pmp. Flushed rods w/ 30 bbls, treated 3% KCL wtr heated to 250°. Soft seated pmp. Filled tbg w/ 20 bbls treated 3% KCL wtr & press tstd tbg string to 1,000 psi (ok). Unseated pmp & TOH visually inspecting rods for wear. Pulled 1275' of rods & re-flushed rods w/ 15 bbls treated, 3% KCL water heated to 250°. Pulled an additional 2475' of rods & re-flushed rods w/ 15 bbl treated, 3% KCL wtr heated to 250°. TLWTR: 80 bbl. Fin TOH / rods & pmp. NO visible sign of scale on pmp or screen.</p> <p>Will have to change out approximately, 55 3/4" rod boxes & install rod guides f/ approximately 5,700' to 5,100' (=/- 24 guides). SWI @ 17:30 hrs, 10/31/07.</p> <p>-</p>
11/1/2007	<p>13 1/2 hr SITP/SICP: 0 psi/300 psi. Bled pressure off casing in 1 hr. RU pump and lines. Pumped 40 bbls, treated, 3% KCL water heated to 240° down casing.</p> <p>NU Weatherford 7-1/16" x 5K# Shaffer double gate BOP. Released TAC and TOH w/ 194 jts. 2-7/8", 6.5#, J-55, EUE, 8rd. tubing (SLM: 6,031.25'). Tubing OD looks good and ID has minimal amount of rod cutting. TIH w/ Halliburton model "BV" RBP and set RBP @ 3760'. TOH to 3700' and spotted 15' sand plug on RBP. TOH to 3640' and circulated 2 surface to surface volumes w/ treated, 3% KCL water heated to 230°.</p> <p>RU Casedhole Solutions wireline unit and ran CBL/GR log from 3,695' to surface. CBL/GR log indicated TOC @ 3,290'. Shot 4 squeeze holes @ 3,250', had to work squeeze gun through wax/grease plug @ 400'. RD and released Casedhole Solutions wireline unit.</p> <p>CIWSDFN @ 20:00 hrs, 11/1/07.</p> <p>-</p>

Date

11/9/2007

Description

13-1/2 hr SITP/SICP: 35 psi/500 psi. Bled press off well & pmpd 30 bbls treated 3% KCL wtr dwn csg to control well. NDBOP & set TAC w/ 10K# tension. Dumped 20 gal diesel dwn annulus & flanged up WH. RU swab. IFL @ 3200'. Made 5 swab runs. Rec 25 BLW w/ no sign of debris in fluid. Made sand line run & tagged PBTD @ +/- 6161'. Ran pmp & rods. Changed out 40, worn, 3/4" rod boxes scattered f/ 4500-5775' & install 50 snap-on guides through same area. Re-torqued all connections while TIH. Soft seated pmp & filled tbg w/ 20 bbl, treated, 3% KCL wtr & stroke tstd pmp to 900 psi, ok. Turned well to prod @ 18:00 hrs, 11/09/2007. TLWTR: 264 bbl. Will RDMOCU on Monday, 11/12/07,

Production Tubing String Detail (top to btm):

194 jts	2-7/8", 6.5#, J-55, EUE, 8rd tbg	6021.25'
1	2-7/8" PSN (2.28" ID)	1.10'
1	Weatherford model "B-2", TAC (45K shear)	2.66'
1 jt	2-7/8", 6.5#, J-55, EUD, 8rd tbg (rod cut)	31.22'
1	2-7/8", f/o, notched collar	00.45'
<hr/>		
195 jts	Total	6056.68'
	KB Correction	+ 12.00'
	EOT:	6068.68'
	TAC:	6034.35'
	PSN:	6033.25

Pump & Rod Detail (top to btm)

1	1-1/2" x 22' polish rod w/ 1-3/4" x 10' liner
1	7/8" grade "D" pony rod (4')
80	7/8" grade "D" ros w/ 4 guides per rod
155	3/4" grade "D" slick rods (50 w/ 1 snap-on guide per rod)
4	1-1/2" K-Brs w/ 5 stabilizers
1	Poor-boy back off tool (see note below)
1	2-1/2" x 1-1/2" x 15', Weatherford, RHAC, THD, single valve pmp (#1617)

Note: To release Poor-boy back off tool, stack out or pull tension & rotate to right!

-

Casing

Date In	Type	Hole Diam	Size	Weight	Grade	Top	Set Depth	Total Jts Run	Total Csg Footage	TD
5/4/2004	Intermediate	7.875	5.5	15.50	J-55	0.00	0.00	149	0.00	0.00
11/26/2004	Production	12.25	8.625	24.00	J-55	7,822.00	311.10	7	310.10	330.00
12/8/2004	Conductor	7.725	5.5	15.50	J-55	0.00	6,281.46	150	0.00	6,424.00
12/11/2004	Conductor	7.875	5.5	15.50	J-55	7,822.00	6,271.46	146	6,269.46	6,292.00

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other2. Name of Operator
FIML Natural Resources, LLC3a. Address
410 17th Street, Suite 900 Denver, CO 802023b. Phone No. (include area code)
303-893-5090

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Produced water from this well will be hauled to R.N. Industries Bluebell disposal facility located in Section 4 T-02S, R-02W, Duchesne County, Utah or Water Disposal Inc. Roosevelt disposal facility located in Sec 32 T-01S, R-01W, Duchesne County, Utah or MC & MC Disposal Vernal disposal facility located in Sec 12 T-06S 19E, Duchesne County, Utah, or Dalbo Inc. disposal facility located in Sec 2 T-06S, R-20E, Duchesne County, Utah.

BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Cassandra ParksTitle **Regulatory Specialist**

Signature



Date

3/5/2008**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED**MAR 07 2008**

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator **FIML Natural Resources, LLC**

3a. Address
410 17th Street, Suite 900 Denver, CO 80202

3b. Phone No. (include area code)
303-893-5090

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SENE 1980' FNL 660' FEL Sec 31 T-5S, R-5W

5. Lease Serial No.

14-20-H62-5060

6. If Indian, Allottee or Tribe Name

Ute Tribe

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Ute Tribal # 8-31-55

9. API Well No.

43-013-32673

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Duchesne

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Produced water from this well will be hauled to R.N. Industries Bluebell disposal facility located in Section 4 T-02S, R-02W, Duchesne County, Utah or Water Disposal Inc. Roosevelt disposal facility located in Sec 32 T-01S, R-01W, Duchesne County, Utah or MC & MC Disposal Vernal disposal facility located in Sec 12 T-06S 19E, Duchesne County, Utah, or Dalbo Inc. disposal facility located in Sec 2 T-06S, R-20E, Duchesne County, Utah or Brennan Bottom Disposal located in Sec 19 T-6S, R-21E, Duchesne County, Utah or LaPoint Recycle & Storage located in Sec 12 T-5S, R19E, Uintah County, Utah.

**BIA Nationwide Oil & Gas Lease Bond No. 8191-82-71.
State of Utah, Division of Oil, Gas & Mining Surety Bond No. 8193-15-93**

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Cassandra Parks

Title **Regulatory Specialist**

Signature



Date

5/6/2008

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED
MAR 10 2008

DIV. OF OIL, GAS & MINING

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET (for state use only)

ROUTING

CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

8/1/2012

FROM: (Old Operator): N2530- FIML Natural Resources, LLC 410 17th Street, Suite 900 Denver, CO 80202 Phone: 1 (303) 893-5073	TO: (New Operator): N2480- Berry Petroleum Company 1999 Broadway, Suite 3700 Denver, CO 80202 Phone: 1 (303) 999-4400
---	--

CA No.			Unit:				N/A	
WELL NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
See Attached List								

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/17/2012
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/17/2012
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 10/12/2012
- Is the new operator registered in the State of Utah: _____ Business Number: 5307764-0143
- (R649-9-2) Waste Management Plan has been received on: Yes
- Inspections of LA PA state/fee well sites complete on: N/A
- Reports current for Production/Disposition & Sundries on: 10/12/2012
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM N/A BIA Not Yet
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: N/A
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: N/A
- Underground Injection Control ("UIC")** Division has approved UIC Form 5 Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 10/12/2012
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 10/12/2012
- Bond information entered in RBDMS on: 10/12/2012
- Fee/State wells attached to bond in RBDMS on: N/A
- Injection Projects to new operator in RBDMS on: N/A
- Receipt of Acceptance of Drilling Procedures for APD/New on: 9/28/2012

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: N/A
- Indian well(s) covered by Bond Number: B0005647
- (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number N/A
- The **FORMER** operator has requested a release of liability from their bond on: N/A

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

FIML Natural Resources, LLC (N2530) to Berry Petroleum Company (N2480)

Well Name	Sec	TWP	RNG	API Number	Entity Number	Lease	Well Type	Well Status	Confidential
UTE TRIBAL 11-11-54	11	050S	040W	4301350861		Indian	OW	APD	C
VIEIRA TRIBAL 4-4-54	04	050S	040W	4301350997		Indian	OW	APD	C
MYRIN TRIBAL 15-10-55	10	050S	050W	4301351024		Indian	OW	APD	C
STATE TRIBAL 15-6-54	06	050S	040W	4301351227		Indian	OW	APD	C
STATE TRIBAL 8-7-54	07	050S	040W	4301351228		Indian	OW	APD	C
STATE TRIBAL 12-1-55	01	050S	050W	4301351229		Indian	OW	APD	C
STATE TRIBAL 11-2-55	02	050S	050W	4301351230		Indian	OW	APD	C
STATE TRIBAL 12-3-55	03	050S	050W	4301351236		Indian	OW	APD	C
UTE TRIBAL 4-9-55	09	050S	050W	4301351238		Indian	OW	APD	C
UTE TRIBAL 15-5-55	05	050S	050W	4301351239		Indian	OW	DRL	C
UTE TRIBAL 16-11-55	11	050S	050W	4301350888	18707	Indian	OW	DRL	C
UTE TRIBAL 16-3-54	03	050S	040W	4301351226	18664	Indian	OW	DRL	C
UTE TRIBAL 11-4-55	04	050S	050W	4301351237	18663	Indian	OW	DRL	C
UTE TRIBAL 3-29	29	050S	040W	4301332193	13042	Indian	OW	P	
UTE TRIBAL 5-29-54	29	050S	040W	4301332525	14045	Indian	OW	P	
UTE TRIBAL 15-29-54	29	050S	040W	4301332561	14316	Indian	OW	P	
UTE TRIBAL 7-29-54	29	050S	040W	4301332562	14354	Indian	OW	P	
UTE TRIBAL 11-29-54	29	050S	040W	4301332563	14337	Indian	OW	P	
UTE TRIBAL 13-29-54	29	050S	040W	4301332564	14315	Indian	OW	P	
UTE TRIBAL 4-29-54	29	050S	040W	4301332565	14367	Indian	OW	P	
UTE TRIBAL 9-29-54	29	050S	040W	4301332566	14369	Indian	OW	P	
UTE TRIBAL 1-35-54	35	050S	040W	4301332567	14266	Indian	OW	P	
UTE TRIBAL 11-13-54	13	050S	040W	4301332568	14281	Indian	OW	P	
UTE TRIBAL 2-24-54	24	050S	040W	4301332569	14314	Indian	OW	P	
UTE TRIBAL 6-24-54	24	050S	040W	4301332570	14299	Indian	OW	P	
UTE TRIBAL 13-18-54	18	050S	040W	4301332571	14388	Indian	OW	P	
UTE TRIBAL 12-29-54	29	050S	040W	4301332572	14336	Indian	OW	P	
UTE TRIBAL 4-24-54	24	050S	040W	4301332573	14247	Indian	OW	P	
UTE TRIBAL 8-31-55	31	050S	050W	4301332673	14407	Indian	OW	P	
UTE TRIBAL 3-35-54	35	050S	040W	4301332675	14656	Indian	OW	P	
UTE TRIBAL 2-30-55	30	050S	050W	4301332680	14427	Indian	OW	P	
UTE TRIBAL 7-35-54	35	050S	040W	4301332774	15019	Indian	OW	P	
UTE TRIBAL 16-24-54	24	050S	040W	4301332775	14762	Indian	OW	P	
UTE TRIBAL 14-25-54	25	050S	040W	4301332776	14753	Indian	OW	P	
UTE TRIBAL 16-25-54	25	050S	040W	4301332779	15078	Indian	OW	P	
UTE TRIBAL 8-25-54	25	050S	040W	4301332780	15280	Indian	OW	P	
UTE TRIBAL 9-35-54	35	050S	040W	4301332781	15535	Indian	OW	P	
MYRIN TRIBAL 14-19-55	19	050S	050W	4301332782	15184	Indian	OW	P	
UTE TRIBAL 6-30-55	30	050S	050W	4301332783	15163	Indian	OW	P	
UTE TRIBAL 15-35-54	35	050S	040W	4301332804	15185	Indian	OW	P	
UTE TRIBAL 5-35-54	35	050S	040W	4301332805	15485	Indian	OW	P	
UTE TRIBAL 13-35-54	35	050S	040W	4301332806	15292	Indian	OW	P	
UTE TRIBAL 11-35-54	35	050S	040W	4301332807	15317	Indian	OW	P	
UTE TRIBAL 11-25-54	25	050S	040W	4301332856	15430	Indian	OW	P	
UTE TRIBAL 3-30-55	30	050S	050W	4301332862	15340	Indian	OW	P	
UTE TRIBAL 7-19-55	19	050S	050W	4301332863	15279	Indian	OW	P	
UTE TRIBAL 8-19-55	19	050S	050W	4301332864	15241	Indian	OW	P	
MOON TRIBAL 10-2-54	02	050S	040W	4301332931	15429	Indian	OW	P	
UTE TRIBAL 10-24-54	24	050S	040W	4301332932	15364	Indian	OW	P	
UTE TRIBAL 8-24-54	24	050S	040W	4301332933	15402	Indian	OW	P	
MYRIN TRIBAL 16-19-55	19	050S	050W	4301332934	15339	Indian	OW	P	
UTE TRIBAL 2-31-55	31	050S	050W	4301332935	15428	Indian	OW	P	
UTE TRIBAL 10-31-55	31	050S	050W	4301332936	15354	Indian	OW	P	
ST TRIBAL 7-18-54	18	050S	040W	4301332952	15724	Indian	OW	P	
ST TRIBAL 5-18-54	18	050S	040W	4301332953	15781	Indian	OW	P	
UTE TRIBAL 14-18-55	18	050S	050W	4301332984	15671	Indian	OW	P	
UTE TRIBAL 14-24-56	24	050S	060W	4301332988	15740	Indian	OW	P	

FIML Natural Resources, LLC (N2530) to Berry Petroleum Company (N2480)

UTE TRIBAL 7-24-56	24	050S	060W	4301332989	15782	Indian	OW	P	
UTE TRIBAL 11-25-56	25	050S	060W	4301332990	15627	Indian	OW	P	
UTE TRIBAL 7-25-56	25	050S	060W	4301332991	15617	Indian	OW	P	
UTE TRIBAL 5-25-56	25	050S	060W	4301332992	15648	Indian	OW	P	
UTE TRIBAL 3-25-56	25	050S	060W	4301332993	15561	Indian	OW	P	
UTE TRIBAL 10-12-55	12	050S	050W	4301333055	15618	Indian	OW	P	
UTE TRIBAL 5-13-54	13	050S	040W	4301333075	15873	Indian	OW	P	
UTE TRIBAL 16-29-54	29	050S	040W	4301333076	17074	Indian	OW	P	
UTE TRIBAL 12-18-54	18	050S	040W	4301333077	15575	Indian	OW	P	
UTE TRIBAL 2-29-54	29	050S	040W	4301333153	15919	Indian	OW	P	
UTE TRIBAL 14-29-54	29	050S	040W	4301333154	15831	Indian	OW	P	
UTE TRIBAL 10-29-54	29	050S	040W	4301333155	15847	Indian	OW	P	
UTE TRIBAL 6-29-54	29	050S	040W	4301333172	15846	Indian	OW	P	
UTE TRIBAL 1A-29-54	29	050S	040W	4301333393	17075	Indian	OW	P	
UTE TRIBAL 1-31-55	31	050S	050W	4301333501	17104	Indian	OW	P	
UTE TRIBAL 9-31-55	31	050S	050W	4301333508	17103	Indian	OW	P	
S BRUNDAGE UTE TRIBAL 1-29	29	050S	040W	4301330964	2621	Indian	OW	PA	

RECEIVED

SEP 17 2012

Form 3160-5
(August 2007)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

DIV. OF OIL, GAS & MINING

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010**SUNDRY NOTICES AND REPORTS ON WELLS**
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.5. Lease Serial No.
See Attached List

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE – Other Instructions on page 2.

1. Type of Well

☒ Oil Well ☒ Gas Well ☐ Other2. Name of Operator
FIML Natural Resources, LLC (FNR)3a. Address
410 17th Street, Suite 900 Denver Colorado 802023b. Phone No. (include area code)
303-893-5073

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.

9. API Well No.

10. Field and Pool or Exploratory Area

11. Country or Parish, State
Duchesne, Utah**12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Change of Operator</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

Effective August 1, 2012 FIML Natural Resources, LLC (FNR) has sold the wells on the attached list to:

N2530
Berry Petroleum Company
1999 Broadway, Suite 3700
Denver, Colorado 80202
303-999-4400 N2480

Ann O. Hummer
VICE PRESIDENT & GENERAL COUNSEL

Bond Number:
B0005647

APPROVED

OCT 12 2012

DIV. OIL GAS & MINING
BY: *Rachel Medina*

14. I hereby certify that the foregoing is true and correct.

Name (Printed/Typed)
Stephen R Winslow

Title President

Signature

Date

9-4-12

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

Name	Well Loc	Section	Twp	Rge	County	API No	Lease
MOON TRIBAL 10-2-54	NWSE	2	5S	4W	Duchesne	43-013-32931	14-20-H62-3404
MYRIN TRIBAL 14-19-55	SESW	19	5S	5W	Duchesne	43-013-32782	14-20-H62-5058
MYRIN TRIBAL 16-19-55	SESE	19	5S	5W	Duchesne	43-013-32934	14-20-H62-5058
STATE TRIBAL 05-18-54	SWNW	18	5S	4W	Duchesne	43-013-32953	14-20-H62-5035
STATE TRIBAL 07-18-54	SWNE	18	5S	4W	Duchesne	43-013-32952	14-20-H62-5035
UTE TRIBAL 01-29-54 (PA)	NENE	29	5S	4W	Duchesne	43-013-30964	14-20-H62-5036
UTE TRIBAL 01-31-55	NENE	31	5S	5W	Duchesne	43-013-33501	14-20-H62-5060
UTE TRIBAL 01-35-54	NENE	35	5S	4W	Duchesne	43-013-32567	14-20-H62-5032
UTE TRIBAL 02-24-54	NWNE	24	5S	4W	Duchesne	43-013-32569	14-20-H62-4716
UTE TRIBAL 02-29-54	NWNE	29	5S	4W	Duchesne	43-013-33153	14-20-H62-5036
UTE TRIBAL 02-30-55	NWNE	30	5S	5W	Duchesne	43-013-32680	14-20-H62-5059
UTE TRIBAL 02-31-55	NWNE	31	5S	5W	Duchesne	43-013-32935	14-20-H62-5060
UTE TRIBAL 03-25-56	NENW	25	5S	6W	Duchesne	43-013-32993	14-20-H62-5065
UTE TRIBAL 03-29	NENW	29	5S	4W	Duchesne	43-013-32193	14-20-H62-3416
UTE TRIBAL 03-30-55	NESW	30	5S	5W	Duchesne	43-013-32862	14-20-H62-5059
UTE TRIBAL 03-35-54	NENW	35	5S	4W	Duchesne	43-013-32675	14-20-H62-5053
UTE TRIBAL 04-24-54	NWNW	24	5S	4W	Duchesne	43-013-32573	14-20-H62-4716
UTE TRIBAL 04-29-54	NWNW	29	5S	4W	Duchesne	43-013-32565	14-20-H62-5036
UTE TRIBAL 05-13-54 (CO1)	SWNW	13	5S	4W	Duchesne	43-013-33075	14-20-H62-4894
UTE TRIBAL 05-25-56	SWNW	25	5S	6W	Duchesne	43-013-32992	14-20-H62-5065
UTE TRIBAL 05-29-54	SWNW	29	5S	4W	Duchesne	43-013-32525	14-20-H62-5032
UTE TRIBAL 05-35-54	SWNW	35	5S	4W	Duchesne	43-013-32805	14-20-H62-5053
UTE TRIBAL 06-24-54	SESW	24	5S	4W	Duchesne	43-013-32570	14-20-H62-4716
UTE TRIBAL 06-29-54	SESW	29	5S	4W	Duchesne	43-013-33172	14-20-H62-5036
UTE TRIBAL 06-30-55	SESW	30	5S	5W	Duchesne	43-013-32783	14-20-H62-5059
UTE TRIBAL 07-19-55	SWNE	19	5S	5W	Duchesne	43-013-32863	14-20-H62-5058
UTE TRIBAL 07-24-56	SWNE	24	5S	6W	Duchesne	43-013-32989	14-20-H62-5064
UTE TRIBAL 07-25-56	SWNE	25	5S	6W	Duchesne	43-013-32991	14-20-H62-5065
UTE TRIBAL 07-29-54	SWNE	29	5S	4W	Duchesne	43-013-32562	14-20-H62-5036
UTE TRIBAL 07-35-54	SWNE	35	5S	4W	Duchesne	43-013-32774	14-20-H62-5053
UTE TRIBAL 08-19-55	SENE	19	5S	5W	Duchesne	43-013-32864	14-20-H62-5058
UTE TRIBAL 08-24-54	SENE	24	5S	4W	Duchesne	43-013-32933	14-20-H62-4716
UTE TRIBAL 08-25-54	SENE	25	5S	4W	Duchesne	43-013-32780	14-20-H62-3440
UTE TRIBAL 08-31-55	SENE	31	5S	5W	Duchesne	43-013-32673	14-20-H62-5032
UTE TRIBAL 09-29-54	NESE	29	5S	4W	Duchesne	43-013-32566	14-20-H62-5036
UTE TRIBAL 09-31-55	NESW	31	5S	5W	Duchesne	43-013-33508	14-20-H62-5060
UTE TRIBAL 09-35-54	NESE	35	5S	4W	Duchesne	43-013-32781	14-20-H62-5053
UTE TRIBAL 10-12-55	NWSE	12	5S	5W	Duchesne	43-013-33055	14-20-H62-5056
UTE TRIBAL 10-24-54	NWSE	24	5S	4W	Duchesne	43-013-32932	14-20-H62-4716
UTE TRIBAL 10-29-54	NWSE	29	5S	4W	Duchesne	43-013-33155	14-20-H62-5036
UTE TRIBAL 10-31-55	NWSE	31	5S	5W	Duchesne	43-013-32936	14-20-H62-5060
UTE TRIBAL 11-13-54	NESW	13	5S	4W	Duchesne	43-013-32568	14-20-H62-4894
UTE TRIBAL 11-25-54	NESW	25	5S	4W	Duchesne	43-013-32856	14-20-H62-3440
UTE TRIBAL 11-25-56	NESW	25	5S	6W	Duchesne	43-013-32990	14-20-H62-5065
UTE TRIBAL 11-29-54	NESW	29	5S	4W	Duchesne	43-013-32563	14-20-H62-5032
UTE TRIBAL 11-35-54	NESW	35	5S	4W	Duchesne	43-013-32807	14-20-H62-5053
UTE TRIBAL 12-18-54	NWSW	18	5S	4W	Duchesne	43-013-33077	14-20-H62-5035
UTE TRIBAL 12-29-54	NWSW	29	5S	4W	Duchesne	43-013-32572	14-20-H62-5036

Name	Well Loc	Section	Twp	Rge	County	API No	Lease
UTE TRIBAL 13-18-54	SWSW	18	5S	4W	Duchesne	43-013-32571	14-20-H62-5032
UTE TRIBAL 13-29-54	SWSW	29	5S	4W	Duchesne	43-013-32564	14-20-H62-5032
UTE TRIBAL 13-35-54	SWSW	35	5S	4W	Duchesne	43-013-32806	14-20-H62-5053
UTE TRIBAL 14-18-55	SESW	18	5S	5W	Duchesne	43-013-32984	14-20-H62-5057
UTE TRIBAL 14-24-56	SESW	24	5S	6W	Duchesne	43-013-32988	14-20-H62-5064
UTE TRIBAL 14-25-54	SESW	25	5S	4W	Duchesne	43-013-32776	14-20-H62-3440
UTE TRIBAL 14-29-54	SESW	29	5S	4W	Duchesne	43-013-33154	14-20-H62-5036
UTE TRIBAL 15-29-54	SWSE	29	5S	4W	Duchesne	43-013-32561	14-20-H62-5036
UTE TRIBAL 15-35-54	SWSE	35	5S	4W	Duchesne	43-013-32804	14-20-H62-5053
UTE TRIBAL 16-24-54	SESE	24	5S	4W	Duchesne	43-013-32775	14-20-H62-4716
UTE TRIBAL 16-25-54	SESE	25	5S	4W	Duchesne	43-013-32779	14-20-H62-3440
UTE TRIBAL 16-29-54	SESE	29	5S	4W	Duchesne	43-013-33076	14-20-H62-5036
UTE TRIBAL 1A-29-54	NENE	29	5S	4W	Duchesne	43-013-33393	14-20-H62-5036

MYRIN TRIBAL 15-10-55	SWSE	10	5S	5W	Duchesne	43-013-51024	
STATE TRIBAL 11-2-55	NESW	2	5S	5W	Duchesne	43-013-51230	
STATE TRIBAL 12-1-55	NWSW	1	5S	5W	Duchesne	43-013-51229	
STATE TRIBAL 12-3-55	NWSW	3	5S	5W	Duchesne	43-013-51236	
STATE TRIBAL 15-6-54	SWSE	6	5S	4W	Duchesne	43-013-51227	
STATE TRIBAL 8-7-54	SENE	7	5S	4W	Duchesne	43-013-51228	
UTE TRIBAL 11-11-54	NESW	11	5S	4W	Duchesne	43-013-50861	
UTE TRIBAL 11-4-55	NESW	4	5S	5W	Duchesne	43-013-51237	
UTE TRIBAL 15-5-55	SWSE	5	5S	5W	Duchesne	43-013-51239	
UTE TRIBAL 16-11-55	SESE	11	5S	5W	Duchesne	43-013-50888	
UTE TRIBAL 16-3-54	SESE	3	5S	4W	Duchesne	43-013-51226	
UTE TRIBAL 4-9-55	NWNW	9	5S	5W	Duchesne	43-013-51238	
VIEIRA TRIBAL 4-4-54	NENW	4	5S	4W	Duchesne	43-013-50997	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: See attached list
2. NAME OF OPERATOR: Berry Petroleum		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Rt 2 Box 7735 CITY Roosevelt STATE UT ZIP 84066		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (435) 722-1325		8. WELL NAME and NUMBER: See Attached List
4. LOCATION OF WELL FOOTAGES AT SURFACE: COUNTY: Duchesne		9. API NUMBER: Attached
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH		10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input checked="" type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Produced wastewater from Berry Petroleum Company wells (see attached well list) will be or have been used for injection in our enhanced oil recovery project(s) in the Brundage Canyon Field or they will be trucked to one of the following approved waste water disposal sites:

- R.N. Industries, Inc. Sec. 4, T2S, R2W, Bluebell
- MC & MC Disposal Sec. 12, T6S, R19E, Vernal
- LaPoint Recycle & Storage Sec. 12, T5S, R19E, LaPoint
- Water Disposal Inc. Sec. 32, T1S, R1W, Roosevelt
- ITL 4461 W 3000 So Roosevelt Location Pleasant Valley
- IWM PO Box 430 Altamont or 20250 W 2000 S Duchesne Location - Blue Bench
- Pro Water 12223 Highland Ave Ste B503 Rancho Cucamonga Ca 91739 Location - Blue Bench

COPY SENT TO OPERATOR

Date: 12-13-2012
Initials: KS

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: 12/11/12

NAME (PLEASE PRINT) Krista Mecham

By: [Signature] TITLE Sr. Regulatory & Permitting Tech

SIGNATURE

[Signature]

DATE 11/21/2012

(This space for State use only)

*Federal Approval of this action
required for Federal Wells.*

RECEIVED

DEC 06 2012

API	Well Name	Lease
43-013-32710	#1 DLB 12-15-56	Fee
43-013-33447	1-15-56 DLB	Fee
43-013-33378	14-11-56 DLB	Fee
43-013-30842	B C UTE TRIBAL 14-15	14-20-H62-3412
43-013-30841	B C UTE TRIBAL 16-16	14-20-H62-3413
43-013-30829	B C UTE TRIBAL 8-21	14-20-H62-3414
43-013-30755	BC UTE TRIBAL 4-22	14-20-H62-3415
43-013-33216	BERRY TRIBAL 1-23-54	14-20-H62-4943
43-013-33867	BERRY TRIBAL 2-34D-54	14-20-H62-4955
43-013-33384	BERRY TRIBAL 4-34-54	14-20-H62-4955
43-013-33381	BERRY TRIBAL 7-23-54	14-20-H62-4943
43-013-33383	BERRY TRIBAL 7-34-54	14-20-H62-4955
43-013-33417	BERRY TRIBAL 8-23D-54	14-20-H62-4943
43-013-33465	BERRY TRIBAL 9-23-54	14-20-H62-4943
43-013-33382	BERRY TRIBAL 9-34-54	14-20-H62-4955
43-013-33724	BERRY TRIBAL 10-23D-54	14-20-H62-4943
43-013-33422	BERRY TRIBAL 10-34D-54	14-20-H62-4955
43-013-33725	BERRY TRIBAL 11-23D-54	14-20-H62-4943
43-013-33529	BERRY TRIBAL 11-34D-54	14-20-H62-4955
43-013-50527	BERRY TRIBAL 12-34D-54	14-20-H62-4955
43-013-34043	BERRY TRIBAL 13-23-54	14-20-H62-4943
43-013-33989	BERRY TRIBAL 14-23D-54	14-20-H62-4943
43-013-33217	BERRY TRIBAL 15-23-54	14-20-H62-4943
43-013-33411	BERRY TRIBAL 15-34-54	14-20-H62-4955
43-013-33464	BERRY TRIBAL 16-34D-54	14-20-H62-4955
43-013-50524	FEDERAL 1-1D-64	UTU-77321
43-013-51142	FEDERAL 1-1D-65	UTU-77326
43-013-51232	FEDERAL 1-11-65	UTU-77330
43-013-50326	FEDERAL 10-1D-65	UTU-77326
43-013-33542	FEDERAL 10-2-65	UTU-77326
43-013-33386	FEDERAL 10-3-65	UTU-77326
43-013-50735	FEDERAL 10-6D-64	UTU-77322
43-013-33451	FEDERAL 11-10-65	UTU-77330
43-013-50327	FEDERAL 11-1D-65	UTU-77326
43-013-50763	FEDERAL 11-2D-65	UTU-77326
43-013-50565	FEDERAL 11-4D-64	UTU-77314
43-013-50348	FEDERAL 11-5D-64	UTU-8894A
43-013-34284	FEDERAL 11-6D-64	UTU-77322
43-013-50328	FEDERAL 12-1D-65	UTU-77326
43-013-50737	FEDERAL 12-3D-64	UTU-77321
43-013-50349	FEDERAL 12-5D-64	UTU-8894A
43-013-50261	FEDERAL 12-6D-64	UTU-77322
43-013-50730	FEDERAL 1-2D-64	UTU-77321
43-013-33966	FEDERAL 1-2D-65	UTU-77326
43-013-50329	FEDERAL 13-1D-65	UTU-77326
43-013-50337	FEDERAL 13-5D-64	UTU-8894A
43-013-50347	FEDERAL 13-6D-64	UTU-77322
43-013-50330	FEDERAL 14-1D-65	UTU-77326

43-013-50338	FEDERAL 14-5D-64	UTU-8894A
43-013-34285	FEDERAL 14-6D-64	UTU-77322
43-013-51175	FEDERAL 15-1D-65	UTU-77326
43-013-50764	FEDERAL 15-2D-65	UTU-77326
43-013-50553	FEDERAL 15-5D-65	UTU-77327
43-013-51176	FEDERAL 16-1D-65	UTU-77326
43-013-33490	FEDERAL 16-5-65	UTU-77327
43-013-50266	FEDERAL 1-6-64	UTU-77322
43-013-51233	FEDERAL 2-11D-65	UTU-77326
43-013-50759	FEDERAL 2-1D-65	UTU-77326
43-013-33385	FEDERAL 2-2-65	UTU-77326
43-013-34018	FEDERAL 2-2D-64	UTU-77321
43-013-34286	FEDERAL 2-6D-64	UTU-77322
43-013-51093	FEDERAL 3-12D-65	UTU-77326
43-013-50760	FEDERAL 3-1D-65	UTU-77326
43-013-34001	FEDERAL 3-2D-65	UTU-77326
43-013-50782	FEDERAL 3-4D-65	UTU-77327
43-013-34287	FEDERAL 3-5D-64	UTU-8894A
43-013-50268	FEDERAL 3-6D-64	UTU-77322
43-013-51094	FEDERAL 4-12D-65	UTU-77326
43-013-50736	FEDERAL 4-3D-64	UTU-77321
43-013-50521	FEDERAL 4-4D-65	UTU-77327
43-013-50263	FEDERAL 4-5D-64	UTU-8894A
43-013-50267	FEDERAL 4-6D-64	UTU-77322
43-013-51095	FEDERAL 5-12D-65	UTU-77330
43-013-50761	FEDERAL 5-1D-65	UTU-77326
43-013-33448	FEDERAL 5-3-64	UTU-77321
43-013-33450	FEDERAL 5-4-64	UTU-77326
43-013-33387	FEDERAL 5-4-65	UTU-77327
43-013-50259	FEDERAL 5-5D-64	UTU-8894A
43-013-33489	FEDERAL 5-6-65	UTU-77327
43-013-50269	FEDERAL 5-6D-64	UTU-77322
43-013-33491	FEDERAL 6-11-65	UTU-77330
43-013-51096	FEDERAL 6-12D-65	UTU-77330
43-013-32699	FEDERAL 6-1-65	UTU-77325
43-013-32557	FEDERAL 6-2-65	UTU-77326
43-013-50522	FEDERAL 6-3D-64	UTU-77321
43-013-34288	FEDERAL 6-5D-64	UTU-8894A
43-013-33745	FEDERAL 6-6D-64	UTU-77322
43-013-50566	FEDERAL 6-6D-65	UTU-77327
43-013-34061	FEDERAL 7-11D-65	UTU-77330
43-013-34015	FEDERAL 7-1D-65	UTU-77325
43-013-50734	FEDERAL 7-2D-64	UTU-77321
43-013-50525	FEDERAL 7-2D-65	UTU-77326
43-013-34065	FEDERAL 7-3D-65	UTU-77326
43-013-34020	FEDERAL 7-6D-64	UTU-77322
43-013-51232	FEDERAL 8-11D-65	UTU-77326
43-013-33449	FEDERAL 8-1-64	UTU-77321
43-013-50350	FEDERAL 8-1D-65	UTU-77326

43-013-33581	FEDERAL 8-2D-64	UTU-77321
43-013-50719	FEDERAL 8-2D-65	UTU-77326
43-013-50325	FEDERAL 8-6D-64	UTU-77322
43-013-50342	FEDERAL 9-1D-65	UTU-77326
43-013-50762	FEDERAL 9-2D-65	UTU-77326
43-013-51218	FEDERAL 9-6D-64	UTU-77322
43-013-32351	FOY TRIBAL 11-34-55	UTU-76968
43-013-33799	FOY TRIBAL 12H-33-55	FEE
43-013-51288	LC FEE 10-28D-56	FEE
43-013-50994	LC FEE 10-31D-45	FEE
43-013-50965	LC FEE 1-22-57	FEE
43-013-50718	LC FEE 1-22D-56	FEE
43-013-51371	LC FEE 1-31D-45	FEE
43-013-50929	LC FEE 13-29-45	FEE
43-013-50870	LC FEE 15-23D-56	FEE
43-013-50601	LC FEE 16-16D-56	FEE
43-013-50777	LC FEE 2-20D-56	FEE
43-013-33593	LC FEE 6-12-57	FEE
43-013-50867	LC FEE 8-28D-56	FEE
43-013-50928	LC FEE 8-29-45	FEE
43-013-50963	LC FEE 9-12D-57	FEE
43-013-51192	LC FEE 9-19-56	FEE
43-013-50602	LC TRIBAL 10-16D-56	14-20-H62-6301
43-013-50999	LC TRIBAL 10-21-56	14-20-H62-3433
43-013-33677	LC TRIBAL 11-17-56	14-20-H62-6300
43-013-50751	LC TRIBAL 11-3D-56	14-20-H62-6435
43-013-50780	LC TRIBAL 12-22D-56	14-20-H62-6302
43-013-33606	LC TRIBAL 12H-6-56	14-20-H62-5500
43-013-34282	LC TRIBAL 13-16D-56	14-20-H62-5623
43-013-33591	LC TRIBAL 13H-3-56	14-20-H62-6435
43-013-50776	LC TRIBAL 14-14D-56	14-20-H62-6436
43-013-50834	LC TRIBAL 14-15D-56	14-20-H62-6435
43-013-33492	LC TRIBAL 14-2-56	14-20-H62-6472
43-013-51030	LC TRIBAL 15-15D-56	14-20-H62-6435
43-013-50606	LC TRIBAL 15-22D-56	14-20-H62-6302
43-013-50871	LC TRIBAL 15-26-56	14-20-H62-6471
43-013-51132	LC TRIBAL 16-30D-56	2OG-000-5500
43-013-33608	LC TRIBAL 1-9-56	14-20-H62-5657
43-013-33538	LC TRIBAL 2-16D-56	14-20-H62-5623
43-013-51429	LC TRIBAL 2-28D-45	2OG-000-5500
43-013-50866	LC TRIBAL 2-28D-56	14-20-H62-6473
43-013-50925	LC TRIBAL 2-5D-56	14-20-H62-6432
43-013-50926	LC TRIBAL 2-9D-56	14-20-H62-5657
43-013-50598	LC TRIBAL 3-15D-56	14-20-H62-6435
43-013-33541	LC TRIBAL 3-17-56	14-20-H62-5655
43-013-50751	LC TRIBAL 3-21D-56	14-20-H62-3433
43-013-50976	LC TRIBAL 3-34-45	2OG-000-5500
43-013-33580	LC TRIBAL 3-5-56	14-20-H62-6257
43-013-33539	LC TRIBAL 4-16-56	14-20-H62-6301

43-013-50262	LC TRIBAL 4-27D-56	14-20-H62-6303
43-013-50661	LC TRIBAL 5-14D-56	14-20-H62-6436
43-013-50752	LC TRIBAL 5-21D-56	14-20-H62-3433
43-013-50625	LC TRIBAL 5-23D-56	14-20-H62-6434
43-013-50260	LC TRIBAL 6-22D-56	14-20-H62-6302
43-013-50868	LC TRIBAL 6-27D-56	14-20-H62-6303
43-013-51034	LC TRIBAL 6-28-45	2OG-000-5500
43-013-51073	LC TRIBAL 7-27-45	2OG-000-5500
43-013-33577	LC TRIBAL 7-3-56	14-20-H62-5656
43-013-50599	LC TRIBAL 8-16D-56	14-20-H62-6301
43-013-33576	LC TRIBAL 8-28-46	14-20-H62-5500
43-013-51131	LC TRIBAL 8-30D-56	2OG-000-5500
43-013-33605	LC TRIBAL 8-4-56	14-20-H62-6256
43-013-51031	LC TRIBAL 9-15D-56	14-20-H62-6435
43-013-51430	LC TRIBAL 9-28D-45	2OG-000-5500
43-013-51112	LC TRIBAL 9-8D-56	2OG-000-5500
43-013-51198	LC TRIBAL 9-9D-56	2OG-000-5500
43-013-51076	LC Tribal 11-24-45	2OG-000-5500
43-013-32931	MOON TRIBAL 10-2-54	14-20-H62-3404
43-013-32540	MOON TRIBAL 10-27-54	14-20-H62-3375
43-013-32845	MOON TRIBAL 11-27-54	14-20-H62-3375
43-013-32347	MOON TRIBAL 12-23-54	14-20-H62-4943
43-013-32541	MOON TRIBAL 12-27-54	14-20-H62-3375
43-013-32937	MOON TRIBAL 1-27-54	14-20-H62-3375
43-013-32801	MOON TRIBAL 13-27-54	14-20-H62-3375
43-013-32408	MOON TRIBAL 14-27-54	14-20-H62-3375
43-013-32846	MOON TRIBAL 15-27-54	14-20-H62-3375
43-013-32927	MOON TRIBAL 16-23-54	14-20-H62-4943
43-013-34109	MOON TRIBAL 16-27D-54	14-20-H62-3375
43-013-32613	MOON TRIBAL 3-27-54	14-20-H62-3375
43-013-32800	MOON TRIBAL 4-23-54	14-20-H62-4943
43-013-32938	MOON TRIBAL 5-23-54	14-20-H62-4943
43-013-32802	MOON TRIBAL 5-27-54	14-20-H62-3375
43-013-32843	MOON TRIBAL 6-23-54	14-20-H62-4943
43-013-32407	MOON TRIBAL 6-27-54	14-20-H62-3375
43-013-33365	MOON TRIBAL 7-27D-54	14-20-H62-3375
43-013-32543	MOON TRIBAL 8-27-54	14-20-H62-3375
43-013-32782	MYRIN TRIBAL 14-19-55	14-20-H62-5058
43-013-32934	MYRIN TRIBAL 16-19-55	14-20-H62-5058
43-013-33152	NIELSEN FEE 13-11-56	14-20-H62-5620
43-013-32737	NIELSEN MARSING 13-14-56	FEE
43-013-31131	S BRUNDAGE CYN UTE TRIBAL 4-27	14-20-H62-3375
43-013-30948	S BRUNDAGE UTE TRIBAL 1-30	14-20-H62-3417
43-013-30933	S COTTONWOOD RIDGE UTE TRIBAL 1-19	14-20-H62-4919
43-007-30890	SCOFIELD THORPE 22-41X RIG SKID	FEE
43-007-31001	SCOFIELD-THORPE 23-31	FEE
43-007-30991	SCOFIELD-THORPE 35-13	FEE
43-013-50686	SFW FEE 14-10D-54	FEE
43-013-50247	SFW FEE 15-10-54	FEE

43-013-34295	SFW TRIBAL 10-10D-54	14-20-H62-5517
43-013-34296	SFW TRIBAL 9-10D-54	14-20-H62-5517
43-013-31701	SOWERS CANYON 9-27	14-20-H62-4753/UTU-76967
43-013-30955	SOWERS CYN UTE TRIBAL 3-26	14-20-H62-3444
43-013-33916	ST TRIBAL 1-15D-54	14-20-H62-4661
43-013-32849	ST TRIBAL 2-15-54	14-20-H62-4661
43-013-34059	ST TRIBAL 3-15D-54	14-20-H62-4661
43-013-32850	ST TRIBAL 4-15-54	14-20-H62-4661
43-013-34060	ST TRIBAL 5-15D-54	14-20-H62-4661
43-013-32848	ST TRIBAL 6-15-54	14-20-H62-4661
43-013-33950	ST TRIBAL 7-15D-54	14-20-H62-4661
43-013-32851	ST TRIBAL 8-15-54	14-20-H62-4661
43-013-33951	ST TRIBAL 9-15D-54	14-20-H62-4661
43-013-50245	STATE TRIBAL 16-10-54	14-20-H62-5517
43-013-32953	STATE TRIBAL 5-18-54	14-20-H62-5035
43-013-32952	STATE TRIBAL 7-18-54	14-20-H62-5035
43-013-30999	T C UTE TRIBAL 9-23X	14-20-H62-3443
43-013-31699	TABBY CANYON 1-21	14-20-H62-4825/UTU-76965
43-013-31700	TABBY CANYON 8-22	14-20-H62-4754/UTU-76966
43-013-30945	TABBY CYN UTE TRIBAL 1-25	14-20-H62-3537
43-013-33121	TAYLOR FEE 13-22-56	FEE
43-013-33140	TAYLOR FEE 7-14-56	FEE
43-013-32738	TAYLOR HERRICK 10-22-56	FEE
43-013-51271	UTE FEE 14-9D-54	FEE
43-013-51272	UTE FEE 15-9D-54	FEE
43-013-33720	UTE FEE 2-13-55	FEE
43-013-51259	UTE FEE 9-9-54	FEE
43-013-33055	UTE TRIBAL 10-12-55	14-20-H62-5056
43-013-33205	UTE TRIBAL 10-14-54	14-20-H62-5033
43-013-32601	UTE TRIBAL 10-14-55	14-20-H62-5016
43-013-32587	UTE TRIBAL 10-15-54	14-20-H62-4661
43-013-32977	UTE TRIBAL 10-15-55	14-20-H62-5017
43-013-33129	UTE TRIBAL 10-16-54	14-20-H62-3413
43-013-32345	UTE TRIBAL 10-16-55	14-20-H62-5024
43-013-33133	UTE TRIBAL 10-17-54	14-20-H62-4731
43-013-33300	UTE TRIBAL 10-18-54	14-20-H62-4919
43-013-32717	UTE TRIBAL 10-19-54	14-20-H62-3528
43-013-32740	UTE TRIBAL 10-20-54	14-20-H62-3529
43-013-32603	UTE TRIBAL 10-21-55	14-20-H62-4825
43-013-32592	UTE TRIBAL 10-22-54	14-20-H62-3415
43-013-33722	UTE TRIBAL 10-22D-55	14-20-H62-4754
43-013-33358	UTE TRIBAL 10-23D-55	14-20-H62-3443
43-013-32932	UTE TRIBAL 10-24-54	14-20-H62-4716
43-013-33156	UTE TRIBAL 10-24D-55	14-20-H62-4749
43-013-32749	UTE TRIBAL 10-25-55	14-20-H62-3537
43-013-33620	UTE TRIBAL 10-26D-54	14-20-H62-4954
43-013-33360	UTE TRIBAL 10-26D-55	14-20-H62-3444
43-013-33683	UTE TRIBAL 10-27D-55	14-20-H62-4753
43-013-32764	UTE TRIBAL 10-28-54	14-20-H62-4740

43-013-32419	UTE TRIBAL 10-28-55	14-20-H62-5019
43-013-33155	UTE TRIBAL 10-29-54	14-20-H62-5036
43-013-33157	UTE TRIBAL 10-29D-55	14-20-H62-5020
43-013-32847	UTE TRIBAL 10-31-54	14-20-H62-4946
43-013-32936	UTE TRIBAL 10-31-55	14-20-H62-5060
43-013-33902	UTE TRIBAL 10-32-54	14-20-H62-4947
43-013-33092	UTE TRIBAL 10-33-54	14-20-H62-4948
43-013-32353	UTE TRIBAL 10-35-55	14-20-H62-4945
43-013-33968	UTE TRIBAL 10-36D-55	14-20-H62-4944
43-013-50854	UTE TRIBAL 10S-21D-54	14-20-H62-3141
43-013-32721	UTE TRIBAL 11-12-55	14-20-H62-5518
43-013-32568	UTE TRIBAL 11-13-54	14-20-H62-4894
43-013-33268	UTE TRIBAL 11-13-55	14-20-H62-4845
43-013-32693	UTE TRIBAL 11-14-55	14-20-H62-5016
43-013-33206	UTE TRIBAL 11-15-54	14-20-H62-4661
43-013-32980	UTE TRIBAL 11-15-55	14-20-H62-5017
43-013-32589	UTE TRIBAL 11-16-54	14-20-H62-3413
43-013-32145	UTE TRIBAL 11-17	14-20-H62-4731
43-013-31547	UTE TRIBAL 11-19	14-20-H62-3528
43-013-32168	UTE TRIBAL 11-20	14-20-H62-3529
43-013-32415	UTE TRIBAL 11-20-55	14-20-H62-5018
43-013-33115	UTE TRIBAL 11-21-54	14-20-H62-3414
43-013-33116	UTE TRIBAL 11-22-54	14-20-H62-3415
43-013-32607	UTE TRIBAL 11-22-55	14-20-H62-4754
43-013-32269	UTE TRIBAL 11-23-55	14-20-H62-3443
43-013-31909	UTE TRIBAL 11-24	14-20-H62-4749
43-013-31911	UTE TRIBAL 11-25	14-20-H62-3537
43-013-32856	UTE TRIBAL 11-25-54	14-20-H62-3440
43-013-32990	UTE TRIBAL 11-25-56	14-20-H62-5065
43-013-32844	UTE TRIBAL 11-26-54	14-20-H62-4954
43-013-33478	UTE TRIBAL 11-26D-55	14-20-H62-3444
43-013-32615	UTE TRIBAL 11-27-55	14-20-H62-4753
43-013-32192	UTE TRIBAL 11-28	14-20-H62-4740
43-013-34057	UTE TRIBAL 11-28-55	14-20-H62-5019
43-013-32563	UTE TRIBAL 11-29-54	14-20-H62-5032
43-013-32512	UTE TRIBAL 11-30-54	14-20-H62-4662
43-013-32530	UTE TRIBAL 11-31-54	14-20-H62-4946
43-013-33793	UTE TRIBAL 11-32D-54	14-20-H62-4947
43-013-32522	UTE TRIBAL 11-33-54	14-20-H62-4948
43-013-33783	UTE TRIBAL 11-35-55	14-20-H62-5053
43-013-33214	UTE TRIBAL 11-36D-55	14-20-H62-4944
43-013-33769	UTE TRIBAL 1-14D-54	14-20-H62-5033
43-013-33279	UTE TRIBAL 1-14D-55	14-20-H62-5016
43-013-32664	UTE TRIBAL 11-5-54	14-20-H62-5516
43-013-32978	UTE TRIBAL 1-15-55	14-20-H62-5017
43-013-33128	UTE TRIBAL 1-16-54	14-20-H62-3413
43-013-30966	UTE TRIBAL 1-20	14-20-H62-3529
43-013-32414	UTE TRIBAL 1-20-55	14-20-H62-5018
43-013-32369	UTE TRIBAL 12-14-54	14-20-H62-5033

43-013-50476	UTE TRIBAL 12-14D-55	14-20-H62-4661
43-013-32205	UTE TRIBAL 12-15	14-20-H62-5017
43-013-32981	UTE TRIBAL 12-15-55	14-20-H62-3413
43-013-33131	UTE TRIBAL 12-16-54	14-20-H62-4919
43-013-32146	UTE TRIBAL 12-17	14-20-H62-5035
43-013-33077	UTE TRIBAL 12-18-54	14-20-H62-3528
43-013-32716	UTE TRIBAL 12-19-54	14-20-H62-3529
43-013-32866	UTE TRIBAL 12-20-54	14-20-H62-3414
43-013-32385	UTE TRIBAL 12-21-54	14-20-H62-4825
43-013-33694	UTE TRIBAL 12-21D-55	14-20-H62-4754
43-013-32616	UTE TRIBAL 12-22-55	14-20-H62-3443
43-013-33908	UTE TRIBAL 12-23D-55	14-20-H62-4749
43-013-33134	UTE TRIBAL 12-24D-55	14-20-H62-4749
43-013-32769	UTE TRIBAL 12-25-55	14-20-H62-3537
43-013-33801	UTE TRIBAL 12-26D-54	14-20-H62-3444
43-013-34118	UTE TRIBAL 12-26D-55	14-20-H62-4740
43-013-32765	UTE TRIBAL 12-28-54	14-20-H62-5019
43-013-33645	UTE TRIBAL 12-28D-55	14-20-H62-5036
43-013-32572	UTE TRIBAL 12-29-54	14-20-H62-5020
43-013-33418	UTE TRIBAL 12-29D-55	14-20-H62-5020
43-013-33215	UTE TRIBAL 1-22D-54	14-20-H62-3415
43-013-33626	UTE TRIBAL 1-22D-55	14-20-H62-4754
43-013-33907	UTE TRIBAL 12-31D-54	14-20-H62-4946
43-013-32925	UTE TRIBAL 12-32-54	14-20-H62-4947
43-013-33266	UTE TRIBAL 12-32-55	14-20-H62-5026
43-013-33090	UTE TRIBAL 12-33-54	14-20-562-4948
43-013-32524	UTE TRIBAL 1-23-55	14-20-H62-3443
43-013-33782	UTE TRIBAL 12-35D-55	14-20-H62-4945
43-013-32354	UTE TRIBAL 12-36-55	14-20-H62-4944
43-013-32259	UTE TRIBAL 1-24-55	14-20-H62-4749
43-013-31912	UTE TRIBAL 1-26	14-20-H62-3444
43-013-33680	UTE TRIBAL 1-26D-54	14-20-H62-4943
43-013-32416	UTE TRIBAL 1-27-55	14-20-H62-4753
43-013-31549	UTE TRIBAL 1-28	14-20-H62-4740
43-013-33784	UTE TRIBAL 1-28D-55	14-20-H62-5019
43-013-33184	UTE TRIBAL 12Q-25-55	14-20-H62-3537
43-013-32599	UTE TRIBAL 13-13-55	14-20-H62-4845
43-013-33364	UTE TRIBAL 13-14-54	14-20-H62-5033
43-013-32600	UTE TRIBAL 13-14-55	14-20-H62-5016
43-013-32526	UTE TRIBAL 1-31-54	14-20-H62-4946
43-013-32602	UTE TRIBAL 13-15-55	14-20-H62-5017
43-013-33039	UTE TRIBAL 13-15D-54	14-20-H662-4661
43-013-32511	UTE TRIBAL 13-16-54	14-20-H62-3413
43-013-31546	UTE TRIBAL 13-17	14-20-H62-4919
43-013-32571	UTE TRIBAL 13-18-54	14-20-H62-5032
43-013-31284	UTE TRIBAL 13-19	14-20-H62-3528
43-013-32206	UTE TRIBAL 13-20	14-20-H62-3529
43-013-32841	UTE TRIBAL 13-20-55	14-20-H62-5018
43-013-33113	UTE TRIBAL 13-21-54	14-20-H62-3414

43-013-31548	UTE TRIBAL 13-22	14-20-H62-3415
43-013-33716	UTE TRIBAL 13-22D-55	14-20-H62-4754
43-013-32513	UTE TRIBAL 13-23-55	14-20-H62-3443
43-013-31910	UTE TRIBAL 13-24	14-20-H62-4749
43-013-32169	UTE TRIBAL 13-25	14-20-H62-3537
43-013-32891	UTE TRIBAL 13-26-54	14-20-H62-4954
43-013-34002	UTE TRIBAL 13-26D-55	14-20-H62-3444
43-013-32387	UTE TRIBAL 13-28-54	14-20-H62-4740
43-013-33646	UTE TRIBAL 13-28D-55	14-20-H62-5019
43-013-32564	UTE TRIBAL 13-29-54	14-20-H62-5032
43-013-33501	UTE TRIBAL 1-31-55	14-20-H62-5060
43-013-30872	UTE TRIBAL 1-32R	14-20-H62-4947
43-013-32185	UTE TRIBAL 1-33	14-20-H62-4948
43-013-32409	UTE TRIBAL 13-30-54	14-20-H62-4662
43-013-32688	UTE TRIBAL 13-31-54	14-20-H62-4946
43-013-32692	UTE TRIBAL 13-32-54	14-20-H62-4947
43-013-32742	UTE TRIBAL 13-33-54	14-20-H62-4948
43-013-32806	UTE TRIBAL 13-35-54	14-20-H62-5053
43-013-34117	UTE TRIBAL 13-35D-55	14-20-H62-4945
43-013-33624	UTE TRIBAL 13-36D-55	14-20-H62-4944
43-013-32186	UTE TRIBAL 1-34	14-20-H62-4955
43-013-50408	UTE TRIBAL 1-34D-55	14-20-H62-5028
43-013-32567	UTE TRIBAL 1-35-54	14-20-H62-5032
43-013-33967	UTE TRIBAL 1-35D-55	14-20-H62-4945
43-013-32760	UTE TRIBAL 1-36-55	14-20-H62-4944
43-013-33380	UTE TRIBAL 13H-16-55	14-20-H62-5024
43-013-33112	UTE TRIBAL 14-14-54	14-20-H62-5033
43-013-32979	UTE TRIBAL 14-15-55	14-20-H62-5017
43-013-33123	UTE TRIBAL 14-16-54	14-20-H62-3413
43-013-32147	UTE TRIBAL 14-17	14-20-H62-4919
43-013-32984	UTE TRIBAL 14-18-55	14-20-H62-5057
43-013-32690	UTE TRIBAL 14-19-54	14-20-H62-3528
43-013-32702	UTE TRIBAL 14-20-54	14-20-H62-3529
43-013-32384	UTE TRIBAL 14-21-54	14-20-H62-3414
43-013-32593	UTE TRIBAL 14-22-54	14-20-H62-3415
43-013-33717	UTE TRIBAL 14-22D-55	14-20-H62-4754
43-013-33915	UTE TRIBAL 14-23D-55	14-20-H62-3443
43-013-33912	UTE TRIBAL 14-24D-55	14-20-H62-4749
43-013-32988	UTE TRIBAL 14-24-56	14-20-H62-5064
43-013-33912	UTE TRIBAL 14-24D-55	14-20-H62-4749
43-013-32776	UTE TRIBAL 14-25-54	14-20-H62-3440
43-013-32750	UTE TRIBAL 14-25-55	14-20-H62-3537
43-013-33673	UTE TRIBAL 14-26D-54	14-20-H62-4954
43-013-33361	UTE TRIBAL 14-26D-55	14-20-H62-3444
43-013-33684	UTE TRIBAL 14-27D-55	14-20-H62-4753
43-013-32348	UTE TRIBAL 14-28-55	14-20-H62-5019
43-013-33278	UTE TRIBAL 14-28D-54	14-20-H62-5036
43-013-33042	UTE TRIBAL 14-31D-54	14-20-H62-4946
43-013-32523	UTE TRIBAL 14-32-54	14-20-H62-4947

43-013-33093	UTE TRIBAL 14-33-54	14-20-H62-4949
43-013-33955	UTE TRIBAL 14-35D-55	14-20-H62-4945
43-013-32355	UTE TRIBAL 14-36-55	14-20-H62-4944
43-013-33277	UTE TRIBAL 14Q-28-54	14-20-H62-4740
43-013-33479	UTE TRIBAL 14Q-30-54	14-20-H62-4662
43-013-33212	UTE TRIBAL 15-13D-55	14-20-H62-4845
43-013-32971	UTE TRIBAL 15-15-54	14-20-H62-4661
43-013-32855	UTE TRIBAL 15-15-55	14-20-H62-5017
43-013-31648	UTE TRIBAL 15-16	14-20-H62-3413
43-013-31649	UTE TRIBAL 15-17	14-20-H62-4731
43-013-32358	UTE TRIBAL 15-17-55	14-20-H62-5025
43-013-32148	UTE TRIBAL 15-18	14-20-H62-4919
43-013-31832	UTE TRIBAL 15-19	14-20-H62-3528
43-013-32386	UTE TRIBAL 15-20-54	14-20-H62-3529
43-013-33357	UTE TRIBAL 15-21-55	14-20-H62-3414
43-013-32617	UTE TRIBAL 15-22-55	14-20-H62-4754
43-013-34116	UTE TRIBAL 15-22D-54	14-20-H62-3415
43-013-31671	UTE TRIBAL 15-23	14-20-H62-3443
43-013-31129	UTE TRIBAL 15-24R	14-20-H62-4749
43-013-32271	UTE TRIBAL 15-25-55	14-20-H62-3537
43-013-33768	UTE TRIBAL 15-26D-54	14-20-H62-4954
43-013-33362	UTE TRIBAL 15-26D-55	14-20-H62-3444
43-013-32339	UTE TRIBAL 15-27-55	14-20-H62-4753
43-013-32389	UTE TRIBAL 15-28-54	14-20-H62-4740
43-013-32561	UTE TRIBAL 15-29-54	14-20-H62-5036
43-013-32382	UTE TRIBAL 15-30-54	14-20-H62-4662
43-013-32743	UTE TRIBAL 15-31-54	14-20-H62-4946
43-013-32666	UTE TRIBAL 15-32-54	14-20-H62-4947
43-013-32768	UTE TRIBAL 15-33-54	14-20-H62-4948
43-013-32804	UTE TRIBAL 15-35-54	14-20-H62-5053
43-013-33954	UTE TRIBAL 15-35D-55	14-20-H62-4945
43-013-33049	UTE TRIBAL 15-36-55	14-20-H62-4944
43-013-33327	UTE TRIBAL 16-13D-55	14-20-H62-4845
43-013-32272	UTE TRIBAL 16-14-55	14-20-H62-5016
43-013-32588	UTE TRIBAL 16-15-54	14-20-H62-4661
43-013-32757	UTE TRIBAL 16-16-55	14-20-H62-5024
43-013-33132	UTE TRIBAL 16-17-54	14-20-H62-4731
43-013-31650	UTE TRIBAL 16-18	14-20-H62-4919
43-013-32691	UTE TRIBAL 16-19-54	14-20-H62-3528
43-013-32739	UTE TRIBAL 16-20-54	14-20-H62-3529
43-013-32381	UTE TRIBAL 16-21-54	14-20-H62-3414
43-013-32842	UTE TRIBAL 16-22-54	14-20-H62-3415
43-013-33267	UTE TRIBAL 16-22D-55	14-20-H62-4754
43-013-33046	UTE TRIBAL 16-23-55	14-20-H-62-3443
43-013-32775	UTE TRIBAL 16-24-54	14-20-H62-4716
43-013-32672	UTE TRIBAL 16-24-55	14-20-H62-3440
43-013-32759	UTE TRIBAL 16-25-55	14-20-H62-3537
43-013-34042	UTE TRIBAL 16-26-54	14-20-H62-4954
43-013-33965	UTE TRIBAL 16-26D-55	14-20-H62-3444

43-013-33786	UTE TRIBAL 16-27D-55	14-20-H62-4753
43-013-33041	UTE TRIBAL 16-28D-54	14-20-H62-4740
43-013-33076	UTE TRIBAL 16-29-54	14-20-H62-5036
43-013-32349	UTE TRIBAL 16-29-55	14-20-H62-5020
43-013-32665	UTE TRIBAL 16-3-54	14-20-H62-4778
43-013-32718	UTE TRIBAL 16-30-54	14-20-H62-4662
43-013-33326	UTE TRIBAL 16-31D-54	14-20-H62-4946
43-013-32926	UTE TRIBAL 16-32D-54	14-20-H62-4947
43-013-33091	UTE TRIBAL 16-33-54	14-20-H62-4948
43-013-32352	UTE TRIBAL 16-35-55	14-20-H62-4945
43-013-32356	UTE TRIBAL 16-36-55	14-20-H62-4944
43-013-33393	UTE TRIBAL 1A-29-54	14-20-H62-5036
43-013-33186	UTE TRIBAL 1I-36-55	14-20-H62-4944
43-013-33111	UTE TRIBAL 2-14-54	14-20-H962-5033
43-013-32140	UTE TRIBAL 2-19	14-20-H62-4919
43-013-32974	UTE TRIBAL 2-20-54	14-20-H62-3529
43-013-33117	UTE TRIBAL 2-21-55	14-20-H62-4825
43-013-32591	UTE TRIBAL 2-22-54	14-20-H62-3415
43-013-32604	UTE TRIBAL 2-22-55	14-20-H62-4754
43-013-33045	UTE TRIBAL 2-23-55	14-20-H62-3443
43-013-32569	UTE TRIBAL 2-24-54	14-20-H62-4716
43-013-31833	UTE TRIBAL 2-25	14-20-H62-3537
43-013-32868	UTE TRIBAL 2-26-54	14-20-H62-4954
43-013-33979	UTE TRIBAL 2-26D-55	14-20-H62-3444
43-013-32179	UTE TRIBAL 2-27	14-20-H62-3375
43-013-33628	UTE TRIBAL 2-27D-55	14-20-H62-4753
43-013-32763	UTE TRIBAL 2-28-54	14-20-H62-4740
43-013-33714	UTE TRIBAL 2-29D-55	14-20-H62-5036
43-013-32680	UTE TRIBAL 2-30-55	14-20-H62-5059
43-013-32894	UTE TRIBAL 2-30D-54	14-20-H62-4662
43-013-32762	UTE TRIBAL 2-31-54	14-20-H62-4946
43-013-32935	UTE TRIBAL 2-31-55	14-20-H62-5060
43-013-32803	UTE TRIBAL 2-32-54	14-20-H62-4947
43-013-32350	UTE TRIBAL 2-32-55	14-20-H62-5026
43-013-32898	UTE TRIBAL 2-33D-54	14-20-H62-4948
43-013-32187	UTE TRIBAL 2-35	14-20-H62-4945
43-013-32422	UTE TRIBAL 2-36-55	14-20-H62-4944
43-013-32663	UTE TRIBAL 3-10-54	14-20-H62-5517
43-013-50478	UTE TRIBAL 3-14-55	14-20-H62-5016
43-013-50389	UTE TRIBAL 3-14D-54	14-20-H62-5033
43-013-31830	UTE TRIBAL 3-19	14-20-H62-3528
43-013-32377	UTE TRIBAL 3-20-54	14-20-H62-4919
43-013-32867	UTE TRIBAL 3-21-54	14-20-H62-3414
43-013-32758	UTE TRIBAL 3-21-55	14-20-H62-4825
43-013-33208	UTE TRIBAL 3-22-54	14-20-H62-3415
43-013-32605	UTE TRIBAL 3-22-55	14-20-H62-4754
43-013-32536	UTE TRIBAL 3-23-55	14-20-H62-3443
43-013-30960	UTE TRIBAL 3-24R-55 (REENTRY)	14-20-H62-4749
43-013-31834	UTE TRIBAL 3-25	14-20-H62-3537

43-013-32993	UTE TRIBAL 3-25-56	14-20-H62-5065
43-013-33681	UTE TRIBAL 3-26D-54	14-20-H62-4954
43-013-32417	UTE TRIBAL 3-27-55	14-20-H62-4753
43-013-32261	UTE TRIBAL 3-28-54	14-20-H62-4740
43-013-33723	UTE TRIBAL 3-29-55	14-20-H62-5020
43-013-32625	UTE TRIBAL 3-30-54	14-20-H62-4662
43-013-32862	UTE TRIBAL 3-30-55	14-20-H62-5059
43-013-32527	UTE TRIBAL 3-31-54	14-20-H62-4946
43-013-32410	UTE TRIBAL 3-32-54	14-20-H62-4947
43-013-33363	UTE TRIBAL 3-32D-55	14-20-H62-5206
43-013-32412	UTE TRIBAL 3-33-54	14-20-H62-4948
43-013-33888	UTE TRIBAL 3-35D-55	14-20-H62-5053
43-013-33888	UTE TRIBAL 3-35D-55	14-20-H62-4945
43-013-32751	UTE TRIBAL 3-36-55	14-20-H62-4944
43-013-33185	UTE TRIBAL 3G-31-54	14-20-H62-4946
43-013-33270	UTE TRIBAL 4-14D-54	14-20-H62-5033
43-013-32972	UTE TRIBAL 4-19-54	14-20-H62-3528
43-013-32621	UTE TRIBAL 4-20-54	14-20-H62-4919
43-013-33549	UTE TRIBAL 4-20D-55	14-20-H62-5018
43-013-32378	UTE TRIBAL 4-21-54	14-20-H62-3414
43-013-33044	UTE TRIBAL 4-22-55	14-20-H62-4754
43-013-33627	UTE TRIBAL 4-23D-55	14-20-H62-3443
43-013-32573	UTE TRIBAL 4-24-54	14-20-H62-4716
43-013-33726	UTE TRIBAL 4-24D-55	14-20-H62-4749
43-013-32928	UTE TRIBAL 4-25-55	14-20-H62-3537
43-013-33595	UTE TRIBAL 4-26D-54	14-20-H62-4954
43-013-33978	UTE TRIBAL 4-26D-55	14-20-H62-3444
43-013-33797	UTE TRIBAL 4-27D-55	14-20-H62-4753
43-013-32741	UTE TRIBAL 4-28-54	14-20-H62-4740
43-013-33118	UTE TRIBAL 4-28-55	14-20-H62-5019
43-013-32565	UTE TRIBAL 4-29-54	14-20-H62-5036
43-013-31550	UTE TRIBAL 4-30	14-20-H62-4662
43-013-32767	UTE TRIBAL 4-31-54	14-20-H62-4946
43-013-32896	UTE TRIBAL 4-32-54	14-20-H62-4947
43-013-33379	UTE TRIBAL 4-32-55	14-20-H62-5026
43-013-32871	UTE TRIBAL 4-33-54	14-20-H62-4948
43-013-32357	UTE TRIBAL 4-33-55	14-20-H62-5027
43-013-32188	UTE TRIBAL 4-36	14-20-H62-4944
43-013-31152	UTE TRIBAL 5-13	14-20-H62-4845
43-013-33075	UTE TRIBAL 5-13-54	14-20-H62-4894
43-013-33619	UTE TRIBAL 5-14-54	14-20-H62-5033
43-013-50479	UTE TRIBAL 5-14-55	14-20-H62-5016
43-013-32344	UTE TRIBAL 5-15-55	14-20-H62-5017
43-013-50475	UTE TRIBAL 5-16D-54	14-20-H62-3413
43-013-32204	UTE TRIBAL 5-19	14-20-H62-3528
43-013-31651	UTE TRIBAL 5-20	14-20-H62-4919
43-013-33324	UTE TRIBAL 5-21-54	14-20-H62-3414
43-013-33706	UTE TRIBAL 5-21D-55	14-20-H62-4825
43-013-32624	UTE TRIBAL 5-22-54	14-20-H62-3415

43-013-32537	UTE TRIBAL 5-23-55	14-20-H62-3443
43-013-32263	UTE TRIBAL 5-24-55	14-20-H62-4749
43-013-32992	UTE TRIBAL 5-25-56	14-20-H62-5065
43-013-33421	UTE TRIBAL 5-25D-55	14-20-H62-3537
43-013-32890	UTE TRIBAL 5-26-54	14-20-H62-4954
43-013-32264	UTE TRIBAL 5-26-55	14-20-H62-3444
43-013-32614	UTE TRIBAL 5-27-55	14-20-H62-4753
43-013-32189	UTE TRIBAL 5-28	14-20-H62-4740
43-013-32525	UTE TRIBAL 5-29-54	14-20-H62-5032
43-013-32380	UTE TRIBAL 5-30-54	14-20-H62-4662
43-013-32190	UTE TRIBAL 5-31	14-20-H62-4946
43-013-32539	UTE TRIBAL 5-32-54	14-20-H62-4947
43-013-32521	UTE TRIBAL 5-33-54	14-20-H62-4948
43-013-32805	UTE TRIBAL 5-35-54	14-20-H62-5053
43-013-32930	UTE TRIBAL 5-36-55	14-20-H62-4944
43-013-32586	UTE TRIBAL 6-14-54	14-20-H62-5033
43-013-50246	UTE TRIBAL 6-14D-55	14-20-H62-5016
43-013-32865	UTE TRIBAL 6-19-54	14-20-H62-3528
43-013-32622	UTE TRIBAL 6-20-54	14-20-H62-4919
43-013-32164	UTE TRIBAL 6-21	14-20-H62-3414
43-013-32163	UTE TRIBAL 6-22	14-20-H62-3415
43-013-33213	UTE TRIBAL 6-22D-55	14-20-H62-4728
43-013-33187	UTE TRIBAL 6-23D-55	14-20-H62-3443
43-013-32570	UTE TRIBAL 6-24-54	14-20-H62-4716
43-013-32143	UTE TRIBAL 6-25H	14-20-H62-3537
43-013-33625	UTE TRIBAL 6-26D-54	14-20-H62-4954
43-013-33476	UTE TRIBAL 6-26D-55	14-20-H62-3444
43-013-32892	UTE TRIBAL 6-28D-54	14-20-H62-4740
43-013-33172	UTE TRIBAL 6-29-54	14-20-H62-5036
43-013-33120	UTE TRIBAL 6-29-55	14-20-H62-5020
43-013-32783	UTE TRIBAL 6-30-55	14-20-H62-5059
43-013-33325	UTE TRIBAL 6-31D-54	14-20-H62-4946
43-013-32420	UTE TRIBAL 6-32-55	14-20-H62-5026
43-013-32897	UTE TRIBAL 6-32D-54	14-20-H62-4947
43-013-32872	UTE TRIBAL 6-33-54	14-20-H62-4948
43-013-34028	UTE TRIBAL 6-35D-55	14-20-H62-4945
43-013-32265	UTE TRIBAL 6-36-55	14-20-H62-4944
43-013-50409	UTE TRIBAL 7-14-54	14-20-H62-5033
43-013-33269	UTE TRIBAL 7-14-55	14-20-H62-5016
43-013-32976	UTE TRIBAL 7-15-55	14-20-H62-5017
43-013-33130	UTE TRIBAL 7-16-54	14-20-H62-3413
43-013-32863	UTE TRIBAL 7-19-55	14-20-H62-5058
43-013-32346	UTE TRIBAL 7-20-55	14-20-H62-5018
43-013-31281	UTE TRIBAL 7-20R-54	14-20-H62-3529
43-013-32623	UTE TRIBAL 7-21-54	14-20-H62-3414
43-013-32761	UTE TRIBAL 7-22-54	14-20-H62-3415
43-013-33721	UTE TRIBAL 7-22D-55	14-20-H62-4754
43-013-32514	UTE TRIBAL 7-23-55	14-20-H62-3443
43-013-32991	UTE TRIBAL 7-24-56	14-20-H62-5064

43-013-32991	UTE TRIBAL 7-25-56	14-20-H62-5065
43-013-33621	UTE TRIBAL 7-26D-54	14-20-H62-4954
43-013-33477	UTE TRIBAL 7-26D-55	14-20-H62-3444
43-013-32418	UTE TRIBAL 7-27-55	14-20-H62-4753
43-013-32166	UTE TRIBAL 7-28	14-20-H62-4740
43-013-33788	UTE TRIBAL 7-28D-55	14-20-H62-5019
43-013-32562	UTE TRIBAL 7-29-54	14-20-H62-5036
43-013-33715	UTE TRIBAL 7-29D-55	14-20-H62-5020
43-013-32167	UTE TRIBAL 7-30	14-20-H62-4662
43-013-32528	UTE TRIBAL 7-31-54	14-20-H62-4946
43-013-32411	UTE TRIBAL 7-32-54	14-20-H62-4947
43-013-32413	UTE TRIBAL 7-33-54	14-20-H62-4948
43-013-50510	UTE TRIBAL 7-34-55	14-20-H62-5028
43-013-32774	UTE TRIBAL 7-35-54	14-20-H62-5053
43-013-33048	UTE TRIBAL 7-35-55	14-20-H62-4945
43-013-32929	UTE TRIBAL 7-36-55	14-20-H62-4944
43-013-50852	UTE TRIBAL 7I-21-54	14-20-H62-3414
43-013-50488	UTE TRIBAL 8-10D-54	14-20-H62-5517
43-013-33204	UTE TRIBAL 8-14-54	14-20-H62-5033
43-013-50477	UTE TRIBAL 8-15D-55	14-20-H62-5017
43-013-32840	UTE TRIBAL 8-19-54	14-20-H62-3528
43-013-32864	UTE TRIBAL 8-19-55	14-20-H62-5058
43-013-32973	UTE TRIBAL 8-20-54	14-20-H62-3529
43-013-50435	UTE TRIBAL 8-21D-55	14-20-H62-4825
43-013-32590	UTE TRIBAL 8-22-54	14-20-H62-3415
43-013-33552	UTE TRIBAL 8-23D-55	14-20-H62-3443
43-013-33420	UTE TRIBAL 8-24-55	14-20-H62-4716
43-013-32780	UTE TRIBAL 8-25-54	14-20-H62-3440
43-013-32620	UTE TRIBAL 8-25-55	14-20-H62-3537
43-013-33682	UTE TRIBAL 8-26D-54	14-20-H62-4954
43-013-33859	UTE TRIBAL 8-26D-55	14-20-H62-3444
43-013-34058	UTE TRIBAL 8-27D-55	14-20-H62-4753
43-013-32766	UTE TRIBAL 8-28-54	14-20-H62-4740
43-013-32694	UTE TRIBAL 8-28-55	14-20-H62-5019
43-013-33119	UTE TRIBAL 8-29-55	14-20-H62-5020
43-013-32746	UTE TRIBAL 8-30-54	14-20-H62-4662
43-013-32869	UTE TRIBAL 8-31-54	14-20-H62-4946
43-013-32673	UTE TRIBAL 8-31-55	14-20-H62-5032
43-013-32870	UTE TRIBAL 8-32-54	14-20-H62-4947
43-013-32421	UTE TRIBAL 8-32-55	14-20-H62-5026
43-013-33089	UTE TRIBAL 8-33-54	14-20-H62-4948
43-013-50436	UTE TRIBAL 8-34D-55	14-20-H62-5028
43-013-32267	UTE TRIBAL 8-35-55	14-20-H62-4945
43-013-32423	UTE TRIBAL 8-36-55	14-20-H62-4944
43-013-50853	UTE TRIBAL 8L-21D-54	14-20-H62-3141
43-013-33328	UTE TRIBAL 9-13D-55	14-20-H62-4845
43-013-33796	UTE TRIBAL 9-14D-54	14-20-H62-5033
43-013-32701	UTE TRIBAL 9-15-55	14-20-H62-5017
43-013-33207	UTE TRIBAL 9-16-54	14-20-H62-3413

43-013-32687	UTE TRIBAL 9-17-54	14-20-H62-4731
43-013-32144	UTE TRIBAL 9-18	14-20-H62-4919
43-013-31831	UTE TRIBAL 9-19	14-20-H62-3528
43-013-32379	UTE TRIBAL 9-20-54	14-20-H62-3529
43-013-33675	UTE TRIBAL 9-20D-55	14-20-H62-5018
43-013-33040	UTE TRIBAL 9-21-54	14-20-H62-3414
43-013-32889	UTE TRIBAL 9-22-54	14-20-H62-3415
43-013-32606	UTE TRIBAL 9-22-55	14-20-H62-4754
43-013-32268	UTE TRIBAL 9-24-55	14-20-H62-4749
43-013-32390	UTE TRIBAL 9-25-55	14-20-H62-3537
43-013-32191	UTE TRIBAL 9-26	14-20-H62-4728
43-013-33359	UTE TRIBAL 9-26D-55	14-20-H62-3444
43-013-32388	UTE TRIBAL 9-28-54	14-20-H62-4740
43-013-33787	UTE TRIBAL 9-28D-55	14-20-H62-5019
43-013-32566	UTE TRIBAL 9-29-54	14-20-H62-5036
43-013-32383	UTE TRIBAL 9-30-54	14-20-H62-4662
43-013-32529	UTE TRIBAL 9-31-54	14-20-H62-4946
43-013-33508	UTE TRIBAL 9-31-55	14-20-H62-5060
43-013-32538	UTE TRIBAL 9-32-54	14-20-H62-4947
43-013-32549	UTE TRIBAL 9-33-54	14-20-H62-4948
43-013-32781	UTE TRIBAL 9-35-54	14-20-H62-5053
43-013-33047	UTE TRIBAL 9-35-55	14-20-H62-4945
43-013-33239	UTE TRIBAL 9-36D-55	14-20-H62-4944
43-013-33276	UTE TRIBAL 9S-19-54	14-20-H62-3528
43-013-33245	UTE TRIBAL 9S-25-55	14-20-H62-3537
43-013-50997	Vieira Tribal 4-4-54	14-20-H62-5659
43-013-33122	WILCOX ELIASON 7-15-56	FEE
43-013-33150	WILCOX FEE 1-20-56	FEE
43-013-33151	WILCOX FEE 15-16-56	FEE
43-013-32550	WILLIAMSON TRIBAL 3-34-54	14-20-H62-4955
43-013-32551	WILLIAMSON TRIBAL 5-34-54	14-20-H62-4955
43-013-31311	Z and T UTE TRIBAL 12-22	14-20-H62-3415
43-013-31280	Z and T UTE TRIBAL 2-21	14-20-H62-3414
43-013-31282	Z and T UTE TRIBAL 7-19	14-20-H62-4919
43-013-31310	Z and T UTE TRIBAL 7-25	14-20-H62-3537

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET (for state use only)

ROUTING
CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

6/1/2014

FROM: (Old Operator):

Berry Petroelum Company, LLC N4075
 1999 Broadway Street , Suite 3700
 Denver, CO 80202
 Phone: 1 (303) 999-4400

TO: (New Operator):

Linn Operating, Inc. N4115
 1999 Broadway Street, Suite 3700
 Denver, CO 80202
 Phone: 1 (303) 999-4400

CA No.

Unit:

**Berry Pilot EOR 246-02
 Brundage Canyon**

WELL NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
See Attached List								

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 6/13/2014
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 6/13/2014
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 6/17/2014
- 4a. Is the new operator registered in the State of Utah: _____ Business Number: 9031632-0143
- 5a. (R649-9-2)Waste Management Plan has been received on: N/A
- 5b. Inspections of LA PA state/fee well sites complete on: Yes
- 5c. Reports current for Production/Disposition & Sundries on: 6/17/2014
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM Not Yet BIA Not Yet
- Federal and Indian Units:**
 The BLM or BIA has approved the successor of unit operator for wells listed on: Not Yet
- Federal and Indian Communization Agreements ("CA"):**
 The BLM or BIA has approved the operator for all wells listed within a CA on: N/A
- Underground Injection Control ("UIC")** Division has approved UIC Form 5 Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 6/18/2014
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 6/18/2014
- Bond information entered in RBDMS on: 6/23/2014
- Fee/State wells attached to bond in RBDMS on: 6/23/2014
- Injection Projects to new operator in RBDMS on: N/A
- Receipt of Acceptance of Drilling Procedures for APD/New on: 6/18/2014
- Surface Agreement Sundry from **NEW** operator on Fee Surface wells received on: Yes

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: NMB000501
- Indian well(s) covered by Bond Number: NMB000501
- 3a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number LPM9149893
- 3b. The **FORMER** operator has requested a release of liability from their bond on: N/A

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 6/23/2014

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

5. LEASE DESIGNATION AND SERIAL NUMBER:

See attached list

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL

OIL WELL ☒

GAS WELL ☐

OTHER _____

2. NAME OF OPERATOR:

Linn Operating, Inc.

3. ADDRESS OF OPERATOR:

1999 Broadway, Ste 3700

CITY

Denver

STATE

CO

ZIP

80202

PHONE NUMBER:

(303) 999-4400

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☒ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will start:

☐ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of work completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☒ OTHER: Change of operator

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Notice of Change of Operator from Berry Petroleum Company, LLC to Linn Operating, Inc., effective June 1, 2014. On December 16, 2013, Berry Petroleum Company became an indirect subsidiary of Linn Energy, LLC. As a result, Berry Petroleum Company converted into a limited liability company named, "Berry Petroleum Company, LLC". On March 5, 2014, Berry Petroleum Company, LLC authorized and empowered Linn Operating, Inc. to act as operator on its behalf. I have attached a copy of the original declaration amending the name change along with a copy of the agency agreement and power of attorney for the operator change.

RECEIVED

JUN 10 2014

Div. of Oil, Gas & Mining

NAME (PLEASE PRINT) Beverly Decker

TITLE Sr Engineering Technician

SIGNATURE

Beverly Decker

DATE 6/1/2014

(This space for State use only)

APPROVED

JUN 18 2014

DIV. OIL GAS & MINING

BY: Rachel Medina

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: See attached list
2. NAME OF OPERATOR: Berry Petroleum Company, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1999 Broadway, Ste 3700 CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (303) 999-4400		8. WELL NAME and NUMBER:
4. LOCATION OF WELL FOOTAGES AT SURFACE:		9. API NUMBER:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT:
		COUNTY:
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Change of operator</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On December 16th, 2013 Berry Petroleum Company and Linn Energy merged. As a result of this merger the companies name has changed to "Berry Petroleum Company, LLC". On March 5th, 2014 Berry Petroleum Company, LLC agreed that Linn Operating, Inc would become the operator of record effective June 1, 2014. I have attached a copy of the original declaration amending the name change along with a copy of the agency agreement and power of attorney for the operator change.

Should you have any questions please don't hesitate to contact me.

RECEIVED
JUN 13 2014
Div. of Oil, Gas & Mining

NAME (PLEASE PRINT) <u>Beverly Decker</u>	TITLE <u>Sr Engineering Technician</u>
SIGNATURE <u><i>Beverly Decker</i></u>	DATE <u>6/1/2014</u>

(This space for State use only)

APPROVED

JUN 18 2014

DIV. OIL GAS & MINING

BY: *Rachel Medina*

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Request to Transfer Application or Permit to Drill

(This form should accompany a Sundry Notice, Form 9, requesting APD transfer)

Well name:	See Attached
API number:	
Location:	Qtr-Qtr: Section Township Range:
Company that filed original application:	Berry Petroleum Company LLC
Date original permit was issued:	
Company that permit was issued to:	Linn Operating, Inc

Check one	Desired Action:
	Transfer pending (unapproved) Application for Permit to Drill to new operator
	The undersigned as owner with legal rights to drill on the property, hereby verifies that the information as submitted in the pending Application for Permit to Drill, remains valid and does not require revision. The new owner of the application accepts and agrees to the information and procedures as stated in the application.
<input checked="" type="checkbox"/>	Transfer approved Application for Permit to Drill to new operator
	The undersigned as owner with legal rights to drill on the property as permitted, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.	Yes	No
If located on private land, has the ownership changed?		<input checked="" type="checkbox"/>
<input type="checkbox"/> If so, has the surface agreement been updated?		
Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?		<input checked="" type="checkbox"/>
Have there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?		<input checked="" type="checkbox"/>
Have there been any changes to the access route including ownership or right-of-way, which could affect the proposed location?		<input checked="" type="checkbox"/>
Has the approved source of water for drilling changed?		<input checked="" type="checkbox"/>
Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?		<input checked="" type="checkbox"/>
Is bonding still in place, which covers this proposed well? Bond No. <u>LPM9149893</u>	<input checked="" type="checkbox"/>	

Any desired or necessary changes to either a pending or approved Application for Permit to Drill that is being transferred, should be filed on a Sundry Notice, Form 9, or amended Application for Permit to Drill, Form 3, as appropriate, with necessary supporting information as required.

Name (please print) Beverly Decker Title Sr Engineering Technician
Signature *Beverly Decker* Date _____
Representing (company name) Berry Petroleum Company LLC and Linn Operating, Inc

The person signing this form must have legal authority to represent the company or individual(s) to be listed as the new operator on the Application for Permit to Drill.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Request to Transfer Application or Permit to Drill

(This form should accompany a Sundry Notice, Form 9, requesting APD transfer)

Well name:	See Attached
API number:	
Location:	Qtr-Qtr: Section: Township: Range:
Company that filed original application:	Berry Petroleum Company LLC
Date original permit was issued:	
Company that permit was issued to:	Linn Operating, Inc

Check one	Desired Action:
<input type="checkbox"/>	
<input checked="" type="checkbox"/>	Transfer pending (unapproved) Application for Permit to Drill to new operator
	The undersigned as owner with legal rights to drill on the property, hereby verifies that the information as submitted in the pending Application for Permit to Drill, remains valid and does not require revision. The new owner of the application accepts and agrees to the information and procedures as stated in the application.
<input type="checkbox"/>	Transfer approved Application for Permit to Drill to new operator
	The undersigned as owner with legal rights to drill on the property as permitted, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.		Yes	No
If located on private land, has the ownership changed?			<input checked="" type="checkbox"/>
<input type="checkbox"/>	If so, has the surface agreement been updated?		
Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?			<input checked="" type="checkbox"/>
Have there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?			<input checked="" type="checkbox"/>
Have there been any changes to the access route including ownership or right-of-way, which could affect the proposed location?			<input checked="" type="checkbox"/>
Has the approved source of water for drilling changed?			<input checked="" type="checkbox"/>
Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?			<input checked="" type="checkbox"/>
Is bonding still in place, which covers this proposed well? Bond No. <u>LPM9149893</u>		<input checked="" type="checkbox"/>	

Any desired or necessary changes to either a pending or approved Application for Permit to Drill that is being transferred, should be filed on a Sundry Notice, Form 9, or amended Application for Permit to Drill, Form 3, as appropriate, with necessary supporting information as required.

Name (please print) Beverly Decker Title Sr Engineering Technician
Signature  Date _____
Representing (company name) Berry Petroleum Company LLC and Linn Operating, Inc

The person signing this form must have legal authority to represent the company or individual(s) to be listed as the new operator on the Application for Permit to Drill.

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

Well Name	Section	TWN	RNG	API Number	Entity	Mineral Lease	Well Type	Well Status	Unit
Z and T UTE TRIBAL 2-21	21	050S	040W	4301331280	11130	Indian	WI	A	BRUNDAGE CANYON
UTE TRIBAL 12-30-54	30	050S	040W	4301332747	14747	Indian	WI	A	BRUNDAGE CANYON
UTE TRIBAL 14-30-54	30	050S	040W	4301332748	14778	Indian	WI	A	BRUNDAGE CANYON
UTE TRIBAL 10-30D-54	30	050S	040W	4301332893	15246	Indian	WI	A	BRUNDAGE CANYON
UTE TRIBAL 6-30-54	30	050S	040W	4301332975	15300	Indian	WI	A	BRUNDAGE CANYON
UTE TRIBAL 1-21-54	21	050S	040W	4301333388	15937	Indian	WI	A	BRUNDAGE CANYON
UTE TRIBAL 13-17D-55	17	050S	050W	4301333550		Indian	OW	APD	
UTE TRIBAL 11-14D-54	14	050S	040W	4301333596		Indian	OW	APD	
UTE TRIBAL 16-17D-55	17	050S	050W	4301333622		Indian	OW	APD	
UTE TRIBAL 15-28D-55	28	050S	050W	4301333623		Indian	OW	APD	
LC TRIBAL 14-16D-56	16	050S	060W	4301334283		Indian	OW	APD	
FEDERAL 10-10D-65	10	060S	050W	4301350523		Federal	OW	APD	
LC TRIBAL 3-23D-56	23	050S	060W	4301350624		Indian	OW	APD	
FEDERAL 2-1D-64	1	060S	040W	4301350765		Federal	OW	APD	
FEDERAL 7-1D-64	1	060S	040W	4301350766		Federal	OW	APD	
FEDERAL 9-1D-64	1	060S	040W	4301350767		Federal	OW	APD	
LC TRIBAL 1-28D-56	28	050S	060W	4301350865		Indian	OW	APD	
LC TRIBAL 13H-9-56	10	050S	060W	4301350874		Indian	OW	APD	
CC FEE 8-24-38	24	030S	080W	4301350885		Fee	OW	APD	
LC TRIBAL 4H-26-56	26	050S	060W	4301350951		Indian	OW	APD	
LC FEE 4H-12-57	12	050S	070W	4301350952		Fee	OW	APD	
CC TRIBAL 4-2-48	2	040S	080W	4301350964		Indian	OW	APD	
LC TRIBAL 5H-34-45	34	040S	050W	4301350974		Indian	OW	APD	
LC TRIBAL 11-34-45	34	040S	050W	4301350975		Indian	OW	APD	
LC TRIBAL 7-2D-56	2	050S	060W	4301350988		Indian	OW	APD	
LC TRIBAL 10-18D-56	18	050S	060W	4301350989		Indian	OW	APD	
CC TRIBAL 4-30D-38	19	030S	080W	4301350993		Indian	OW	APD	
FEDERAL 4-1-65	1	060S	050W	4301351016		Federal	OW	APD	
LC TRIBAL 3-16D-56	16	050S	060W	4301351032		Indian	OW	APD	
CC FEE 6-21-38	21	030S	080W	4301351059		Fee	OW	APD	
LC TRIBAL 13H-28-45	28	040S	050W	4301351061		Indian	OW	APD	
LC TRIBAL 5H-23-45	23	040S	050W	4301351071		Indian	OW	APD	
LC TRIBAL 4H-27-45	27	040S	050W	4301351072		Indian	OW	APD	
LC TRIBAL 16-27-45	27	040S	050W	4301351074		Indian	OW	APD	
LC TRIBAL 12-27-45	27	040S	050W	4301351075		Indian	OW	APD	
LC TRIBAL 16-23-45	23	040S	050W	4301351077		Indian	OW	APD	
LC TRIBAL 12H-30-56	30	050S	060W	4301351133		Indian	OW	APD	
LC TRIBAL 5-29D-56	29	050S	060W	4301351184		Indian	OW	APD	
LC TRIBAL 12H-19-56	19	050S	060W	4301351193		Indian	OW	APD	
LC FEE 15-11D-56	11	050S	060W	4301351197		Fee	OW	APD	
LC TRIBAL 13H-10-56	11	050S	060W	4301351209		Indian	OW	APD	
LC TRIBAL 2-31D-45	31	040S	050W	4301351261		Indian	OW	APD	
LC TRIBAL 13H-24-45	24	040S	050W	4301351273		Indian	OW	APD	
UTE TRIBAL 6-21D-55	21	050S	050W	4301351274		Indian	OW	APD	
UTE TRIBAL 15-16D-55	16	050S	050W	4301351284		Indian	OW	APD	
UTE TRIBAL 4H-15-55	15	050S	050W	4301351292		Indian	OW	APD	
UTE TRIBAL 13H-14-54	14	050S	040W	4301351297		Indian	OW	APD	
UTE TRIBAL 1-32-55	32	050S	050W	4301351298		Indian	OW	APD	
UTE TRIBAL 4-21D-55	21	050S	050W	4301351299		Indian	OW	APD	
LC TRIBAL 12-33-45	33	040S	050W	4301351301		Indian	OW	APD	
UTE TRIBAL 16-15D-55	15	050S	050W	4301351302		Indian	OW	APD	
UTE TRIBAL 2-24-55	24	050S	050W	4301351304		Indian	OW	APD	
LC TRIBAL 11-32D-56	32	050S	060W	4301351315		Indian	OW	APD	
LC TRIBAL 1-32D-56	32	050S	060W	4301351317		Indian	OW	APD	
LC TRIBAL 5H-32-56	32	050S	060W	4301351318		Indian	OW	APD	
LC TRIBAL 5H-33-45	33	040S	050W	4301351338		Indian	OW	APD	
LC TRIBAL 14-28-45	28	040S	050W	4301351339		Indian	OW	APD	
LC TRIBAL 16-32D-45	32	040S	050W	4301351340		Indian	OW	APD	
LC TRIBAL 3-31-45	31	040S	050W	4301351347		Indian	OW	APD	
LC TRIBAL 1-18D-56	18	050S	060W	4301351367		Indian	OW	APD	
LC TRIBAL 9-18D-56	18	050S	060W	4301351368		Indian	OW	APD	
LC FEE 9-23D-56	23	050S	060W	4301351380		Fee	OW	APD	
LC TRIBAL 1-34D-45	34	040S	050W	4301351382		Indian	OW	APD	
LC TRIBAL 12-21D-56	21	050S	060W	4301351383		Indian	OW	APD	
LC TRIBAL 7-29D-56	29	050S	060W	4301351386		Indian	OW	APD	

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

UTE TRIBAL 6-15-55	15	050S	050W	4301351399	Indian	OW	APD
UTE TRIBAL 13H-21-55	21	050S	050W	4301351403	Indian	OW	APD
LC TRIBAL 6-16D-56	16	050S	060W	4301351406	Indian	OW	APD
LC TRIBAL 3-14D-56	14	050S	060W	4301351408	Indian	OW	APD
CC FEE 13-9D-37	9	030S	070W	4301351409	Fee	OW	APD
CC FEE 16-21D-38	21	030S	080W	4301351410	Fee	OW	APD
UTE TRIBAL 5H-10-54	10	050S	040W	4301351415	Indian	OW	APD
LC TRIBAL 13-6D-57	6	050S	070W	4301351417	Indian	OW	APD
LC TRIBAL 9-23-45	23	040S	050W	4301351432	Indian	OW	APD
LC TRIBAL 5-28D-56	29	050S	060W	4301351441	Indian	OW	APD
LC TRIBAL 15-20D-56	29	050S	060W	4301351443	Indian	OW	APD
LC FEE 14-1-56	1	050S	060W	4301351457	Fee	OW	APD
LC TRIBAL 5-3D-56	3	050S	060W	4301351459	Indian	OW	APD
LC Tribal 16-33-45	33	040S	050W	4301351463	Indian	OW	APD
LC TRIBAL 7-23D-56	23	050S	060W	4301351479	Indian	OW	APD
LC TRIBAL 4-7-56	7	050S	060W	4301351482	Indian	OW	APD
LC TRIBAL 3-2-56	2	050S	060W	4301351483	Indian	OW	APD
LC TRIBAL 12H-23-56	23	050S	060W	4301351488	Indian	OW	APD
CC TRIBAL 15-34D-38	2	040S	080W	4301351490	Indian	OW	APD
CC TRIBAL 14-35D-38	2	040S	080W	4301351491	Indian	OW	APD
CC TRIBAL 8-3D-48	2	040S	080W	4301351493	Indian	OW	APD
LC TRIBAL 12HH-31-45	32	040S	050W	4301351499	Indian	OW	APD
LC TRIBAL 1-10D-56	10	050S	060W	4301351510	Indian	OW	APD
LC TRIBAL 3-10D-56	10	050S	060W	4301351511	Indian	OW	APD
LC TRIBAL 7-10D-56	10	050S	060W	4301351512	Indian	OW	APD
LC TRIBAL 9-29D-56	29	050S	060W	4301351513	Indian	OW	APD
UTE TRIBAL 1-16-55	16	050S	050W	4301351519	Indian	OW	APD
CC Tribal 3-27D-38	27	030S	080W	4301351604	Indian	OW	APD
LC FEE 10-36D-56	36	050S	060W	4301351622	Fee	OW	APD
Myrin Fee 3-16D-55	16	050S	050W	4301351633	Fee	OW	APD
LC TRIBAL 12H-34-56	34	050S	060W	4301351634	Indian	OW	APD
UTE FEE 12-16D-55	16	050S	050W	4301351635	Fee	OW	APD
LC TRIBAL 15-27-56	27	050S	060W	4301351649	Indian	OW	APD
LC TRIBAL 11-27D-56	27	050S	060W	4301351650	Indian	OW	APD
LC TRIBAL 1-17-56	17	050S	060W	4301351704	Indian	OW	APD
LC Tribal 13-11D-58	11	050S	080W	4301351708	Indian	OW	APD
LC Tribal 15-11D-58	11	050S	080W	4301351709	Indian	OW	APD
LC Tribal 4HW-8-56	8	050S	060W	4301351710	Indian	OW	APD
LC FEE 1-11D-56	11	050S	060W	4301351712	Fee	OW	APD
LC TRIBAL 3-11D-56	11	050S	060W	4301351713	Indian	OW	APD
LC TRIBAL 7-11D-56	11	050S	060W	4301351714	Indian	OW	APD
LC TRIBAL 9-34D-45	34	040S	050W	4301351717	Indian	OW	APD
LC Tribal 8M-23-45	23	040S	050W	4301351722	Indian	OW	APD
LC TRIBAL 4-34D-45	34	040S	050W	4301351723	Indian	OW	APD
LC TRIBAL 7-34D-45	34	040S	050W	4301351724	Indian	OW	APD
LC Tribal 3-14D-58	11	050S	080W	4301351726	Indian	OW	APD
LC Tribal 11-11D-58	11	050S	080W	4301351729	Indian	OW	APD
LC TRIBAL 8-31D-56	31	050S	060W	4301351746	Indian	OW	APD
LC TRIBAL 13-34D-45	34	040S	050W	4301351747	Indian	OW	APD
LC Fee 2-6D-57	6	050S	070W	4301351749	Fee	OW	APD
LC Tribal 15-12D-58	12	050S	080W	4301351783	Indian	OW	APD
LC Tribal 9-12D-58	12	050S	080W	4301351784	Indian	OW	APD
LC Tribal 1-13D-58	12	050S	080W	4301351785	Indian	OW	APD
LC Tribal 13-7D-57	12	050S	080W	4301351786	Indian	OW	APD
LC Tribal 9-2D-58	2	050S	080W	4301351788	Indian	OW	APD
LC Tribal 1-2D-58	2	050S	080W	4301351789	Indian	OW	APD
LC Tribal 5-1D-58	2	050S	080W	4301351790	Indian	OW	APD
LC TRIBAL 12-31D-56	31	050S	060W	4301351799	Indian	OW	APD
LC TRIBAL 8-20D-56	20	050S	060W	4301351800	Indian	OW	APD
LC TRIBAL 6-31D-56	31	050S	060W	4301351801	Indian	OW	APD
LC Tribal 11-7D-57	7	050S	070W	4301351814	Indian	OW	APD
LC Tribal 5-7D-57	7	050S	070W	4301351815	Indian	OW	APD
LC Fee 15-6D-57	6	050S	070W	4301351816	Fee	OW	APD
LC Tribal 11-6D-57	6	050S	070W	4301351817	Indian	OW	APD
LC TRIBAL 9-27-56	27	050S	060W	4301351822	Indian	OW	APD
LC TRIBAL 7-27D-56	27	050S	060W	4301351823	Indian	OW	APD

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

LC Fee 7-31D-45	31	040S	050W	4301351857	Fee	OW	APD
LC Tribal 5-31D-45	31	040S	050W	4301351858	Indian	OW	APD
LC Tribal 8-33-45	33	040S	050W	4301351859	Indian	OW	APD
LC Tribal 16-31-45	31	040S	050W	4301351863	Indian	OW	APD
LC Tribal 7-23D-45	23	040S	050W	4301351865	Indian	OW	APD
LC Tribal 1-23D-56	23	050S	060W	4301351866	Indian	OW	APD
LC TRIBAL 1-19-56	19	050S	060W	4301351867	Indian	OW	APD
LC TRIBAL 7-19D-56	19	050S	060W	4301351868	Indian	OW	APD
LC TRIBAL 9-4D-56	4	050S	060W	4301351869	Indian	OW	APD
LC Tribal 14-32D-45	32	040S	050W	4301351879	Indian	OW	APD
LC TRIBAL 7-17D-56	17	050S	060W	4301351886	Indian	OW	APD
LC TRIBAL 5-17D-56	17	050S	060W	4301351887	Indian	OW	APD
LC FEE 4-32D-45	31	040S	050W	4301351892	Fee	OW	APD
LC TRIBAL 9-2D-56	2	050S	060W	4301351893	Indian	OW	APD
LC TRIBAL 1-2D-56	2	050S	060W	4301351894	Indian	OW	APD
LC Tribal 15-23D-45	23	040S	050W	4301351895	Indian	OW	APD
LC TRIBAL 11-34D-56	34	050S	060W	4301351900	Indian	OW	APD
LC TRIBAL 9-5D-56	4	050S	060W	4301351901	Indian	OW	APD
LC Tribal 10-28D-45	28	040S	050W	4301351903	Indian	OW	APD
LC TRIBAL 13-20D-56	20	050S	060W	4301351904	Indian	OW	APD
Ute Tribal 14-17-55	17	050S	050W	4301351908	Indian	OW	APD
LC Tribal 3-27D-45	27	040S	050W	4301351911	Indian	OW	APD
LC TRIBAL 9-34D-56	34	050S	060W	4301351914	Indian	OW	APD
CC Fee 8R-9-37	9	030S	070W	4301351937	Fee	OW	APD
LC Tribal 10-33D-45	33	040S	050W	4301351939	Indian	OW	APD
LC Tribal 14-33D-45	33	040S	050W	4301351940	Indian	OW	APD
LC Tribal 10-27D-45	27	040S	050W	4301351941	Indian	OW	APD
LC Tribal 14-27D-45	27	040S	050W	4301351951	Indian	OW	APD
LC Tribal 6-33D-45	33	040S	050W	4301351955	Indian	OW	APD
LC Tribal 6-32D-45	32	040S	050W	4301351956	Indian	OW	APD
Federal 3-11D-65	11	060S	050W	4301351982	Federal	OW	APD
Federal 2-4-64	4	060S	040W	4301351983	Federal	OW	APD
Federal 5-11D-65	11	060S	050W	4301351984	Federal	OW	APD
Federal 7-4D-64	4	060S	040W	4301351985	Federal	OW	APD
Federal 3-4D-64	4	060S	040W	4301351986	Federal	OW	APD
Federal 8-4D-64	4	060S	040W	4301351988	Federal	OW	APD
Federal 6-4D-64	4	060S	040W	4301351989	Federal	OW	APD
Federal 7-9D-64	9	060S	040W	4301351990	Federal	OW	APD
Federal 4-4D-64	4	060S	040W	4301351991	Federal	OW	APD
Federal 9-4D-64	4	060S	040W	4301352004	Federal	OW	APD
Federal 10-4D-64	4	060S	040W	4301352011	Federal	OW	APD
Federal 3-9D-64	9	060S	040W	4301352015	Federal	OW	APD
Federal 1-9D-64	9	060S	040W	4301352020	Federal	OW	APD
Federal 6-9-64	9	060S	040W	4301352021	Federal	OW	APD
Federal 8-9D-64	9	060S	040W	4301352023	Federal	OW	APD
Federal 1-4D-64	4	060S	040W	4301352025	Federal	OW	APD
Federal 16-4D-64	4	060S	040W	4301352026	Federal	OW	APD
LC Tribal 10-23D-45	23	040S	050W	4301352029	Indian	OW	APD
Federal 15-4D-64	4	060S	040W	4301352032	Federal	OW	APD
Federal 5-9D-64	9	060S	040W	4301352035	Federal	OW	APD
Federal 9-9D-64	9	060S	040W	4301352036	Federal	OW	APD
Federal 11-9D-64	9	060S	040W	4301352037	Federal	OW	APD
Federal 12-9D-64	9	060S	040W	4301352038	Federal	OW	APD
Federal 13-9D-64	9	060S	040W	4301352039	Federal	OW	APD
FEDERAL 14-9D-64	9	060S	040W	4301352040	Federal	OW	APD
Federal 10-9D-64	9	060S	040W	4301352041	Federal	OW	APD
Federal 2-9D-64	9	060S	040W	4301352042	Federal	OW	APD
Federal 15-9D-64	9	060S	040W	4301352043	Federal	OW	APD
Federal 16-9D-64	9	060S	040W	4301352044	Federal	OW	APD
LC Tribal 10-32D-45	32	040S	050W	4301352065	Indian	OW	APD
LC Tribal 16-28D-45	28	040S	050W	4301352073	Indian	OW	APD
LC Tribal 15-24D-45	24	040S	050W	4301352074	Indian	OW	APD
LC Tribal 13-17D-56	17	050S	060W	4301352076	Indian	OW	APD
LC Tribal 15-17D-56	17	050S	060W	4301352077	Indian	OW	APD
LC Tribal 5-26D-56	26	050S	060W	4301352097	Indian	OW	APD
LC Tribal 11-26D-56	26	050S	060W	4301352098	Indian	OW	APD

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

LC Tribal 13-26D-56	26	050S	060W	4301352099	Indian	OW	APD	
LC Tribal 2-27D-45	27	040S	050W	4301352100	Indian	OW	APD	
LC Tribal 8-27D-45	27	040S	050W	4301352101	Indian	OW	APD	
LC Tribal 4-9D-56	9	050S	060W	4301352102	Indian	OW	APD	
LC Tribal 8-32D-45	32	040S	050W	4301352135	Indian	OW	APD	
UTE Tribal 15-24D-54	24	050S	040W	4301352156	Indian	GW	APD	
UTE Tribal 9-24D-54	24	050S	040W	4301352157	Indian	GW	APD	
UTE Tribal 1-25D-54	25	050S	040W	4301352173	Indian	GW	APD	
UTE Tribal 9-25D-54	25	050S	040W	4301352177	Indian	GW	APD	
Myrin Tribal 9-10D-55	10	050S	050W	4301352189	Indian	OW	APD	
Myrin Tribal 16-10D-55	10	050S	050W	4301352190	Indian	OW	APD	
Myrin Tribal 10-10D-55	10	050S	050W	4301352191	Indian	OW	APD	
UTE Tribal 1-24D-54	24	050S	040W	4301352304	Indian	GW	APD	
UTE Tribal 7-24D-54	24	050S	040W	4301352306	Indian	GW	APD	
UTE Tribal 12-25D-54	25	050S	040W	4301352308	Indian	GW	APD	
UTE Tribal 4-13D-54	13	050S	040W	4301352321	Indian	GW	APD	
UTE Tribal 13-25D-54	25	050S	040W	4301352322	Indian	GW	APD	
Abbott Fee 1-6D-54	6	050S	040W	4301352324	Fee	OW	APD	
Abbott Fee 7-6D-54	6	050S	040W	4301352327	Fee	OW	APD	
UTE Tribal 3-24D-54	24	050S	040W	4301352347	Indian	GW	APD	
UTE Tribal 5-24D-54	24	050S	040W	4301352348	Indian	GW	APD	
State Tribal 7-12D-55	12	050S	050W	4301352369	Indian	OW	APD	
State Tribal 14-1D-55	1	050S	050W	4301352372	Indian	OW	APD	
State Tribal 11-1D-55	1	050S	050W	4301352373	Indian	OW	APD	
State Tribal 13-1D-55	1	050S	050W	4301352374	Indian	OW	APD	
State Tribal 12-2D-55	2	050S	050W	4301352391	Indian	OW	APD	
State Tribal 14-2D-55	2	050S	050W	4301352392	Indian	OW	APD	
State Tribal 13-2D-55	2	050S	050W	4301352393	Indian	OW	APD	
State Tribal 14-3D-55	3	050S	050W	4301352430	Indian	OW	APD	
State Tribal 11-3D-55	3	050S	050W	4301352434	Indian	OW	APD	
State Tribal 13-3D-55	3	050S	050W	4301352435	Indian	OW	APD	
UTE TRIBAL 2-5D-55	5	050S	050W	4301352450	Indian	OW	APD	
Ute Tribal 1-5D-55	5	050S	050W	4301352456	Indian	OW	APD	BRUNDAGE CANYON
Ute Tribal 7-5-55	5	050S	050W	4301352459	Indian	OW	APD	
Ute Tribal 3-16D-54	9	050S	040W	4301352467	Indian	OW	APD	
State Tribal 1-3D-55	3	050S	050W	4301352471	Indian	OW	APD	
State Tribal 2-3D-55	3	050S	050W	4301352472	Indian	OW	APD	
State Tribal 7-3D-55	3	050S	050W	4301352473	Indian	OW	APD	
State Tribal 8-3D-55	3	050S	050W	4301352474	Indian	OW	APD	
UTE FEE 10-9D-54	9	050S	040W	4301352475	Fee	OW	APD	
UTE FEE 12-9D-54	9	050S	040W	4301352476	Fee	OW	APD	
UTE FEE 16-9D-54	9	050S	040W	4301352478	Fee	OW	APD	
Ute Tribal 2-16D-54	9	050S	040W	4301352481	Indian	OW	APD	
Federal 14-6D-65	6	060S	050W	4301352495	Federal	OW	APD	
Federal 13-6D-65	6	060S	050W	4301352496	Federal	OW	APD	
Federal 11-6D-65	6	060S	050W	4301352497	Federal	OW	APD	
Federal 10-6D-65	6	060S	050W	4301352498	Federal	OW	APD	
State Tribal 3-3D-55	3	050S	050W	4301352532	Indian	OW	APD	
State Tribal 4-3D-55	3	050S	050W	4301352533	Indian	OW	APD	
State Tribal 5-3D-55	3	050S	050W	4301352535	Indian	OW	APD	
State Tribal 6-3D-55	3	050S	050W	4301352536	Indian	OW	APD	
Federal 2-7D-65	7	060S	050W	4301352537	Federal	OW	APD	
Federal 5-7D-65	7	060S	050W	4301352538	Federal	OW	APD	
Federal 4-7D-65	7	060S	050W	4301352541	Federal	OW	APD	
UTE FEE 11-9D-54	9	050S	040W	4301352544	Fee	OW	APD	
UTE TRIBAL 15-12D-55	12	050S	050W	4301352549	Indian	OW	APD	
UTE TRIBAL 6-5D-55	5	050S	050W	4301352556	Indian	OW	APD	
UTE TRIBAL 5-5D-55	5	050S	050W	4301352557	Indian	OW	APD	
UTE TRIBAL 4-5D-55	5	050S	050W	4301352558	Indian	OW	APD	
UTE TRIBAL 3-5D-55	5	050S	050W	4301352559	Indian	OW	APD	
Federal 3-7-65	7	060S	050W	4301352560	Federal	OW	APD	
Ute Tribal 9-11D-55	11	050S	050W	4301352564	Indian	OW	APD	
UTE TRIBAL 10-11D-55	11	050S	050W	4301352566	Indian	OW	APD	
UTE TRIBAL 15-11D-55	11	050S	050W	4301352567	Indian	OW	APD	
Federal 1-7D-65	6	060S	050W	4301352589	Federal	OW	APD	
Federal 16-6D-65	6	060S	050W	4301352590	Federal	OW	APD	

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

Federal 15-6D-65	6	060S	050W	4301352591	Federal	OW	APD
UTE TRIBAL 14-12D-55	12	050S	050W	4301352592	Indian	OW	APD
UTE TRIBAL 13-12D-55	12	050S	050W	4301352593	Indian	OW	APD
UTE TRIBAL 10-11D-54	11	050S	040W	4301352603	Indian	OW	APD
UTE TRIBAL 9-11D-54	11	050S	040W	4301352604	Indian	OW	APD
UTE TRIBAL 15-11-54	11	050S	040W	4301352605	Indian	OW	APD
UTE TRIBAL 16-11D-54	11	050S	040W	4301352606	Indian	OW	APD
UTE TRIBAL 14-11D-55	11	050S	050W	4301352610	Indian	OW	APD
UTE TRIBAL 13-11D-55	11	050S	050W	4301352611	Indian	OW	APD
UTE TRIBAL 12-11D-55	11	050S	050W	4301352612	Indian	OW	APD
UTE TRIBAL 11-11D-55	11	050S	050W	4301352613	Indian	OW	APD
Federal 6-7D-65	7	060S	050W	4301352682	Federal	OW	APD
Federal 11-7D-65	7	060S	050W	4301352683	Federal	OW	APD
Federal 10-7D-65	7	060S	050W	4301352684	Federal	OW	APD
Federal 7-7D-65	7	060S	050W	4301352685	Federal	OW	APD
UTE TRIBAL 14-30D-55	30	050S	050W	4301352687	Indian	OW	APD
UTE TRIBAL 13-30D-55	30	050S	050W	4301352688	Indian	OW	APD
UTE TRIBAL 12-30D-55	30	050S	050W	4301352689	Indian	OW	APD
UTE TRIBAL 11-30D-55	30	050S	050W	4301352690	Indian	OW	APD
UTE TRIBAL 7-17D-55	17	050S	050W	4301352691	Indian	OW	APD
UTE TRIBAL 6-17D-55	17	050S	050W	4301352692	Indian	OW	APD
UTE TRIBAL 3-17D-55	17	050S	050W	4301352693	Indian	OW	APD
UTE TRIBAL 2-17D-55	17	050S	050W	4301352694	Indian	OW	APD
UTE TRIBAL 4-17D-55	17	050S	050W	4301352695	Indian	OW	APD
State Tribal 3-12D-55	12	050S	050W	4301352697	Indian	OW	APD
State Tribal 4-12D-55	12	050S	050W	4301352698	Indian	OW	APD
UTE TRIBAL 12-31D-55	31	050S	050W	4301352699	Indian	OW	APD
UTE TRIBAL 13-31D-55	31	050S	050W	4301352700	Indian	OW	APD
UTE TRIBAL 14-31D-55	31	050S	050W	4301352701	Indian	OW	APD
UTE TRIBAL 14-13D-54	13	050S	040W	4301352702	Indian	OW	APD
UTE TRIBAL 11-31-55	31	050S	050W	4301352703	Indian	OW	APD
State Tribal 3-11D-55	11	050S	050W	4301352704	Indian	OW	APD
State Tribal 4-11D-55	11	050S	050W	4301352705	Indian	OW	APD
State Tribal 5-11D-55	11	050S	050W	4301352706	Indian	OW	APD
State Tribal 6-11D-55	11	050S	050W	4301352707	Indian	OW	APD
State Tribal 8-11D-55	11	050S	050W	4301352708	Indian	OW	APD
State Tribal 7-11D-55	11	050S	050W	4301352709	Indian	OW	APD
State Tribal 2-11D-55	11	050S	050W	4301352710	Indian	OW	APD
State Tribal 1-11D-55	11	050S	050W	4301352711	Indian	OW	APD
UTE TRIBAL 9-4D-55	4	050S	050W	4301352713	Indian	OW	APD
State Tribal 2-10D-55	10	050S	050W	4301352714	Indian	OW	APD
State Tribal 7-10D-55	10	050S	050W	4301352715	Indian	OW	APD
State Tribal 8-10D-55	10	050S	050W	4301352716	Indian	OW	APD
UTE TRIBAL 10-4D-55	4	050S	050W	4301352717	Indian	OW	APD
UTE TRIBAL 15-4D-55	4	050S	050W	4301352718	Indian	OW	APD
State Tribal 1-10D-55	10	050S	050W	4301352720	Indian	OW	APD
UTE TRIBAL 16-4D-55	4	050S	050W	4301352721	Indian	OW	APD
State Tribal 3-10D-55	10	050S	050W	4301352723	Indian	OW	APD
State Tribal 4-10D-55	10	050S	050W	4301352724	Indian	OW	APD
State Tribal 5-10D-55	10	050S	050W	4301352725	Indian	OW	APD
State Tribal 6-10D-55	10	050S	050W	4301352726	Indian	OW	APD
UTE TRIBAL 11-5D-55	5	050S	050W	4301352727	Indian	OW	APD
UTE TRIBAL 12-5D-55	5	050S	050W	4301352728	Indian	OW	APD
UTE TRIBAL 13-5D-55	5	050S	050W	4301352729	Indian	OW	APD
UTE TRIBAL 14-5D-55	5	050S	050W	4301352730	Indian	OW	APD
UTE TRIBAL 9-30D-55	30	050S	050W	4301352731	Indian	OW	APD
State Tribal 15-2D-55	2	050S	050W	4301352732	Indian	OW	APD
State Tribal 16-2D-55	2	050S	050W	4301352733	Indian	OW	APD
State Tribal 10-2D-55	2	050S	050W	4301352734	Indian	OW	APD
State Tribal 9-2D-55	2	050S	050W	4301352735	Indian	OW	APD
UTE TRIBAL 10-30D-55	30	050S	050W	4301352736	Indian	OW	APD
UTE TRIBAL 15-30D-55	30	050S	050W	4301352737	Indian	OW	APD
UTE TRIBAL 16-30D-55	30	050S	050W	4301352738	Indian	OW	APD
Myrin Tribal 9-19D-55	19	050S	050W	4301352739	Indian	OW	APD
State Tribal 16-3D-55	3	050S	050W	4301352740	Indian	OW	APD
State Tribal 15-3D-55	3	050S	050W	4301352741	Indian	OW	APD

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

State Tribal 10-3D-55	3	050S	050W	4301352742		Indian	OW	APD	
State Tribal 9-3D-55	3	050S	050W	4301352743		Indian	OW	APD	
Myrin Tribal 15-19D-55	19	050S	050W	4301352744		Indian	OW	APD	
Myrin Tribal 13-19D-55	19	050S	050W	4301352745		Indian	OW	APD	
Myrin Tribal 12-19D-55	19	050S	050W	4301352746		Indian	OW	APD	
UTE TRIBAL 5-4D-55	4	050S	050W	4301352747		Indian	OW	APD	
UTE TRIBAL 4-4D-55	4	050S	050W	4301352748		Indian	OW	APD	
UTE TRIBAL 3-4D-55	4	050S	050W	4301352749		Indian	OW	APD	
UTE TRIBAL 6-4D-55	4	050S	050W	4301352754		Indian	OW	APD	
UTE TRIBAL 3-31D-55	31	050S	050W	4301352757		Indian	OW	APD	
UTE TRIBAL 5-31D-55	31	050S	050W	4301352758		Indian	OW	APD	
UTE TRIBAL 6-31D-55	31	050S	050W	4301352759		Indian	OW	APD	
UTE TRIBAL 7-31D-55	31	050S	050W	4301352764		Indian	OW	APD	
Myrin Tribal 11-19D-55	19	050S	050W	4301352765		Indian	OW	APD	
Federal 8-14D-65	14	060S	050W	4301352767		Federal	OW	APD	
Federal 7-14D-65	14	060S	050W	4301352768		Federal	OW	APD	
Federal 2-14D-65	14	060S	050W	4301352769		Federal	OW	APD	
Federal 1-14D-65	14	060S	050W	4301352770		Federal	OW	APD	
UTE TRIBAL 8-5D-55	5	050S	050W	4301352773		Indian	OW	APD	
UTE TRIBAL 4-31D-55	31	050S	050W	4301352795		Indian	OW	APD	
UTE TRIBAL 4-30D-55	30	050S	050W	4301352796		Indian	OW	APD	
UTE TRIBAL 5-30D-55	30	050S	050W	4301352797		Indian	OW	APD	
UTE TRIBAL 7-30D-55	30	050S	050W	4301352799		Indian	OW	APD	
Federal 1-13D-65	13	060S	050W	4301352800		Federal	OW	APD	
Federal 7-13D-65	13	060S	050W	4301352802		Federal	OW	APD	
UTE TRIBAL 1-30D-55	30	050S	050W	4301352809		Indian	OW	APD	
LC TRIBAL 6-25D-56	25	050S	060W	4301352810		Indian	OW	APD	
LC TRIBAL 4-25D-56	25	050S	060W	4301352812		Indian	OW	APD	
Federal 6-13D-65	13	060S	050W	4301352813		Federal	OW	APD	
Federal 4-13D-65	13	060S	050W	4301352814		Federal	OW	APD	
Federal 3-13D-65	13	060S	050W	4301352815		Federal	OW	APD	
Federal 3-16D-64	16	060S	040W	4301352823		Federal	OW	APD	
Federal 4-16D-64	16	060S	040W	4301352824		Federal	OW	APD	
Federal 5-16D-64	16	060S	040W	4301352825		Federal	OW	APD	
Federal 6-16D-64	16	060S	040W	4301352826		Federal	OW	APD	
Federal 5-13D-65	13	060S	050W	4301352827		Federal	OW	APD	
LC TRIBAL 1-25D-56	25	050S	060W	4301352835		Indian	OW	APD	
LC TRIBAL 2-25D-56	25	050S	060W	4301352836		Indian	OW	APD	
LC TRIBAL 8-25D-56	25	050S	060W	4301352837		Indian	OW	APD	
UTE FEE 1-13D-55	13	050S	050W	4301352838		Fee	OW	APD	
LC TRIBAL 9-25D-56	25	050S	060W	4301352840		Indian	OW	APD	
LC TRIBAL 15-25-56	25	050S	060W	4301352844		Indian	OW	APD	
Federal 9-5D-65	5	060S	050W	4301352846		Federal	OW	APD	
Federal 10-5D-65	5	060S	050W	4301352847		Federal	OW	APD	
LC TRIBAL 16-25D-56	25	050S	060W	4301352848		Indian	OW	APD	
LC TRIBAL 10-25D-56	25	050S	060W	4301352849		Indian	OW	APD	
UTE TRIBAL 8-30D-55	29	050S	050W	4301352855		Indian	OW	APD	
UTE TRIBAL 9-29D-55	29	050S	050W	4301352870		Indian	OW	APD	
UTE TRIBAL 6-24D-55	24	050S	050W	4301352871		Indian	OW	APD	
UTE TRIBAL 16-17D-55	17	050S	050W	4301352872		Indian	OW	APD	
UTE TRIBAL 13-27D-55	27	050S	050W	4301352882		Indian	OW	APD	
UTE TRIBAL 4-29D-55	29	050S	050W	4301352883		Indian	OW	APD	
UTE TRIBAL 1-29D-55	29	050S	050W	4301352884		Indian	OW	APD	
Federal 4-2D-65	2	060S	050W	4301352885		Federal	OW	APD	
Federal 5-2D-65	2	060S	050W	4301352886		Federal	OW	APD	
Federal 12-2D-65	2	060S	050W	4301352887		Federal	OW	APD	
LC TRIBAL 12-25D-56	25	050S	060W	4301352888		Indian	OW	APD	
LC TRIBAL 13-25D-56	25	050S	060W	4301352890		Indian	OW	APD	
LC TRIBAL 14-25D-56	25	050S	060W	4301352891		Indian	OW	APD	
Federal 15-3D-65	3	060S	050W	4301352892		Federal	OW	APD	
Federal 9-3D-65	3	060S	050W	4301352893		Federal	OW	APD	
Federal 8-3D-65	3	060S	050W	4301352894		Federal	OW	APD	
Federal 6-3D-65	3	060S	050W	4301352895		Federal	OW	APD	
UTE TRIBAL 6-28D-55	28	050S	050W	4301334056	18593	Indian	OW	DRL	
MOON TRIBAL 9-27D-54	27	050S	040W	4301334108	19095	Indian	OW	DRL	
LC TRIBAL 9-16D-56	16	050S	060W	4301350600	99999	Indian	OW	DRL	

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

FEDERAL 15-6D-64	6	060S	040W	4301351219	18793	Federal	OW	DRL	
UTE TRIBAL 9-21D-55	21	050S	050W	4301351258	19401	Indian	OW	DRL	
STATE TRIBAL 2-12D-55	12	050S	050W	4301351310	19444	Indian	OW	DRL	
UTE TRIBAL 7-10D-54	10	050S	040W	4301351365	19391	Indian	OW	DRL	
LC TRIBAL 9-26D-56	26	050S	060W	4301351381	19433	Indian	OW	DRL	
UTE TRIBAL 8-17D-55	17	050S	050W	4301351413	19388	Indian	OW	DRL	
LC TRIBAL 9-24D-45	24	040S	050W	4301351431	18861	Indian	OW	DRL	
LC TRIBAL 2-29D-45	29	040S	050W	4301351705	99999	Indian	OW	DRL	
LC TAYLOR FEE 14-22D-56	22	050S	060W	4301351744	19508	Fee	OW	DRL	
LC FEE 14-6D-56	6	050S	060W	4301351787	18910	Fee	OW	DRL	
LC FEE 15-6-56	6	050S	060W	4301351792	19334	Fee	OW	DRL	
LC Fee 14-36D-56	36	050S	060W	4301351878	19376	Fee	OW	DRL	
LC Fee 12-36-56	36	050S	060W	4301351883	19377	Fee	OW	DRL	
LC Tribal 6-29D-45	29	040S	050W	4301351902	19402	Indian	OW	DRL	
Federal 4-6D-65	6	060S	050W	4301352005	19173	Federal	OW	DRL	
Federal 12-6D-65	6	060S	050W	4301352006	19174	Federal	OW	DRL	
UTE Tribal 14-18D-54	18	050S	040W	4301352213	19509	Indian	GW	DRL	
UTE Tribal 15-31D-55	31	050S	050W	4301352309	19472	Indian	GW	DRL	
UTE Tribal 16-31D-55	31	050S	050W	4301352318	19473	Indian	GW	DRL	
State Tribal 1-12D-55	12	050S	050W	4301352390	19445	Indian	OW	DRL	
State Tribal 16-6D-54	6	050S	040W	4301352394	19424	Indian	OW	DRL	
State Tribal 10-6D-54	6	050S	040W	4301352395	19425	Indian	OW	DRL	
State Tribal 9-6D-54	6	050S	040W	4301352396	19426	Indian	OW	DRL	
State Tribal 7-7D-54	7	050S	040W	4301352426	19496	Indian	OW	DRL	
State Tribal 1-7D-54	7	050S	040W	4301352427	19497	Indian	OW	DRL	
State Tribal 2-7D-54	7	050S	040W	4301352428	19498	Indian	OW	DRL	
State Tribal 3-7D-54	7	050S	040W	4301352429	19517	Indian	OW	DRL	
State Tribal 4-7D-54	7	050S	040W	4301352431	99999	Indian	OW	DRL	
State Tribal 5-7D-54	7	050S	040W	4301352432	99999	Indian	OW	DRL	
State Tribal 6-7D-54	7	050S	040W	4301352433	19518	Indian	OW	DRL	
State Tribal 11-6D-54	6	050S	040W	4301352452	19474	Indian	OW	DRL	
State Tribal 12-6D-54	6	050S	040W	4301352453	19475	Indian	OW	DRL	
State Tribal 13-6D-54	6	050S	040W	4301352454	19476	Indian	OW	DRL	
State Tribal 14-6D-54	6	050S	040W	4301352455	19477	Indian	OW	DRL	
Ute Tribal 1-9D-54	9	050S	040W	4301352465	19356	Indian	OW	DRL	
Ute Tribal 7-9D-54	9	050S	040W	4301352466	19357	Indian	OW	DRL	
UTE TRIBAL 12-5D-54	5	050S	040W	4301352480	19499	Indian	OW	DRL	
UTE TRIBAL 13-5D-54	5	050S	040W	4301352484	19500	Indian	OW	DRL	
UTE TRIBAL 14-5D-54	5	050S	040W	4301352493	19510	Indian	OW	DRL	
State Tribal 13-11D-54	10	050S	040W	4301352561	19519	Indian	OW	DRL	
State Tribal 1-18D-54	18	050S	040W	4301352568	19434	Indian	OW	DRL	
State Tribal 2-18D-54	18	050S	040W	4301352576	19427	Indian	OW	DRL	
State Tribal 8-18D-54	18	050S	040W	4301352577	19428	Indian	OW	DRL	
State Tribal 4-18D-54	18	050S	040W	4301352607	19435	Indian	OW	DRL	
State Tribal 3-18D-54	18	050S	040W	4301352608	19436	Indian	OW	DRL	
State Tribal 6-18D-54	18	050S	040W	4301352609	19437	Indian	OW	DRL	
State Tribal 5-12-55	12	050S	050W	4301352643	19446	Indian	OW	DRL	
State Tribal 12-12D-55	12	050S	050W	4301352644	19447	Indian	OW	DRL	
State Tribal 6-12D-55	12	050S	050W	4301352645	19438	Indian	OW	DRL	
State Tribal 16-1D-55	1	050S	050W	4301352646	19483	Indian	OW	DRL	
State Tribal 15-1D-55	1	050S	050W	4301352647	19484	Indian	OW	DRL	
State Tribal 10-1D-55	1	050S	050W	4301352648	19485	Indian	OW	DRL	
State Tribal 9-1D-55	1	050S	050W	4301352649	19486	Indian	OW	DRL	
LC FEE 16-15D-56	14	050S	060W	4301352655	19520	Fee	OW	DRL	
LC Tribal 2-22D-56	22	050S	060W	4301352663	99999	Indian	OW	DRL	
LC Tribal 3-22D-56	22	050S	060W	4301352664	99999	Indian	OW	DRL	
Federal 2-13-65	13	060S	050W	4301352801	19501	Federal	OW	DRL	
Federal 8-13D-65	13	060S	050W	4301352803	19502	Federal	OW	DRL	
Federal 12-8D-64	7	060S	040W	4301352832	99999	Federal	OW	DRL	
Federal 5-8D-64	7	060S	040W	4301352833	99999	Federal	OW	DRL	
Federal 4-8D-64	7	060S	040W	4301352834	99999	Federal	OW	DRL	
Federal 3-8D-64	5	060S	040W	4301352845	19503	Federal	OW	DRL	
LC TRIBAL 4H-31-56	31	050S	060W	4301351738		Indian	OW	NEW	
Federal 14-7D-65	31	050S	060W	4301351910		Indian	OW	NEW	
LC Fee 11-22-57	22	050S	070W	4301352127		Fee	OW	NEW	
LC Fee 13-22D-57	22	050S	070W	4301352131		Fee	OW	NEW	

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

LC Tribal 5-22D-57	22	050S	070W	4301352133		Indian	OW	NEW	
LC Tribal 15-22D-57	22	050S	070W	4301352134		Indian	OW	NEW	
LC Tribal 11-18D-56	18	050S	060W	4301352140		Indian	OW	NEW	
LC Tribal 13-18D-56	18	050S	060W	4301352141		Indian	OW	NEW	
LC Tribal 15-18D-56	18	050S	060W	4301352142		Indian	OW	NEW	
LC Tribal 7-18D-56	18	050S	060W	4301352153		Indian	OW	NEW	
LC Tribal 5-18D-56	18	050S	060W	4301352154		Indian	OW	NEW	
LC Tribal 3-18-56	18	050S	060W	4301352155		Indian	OW	NEW	
LC Tribal 6-19D-56	19	050S	060W	4301352247		Indian	OW	NEW	
LC Tribal 4-19D-56	19	050S	060W	4301352248		Indian	OW	NEW	
Abbott Fee 3-6D-54	6	050S	040W	4301352325		Fee	OW	NEW	
LC Fee 9-11D-56	11	050S	060W	4301352479		Fee	OW	NEW	
Williams Tribal 8-4D-54	4	050S	040W	4301352650		Indian	OW	NEW	
Williams Tribal 7-4D-54	4	050S	040W	4301352651		Indian	OW	NEW	
Williams Tribal 2-4D-54	4	050S	040W	4301352652		Indian	OW	NEW	
Williams Tribal 1-4D-54	4	050S	040W	4301352653		Indian	OW	NEW	
Federal 9-8D-64	9	060S	040W	4301352880		Federal	OW	NEW	
Federal 16-8D-64	9	060S	040W	4301352881		Federal	OW	NEW	
LC Nielsen Tribal 6-33D-56	33	050S	060W	4301352896		Indian	OW	NEW	
LC Nielsen Tribal 2-33D-56	33	050S	060W	4301352897		Indian	OW	NEW	
LC Nielsen Tribal 4-33D-56	33	050S	060W	4301352898		Indian	OW	NEW	
LC Nielsen Tribal 5-33D-56	33	050S	060W	4301352899		Indian	OW	NEW	
UTE FEE 13-9D-54	9	050S	040W	4301352906		Fee	OW	NEW	
UTE FEE 2-34D-55	27	050S	050W	4301352971		Fee	OW	NEW	
Federal 13-7D-65	7	060S	050W	4301352974		Federal	OW	NEW	
Federal 14-7D-65	7	060S	050W	4301352975		Federal	OW	NEW	
UTE TRIBAL 6-27D-55	27	050S	050W	4301352976		Indian	OW	NEW	
LC Nielsen Tribal 12-27D-56	27	050S	060W	4301352977		Indian	OW	NEW	
LC Nielsen Tribal 13-27D-56	27	050S	060W	4301352978		Indian	OW	NEW	
LC Nielsen Tribal 16-28D-56	27	050S	060W	4301352979		Indian	OW	NEW	
LC Nielsen Fee 9-28D-56	27	050S	060W	4301352980		Fee	OW	NEW	
LC FEE 9-36D-56	36	050S	060W	4301352982		Fee	OW	NEW	
LC FEE 15-36D-56	36	050S	060W	4301352983		Fee	OW	NEW	
LC TRIBAL 6-36D-56	36	050S	060W	4301352984		Indian	OW	NEW	
LC TRIBAL 5-36D-56	36	050S	060W	4301352985		Indian	OW	NEW	
LC TRIBAL 4-36D-56	36	050S	060W	4301352986		Indian	OW	NEW	
LC TRIBAL 3-36D-56	36	050S	060W	4301352987		Indian	OW	NEW	
LC TRIBAL 2-35D-56	35	050S	060W	4301352988		Indian	OW	NEW	
LC TRIBAL 1-35D-56	35	050S	060W	4301352989		Indian	OW	NEW	
UTE TRIBAL 13-3R-54	3	050S	040W	4301330924	9488	Indian	OW	OPS	
UTE TRIBAL 3-20D-55	20	050S	050W	4301333280	18424	Indian	OW	OPS	
LC TRIBAL 4H-17-56	17	050S	060W	4301333540	18067	Indian	OW	OPS	
LC TRIBAL 16-21-46	21	040S	060W	4301333575	16156	Indian	OW	OPS	
UTE TRIBAL 8-20D-55	20	050S	050W	4301333676	17308	Indian	OW	OPS	
UTE TRIBAL 14-14D-55	14	050S	050W	4301333699	18409	Indian	OW	OPS	
UTE TRIBAL 5-29D-55	29	050S	050W	4301333740	17306	Indian	OW	OPS	
UTE TRIBAL 7-32D-55	32	050S	050W	4301333794	18359	Indian	OW	OPS	
UTE TRIBAL 12-27D-55	27	050S	050W	4301333798	18360	Indian	OW	OPS	
FOY 9-33D-55	33	050S	050W	4301333802	17125	Fee	OW	OPS	
BERRY TRIBAL 2-23D-54	23	050S	040W	4301333805	18546	Indian	OW	OPS	
UTE TRIBAL 13-29D-55	29	050S	050W	4301333807	18378	Indian	OW	OPS	
UTE TRIBAL 16-28D-55	28	050S	050W	4301333887	18594	Indian	OW	OPS	
LC FEE 8-15D-56	15	050S	060W	4301350597	19347	Fee	OW	OPS	
SFW FEE 13-10D-54	10	050S	040W	4301350892	19186	Fee	OW	OPS	
SFW TRIBAL 11-10D-54	10	050S	040W	4301350893	19215	Indian	OW	OPS	
LC TRIBAL 5HH-5-56	4	050S	060W	4301350927	18463	Indian	OW	OPS	
LC TRIBAL 16-34D-45	34	040S	050W	4301350977	18658	Indian	OW	OPS	
LC TRIBAL 3-4D-56	4	050S	060W	4301351000	18852	Indian	OW	OPS	
FEDERAL 7-12D-65	12	060S	050W	4301351058	18717	Federal	OW	OPS	
LC TRIBAL 2-33D-45	33	040S	050W	4301351402	18854	Indian	OW	OPS	
LC TRIBAL 9-3D-56	3	050S	060W	4301351514	18948	Indian	OW	OPS	
LC Tribal 3-34D-56	34	050S	060W	4301352087	19234	Indian	OW	OPS	
LC Tribal 7-34D-56	34	050S	060W	4301352088	19235	Indian	OW	OPS	
Ute Tribal 5-9D-54	9	050S	040W	4301352463	19354	Indian	OW	OPS	
Ute Tribal 3-9D-54	9	050S	040W	4301352464	19355	Indian	OW	OPS	
BC UTE TRIBAL 4-22	22	050S	040W	4301330755	2620	Indian	OW	P	

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

B C UTE TRIBAL 16-16	16	050S	040W	4301330841	9489	Indian	OW	P	
B C UTE TRIBAL 14-15	15	050S	040W	4301330842	9440	Indian	OW	P	
UTE TRIBAL 1-32R	32	050S	040W	4301330872	13020	Indian	OW	P	
UTE TRIBAL 23-3R	23	050S	040W	4301330886	13034	Indian	OW	P	
S COTTONWOOD RIDGE UTE TRIBAL 1-19	19	050S	040W	4301330933	9845	Indian	OW	P	BRUNDAGE CANYON
TABBY CYN UTE TRIBAL 1-25	25	050S	050W	4301330945	9722	Indian	OW	P	
S BRUNDAGE UTE TRIBAL 1-30	30	050S	040W	4301330948	9850	Indian	OW	P	
SOWERS CYN UTE TRIBAL 3-26	26	050S	050W	4301330955	10423	Indian	OW	P	
UTE TRIBAL 3-24R-55 (REENTRY)	24	050S	050W	4301330960	15173	Indian	OW	P	
UTE TRIBAL 1-20	20	050S	040W	4301330966	9925	Indian	OW	P	
T C UTE TRIBAL 9-23X	23	050S	050W	4301330999	9720	Indian	OW	P	
UTE TRIBAL 15-24R	24	050S	050W	4301331129	11985	Indian	OW	P	
S BRUNDAGE CYN UTE TRIBAL 4-27	27	050S	040W	4301331131	9851	Indian	OW	P	
UTE TRIBAL 5-13	13	050S	050W	4301331152	10421	Indian	OW	P	
UTE TRIBAL 7-20R-54	20	050S	040W	4301331281	14088	Indian	OW	P	
Z and T UTE TRIBAL 7-19	19	050S	040W	4301331282	11131	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 13-19	19	050S	040W	4301331284	11134	Indian	OW	P	
Z and T UTE TRIBAL 7-25	25	050S	050W	4301331310	11416	Indian	OW	P	
UTE TRIBAL 13-17	17	050S	040W	4301331546	11921	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 11-19	19	050S	040W	4301331547	11920	Indian	OW	P	
UTE TRIBAL 13-22	22	050S	040W	4301331548	11926	Indian	OW	P	
UTE TRIBAL 1-28	28	050S	040W	4301331549	11925	Indian	OW	P	
UTE TRIBAL 4-30	30	050S	040W	4301331550	11914	Indian	OW	P	
UTE TRIBAL 15-16	16	050S	040W	4301331648	11951	Indian	OW	P	
UTE TRIBAL 16-18	18	050S	040W	4301331650	11946	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 5-20	20	050S	040W	4301331651	11957	Indian	OW	P	
UTE TRIBAL 15-23	23	050S	050W	4301331671	11989	Indian	OW	P	
TABBY CANYON 1-21	21	050S	050W	4301331699	12225	Indian	OW	P	
TABBY CANYON 8-22	22	050S	050W	4301331700	12008	Indian	OW	P	
SOWERS CANYON 9-27	27	050S	050W	4301331701	11997	Indian	OW	P	
UTE TRIBAL 3-19	19	050S	040W	4301331830	12197	Indian	OW	P	
UTE TRIBAL 9-19	19	050S	040W	4301331831	12175	Indian	OW	P	
UTE TRIBAL 15-19	19	050S	040W	4301331832	12180	Indian	OW	P	
UTE TRIBAL 2-25	25	050S	050W	4301331833	12153	Indian	OW	P	
UTE TRIBAL 3-25	25	050S	050W	4301331834	12152	Indian	OW	P	
UTE TRIBAL 11-24	24	050S	050W	4301331909	12190	Indian	OW	P	
UTE TRIBAL 13-24	24	050S	050W	4301331910	12217	Indian	OW	P	
UTE TRIBAL 11-25	25	050S	050W	4301331911	12182	Indian	OW	P	
UTE TRIBAL 1-26	26	050S	050W	4301331912	12235	Indian	OW	P	
UTE TRIBAL 2-19	19	050S	040W	4301332140	12795	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 6-25H	25	050S	050W	4301332143	12750	Indian	OW	P	
UTE TRIBAL 9-18	18	050S	040W	4301332144	12746	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 11-17	17	050S	040W	4301332145	12747	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 12-17	17	050S	040W	4301332146	12745	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 14-17	17	050S	040W	4301332147	12755	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 15-18	18	050S	040W	4301332148	12794	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 6-22	22	050S	040W	4301332163	12974	Indian	OW	P	
UTE TRIBAL 6-21	21	050S	040W	4301332164	12994	Indian	OW	P	
UTE TRIBAL 7-28	28	050S	040W	4301332166	12995	Indian	OW	P	
UTE TRIBAL 11-20	20	050S	040W	4301332168	12946	Indian	OW	P	
UTE TRIBAL 13-25	25	050S	050W	4301332169	12857	Indian	OW	P	
UTE TRIBAL 2-27	27	050S	040W	4301332179	12975	Indian	OW	P	
UTE TRIBAL 1-33	33	050S	040W	4301332185	13024	Indian	OW	P	
UTE TRIBAL 1-34	34	050S	040W	4301332186	13121	Indian	OW	P	
UTE TRIBAL 2-35	35	050S	050W	4301332187	13021	Indian	OW	P	
UTE TRIBAL 4-36	36	050S	050W	4301332188	13063	Indian	OW	P	
UTE TRIBAL 5-28	28	050S	040W	4301332189	13026	Indian	OW	P	
UTE TRIBAL 5-31	31	050S	040W	4301332190	13080	Indian	OW	P	
UTE TRIBAL 9-26	26	050S	040W	4301332191	13101	Indian	OW	P	
UTE TRIBAL 11-28	28	050S	040W	4301332192	13022	Indian	OW	P	
UTE TRIBAL 3-29	29	050S	040W	4301332193	13042	Indian	OW	P	
UTE TRIBAL 5-19	19	050S	040W	4301332204	13090	Indian	OW	P	
UTE TRIBAL 12-15	15	050S	040W	4301332205	13100	Indian	OW	P	
UTE TRIBAL 13-20	20	050S	040W	4301332206	13048	Indian	OW	P	
UTE TRIBAL 1-24-55	24	050S	050W	4301332259	13618	Indian	OW	P	
UTE TRIBAL 3-28-54	28	050S	040W	4301332261	13644	Indian	OW	P	

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

UTE TRIBAL 5-24-55	24	050S	050W	4301332263	13621	Indian	OW	P	
UTE TRIBAL 5-26-55	26	050S	050W	4301332264	13642	Indian	OW	P	
UTE TRIBAL 6-36-55	36	050S	050W	4301332265	13600	Indian	OW	P	
UTE TRIBAL 9-24-55	24	050S	050W	4301332268	13620	Indian	OW	P	
UTE TRIBAL 11-23-55	23	050S	050W	4301332269	13572	Indian	OW	P	
UTE TRIBAL 15-25-55	25	050S	050W	4301332271	13566	Indian	OW	P	
UTE TRIBAL 16-14-55	14	050S	050W	4301332272	13567	Indian	OW	P	
UTE TRIBAL 15-27-55	27	050S	050W	4301332339	14020	Indian	OW	P	
UTE TRIBAL 5-15-55	15	050S	050W	4301332344	13606	Indian	OW	P	
UTE TRIBAL 7-20-55	20	050S	050W	4301332346	13607	Indian	OW	P	
MOON TRIBAL 12-23-54	23	050S	040W	4301332347	14008	Indian	OW	P	
UTE TRIBAL 14-28-55	28	050S	050W	4301332348	13580	Indian	OW	P	
UTE TRIBAL 16-29-55	29	050S	050W	4301332349	13581	Indian	OW	P	
UTE TRIBAL 2-32-55	32	050S	050W	4301332350	13695	Indian	OW	P	
UTE TRIBAL 16-35-55	35	050S	050W	4301332352	14267	Indian	OW	P	
UTE TRIBAL 10-35-55	35	050S	050W	4301332353	13645	Indian	OW	P	
UTE TRIBAL 12-36-55	36	050S	050W	4301332354	13643	Indian	OW	P	
UTE TRIBAL 14-36-55	36	050S	050W	4301332355	14262	Indian	OW	P	
UTE TRIBAL 16-36-55	36	050S	050W	4301332356	14122	Indian	OW	P	
UTE TRIBAL 4-33-55	33	050S	050W	4301332357	13685	Indian	OW	P	
UTE TRIBAL 15-17-55	17	050S	050W	4301332358	13698	Indian	OW	P	
UTE TRIBAL 12-14-54	14	050S	040W	4301332369	13647	Indian	OW	P	
UTE TRIBAL 3-20-54	20	050S	040W	4301332377	13955	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 4-21-54	21	050S	040W	4301332378	13907	Indian	OW	P	
UTE TRIBAL 9-20-54	20	050S	040W	4301332379	13906	Indian	OW	P	
UTE TRIBAL 5-30-54	30	050S	040W	4301332380	13905	Indian	OW	P	
UTE TRIBAL 16-21-54	21	050S	040W	4301332381	13912	Indian	OW	P	BERRY PILOT EOR 246-02
UTE TRIBAL 15-30-54	30	050S	040W	4301332382	13944	Indian	OW	P	
UTE TRIBAL 9-30-54	30	050S	040W	4301332383	14050	Indian	OW	P	
UTE TRIBAL 14-21-54	21	050S	040W	4301332384	13946	Indian	OW	P	
UTE TRIBAL 12-21-54	21	050S	040W	4301332385	13928	Indian	OW	P	
UTE TRIBAL 15-20-54	20	050S	040W	4301332386	13911	Indian	OW	P	
UTE TRIBAL 13-28-54	28	050S	040W	4301332387	13908	Indian	OW	P	
UTE TRIBAL 9-28-54	28	050S	040W	4301332388	13910	Indian	OW	P	
UTE TRIBAL 15-28-54	28	050S	040W	4301332389	13909	Indian	OW	P	
UTE TRIBAL 9-25-55	25	050S	050W	4301332390	13715	Indian	OW	P	
MOON TRIBAL 6-27-54	27	050S	040W	4301332407	13969	Indian	OW	P	
MOON TRIBAL 14-27-54	27	050S	040W	4301332408	13998	Indian	OW	P	
UTE TRIBAL 3-32-54	32	050S	040W	4301332410	13949	Indian	OW	P	
UTE TRIBAL 7-32-54	32	050S	040W	4301332411	13936	Indian	OW	P	
UTE TRIBAL 7-33-54	33	050S	040W	4301332413	13945	Indian	OW	P	
UTE TRIBAL 11-20-55	20	050S	050W	4301332415	14269	Indian	OW	P	
UTE TRIBAL 1-27-55	27	050S	050W	4301332416	13947	Indian	OW	P	
UTE TRIBAL 3-27-55	27	050S	050W	4301332417	14022	Indian	OW	P	
UTE TRIBAL 7-27-55	27	050S	050W	4301332418	13948	Indian	OW	P	
UTE TRIBAL 10-28-55	28	050S	050W	4301332419	14580	Indian	OW	P	
UTE TRIBAL 6-32-55	32	050S	050W	4301332420	14895	Indian	OW	P	
UTE TRIBAL 8-32-55	32	050S	050W	4301332421	14896	Indian	OW	P	
UTE TRIBAL 2-36-55	36	050S	050W	4301332422	13937	Indian	OW	P	
UTE TRIBAL 8-36-55	36	050S	050W	4301332423	14021	Indian	OW	P	
UTE TRIBAL 13-16-54	16	050S	040W	4301332511	13981	Indian	OW	P	
UTE TRIBAL 13-23-55	23	050S	050W	4301332513	13975	Indian	OW	P	
UTE TRIBAL 7-23-55	23	050S	050W	4301332514	13976	Indian	OW	P	
UTE TRIBAL 5-33-54	33	050S	040W	4301332521	14060	Indian	OW	P	
UTE TRIBAL 11-33-54	33	050S	040W	4301332522	14061	Indian	OW	P	
UTE TRIBAL 14-32-54	32	050S	040W	4301332523	14062	Indian	OW	P	
UTE TRIBAL 1-23-55	23	050S	050W	4301332524	14044	Indian	OW	P	
UTE TRIBAL 5-29-54	29	050S	040W	4301332525	14045	Indian	OW	P	
UTE TRIBAL 1-31-54	31	050S	040W	4301332526	14116	Indian	OW	P	
UTE TRIBAL 3-31-54	31	050S	040W	4301332527	14109	Indian	OW	P	
UTE TRIBAL 7-31-54	31	050S	040W	4301332528	14160	Indian	OW	P	
UTE TRIBAL 9-31-54	31	050S	040W	4301332529	14177	Indian	OW	P	
UTE TRIBAL 11-31-54	31	050S	040W	4301332530	14163	Indian	OW	P	
UTE TRIBAL 3-23-55	23	050S	050W	4301332536	14077	Indian	OW	P	
UTE TRIBAL 5-23-55	23	050S	050W	4301332537	14108	Indian	OW	P	
UTE TRIBAL 9-32-54	32	050S	040W	4301332538	14199	Indian	OW	P	

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

UTE TRIBAL 5-32-54	32	050S	040W	4301332539	14112	Indian	OW	P	
MOON TRIBAL 10-27-54	27	050S	040W	4301332540	14195	Indian	OW	P	
MOON TRIBAL 12-27-54	27	050S	040W	4301332541	14161	Indian	OW	P	
MOON TRIBAL 8-27-54	27	050S	040W	4301332543	14139	Indian	OW	P	
UTE TRIBAL 9-33-54	33	050S	040W	4301332549	14162	Indian	OW	P	
WILLIAMSON TRIBAL 3-34-54	34	050S	040W	4301332550	14222	Indian	OW	P	
WILLIAMSON TRIBAL 5-34-54	34	050S	040W	4301332551	14235	Indian	OW	P	
FEDERAL 6-2-65	2	060S	050W	4301332557	14655	Federal	OW	P	
UTE TRIBAL 15-29-54	29	050S	040W	4301332561	14316	Indian	OW	P	
UTE TRIBAL 7-29-54	29	050S	040W	4301332562	14354	Indian	OW	P	
UTE TRIBAL 11-29-54	29	050S	040W	4301332563	14337	Indian	OW	P	
UTE TRIBAL 13-29-54	29	050S	040W	4301332564	14315	Indian	OW	P	
UTE TRIBAL 4-29-54	29	050S	040W	4301332565	14367	Indian	OW	P	
UTE TRIBAL 9-29-54	29	050S	040W	4301332566	14369	Indian	OW	P	
UTE TRIBAL 1-35-54	35	050S	040W	4301332567	14266	Indian	OW	P	
UTE TRIBAL 11-13-54	13	050S	040W	4301332568	14281	Indian	OW	P	
UTE TRIBAL 6-24-54	24	050S	040W	4301332570	14299	Indian	OW	P	
UTE TRIBAL 13-18-54	18	050S	040W	4301332571	14388	Indian	OW	P	
UTE TRIBAL 12-29-54	29	050S	040W	4301332572	14336	Indian	OW	P	
UTE TRIBAL 4-24-54	24	050S	040W	4301332573	14247	Indian	OW	P	
UTE TRIBAL 6-14-54	14	050S	040W	4301332586	15270	Indian	OW	P	
UTE TRIBAL 10-15-54	15	050S	040W	4301332587	14194	Indian	OW	P	
UTE TRIBAL 16-15-54	15	050S	040W	4301332588	14311	Indian	OW	P	
UTE TRIBAL 11-16-54	16	050S	040W	4301332589	14178	Indian	OW	P	
UTE TRIBAL 8-22-54	22	050S	040W	4301332590	14219	Indian	OW	P	
UTE TRIBAL 2-22-54	22	050S	040W	4301332591	14328	Indian	OW	P	
UTE TRIBAL 10-22-54	22	050S	040W	4301332592	14218	Indian	OW	P	
UTE TRIBAL 14-22-54	22	050S	040W	4301332593	14220	Indian	OW	P	
UTE TRIBAL 13-13-55	13	050S	050W	4301332599	15134	Indian	OW	P	
UTE TRIBAL 13-14-55	14	050S	050W	4301332600	14236	Indian	OW	P	
UTE TRIBAL 13-15-55	15	050S	050W	4301332602	14263	Indian	OW	P	
UTE TRIBAL 10-21-55	21	050S	050W	4301332603	14385	Indian	OW	P	
UTE TRIBAL 2-22-55	22	050S	050W	4301332604	14268	Indian	OW	P	
UTE TRIBAL 3-22-55	22	050S	050W	4301332605	14298	Indian	OW	P	
UTE TRIBAL 9-22-55	22	050S	050W	4301332606	14330	Indian	OW	P	
UTE TRIBAL 11-22-55	22	050S	050W	4301332607	14329	Indian	OW	P	
UTE TRIBAL 5-27-55	27	050S	050W	4301332614	14881	Indian	OW	P	
UTE TRIBAL 11-27-55	27	050S	050W	4301332615	14882	Indian	OW	P	
UTE TRIBAL 12-22-55	22	050S	050W	4301332616	14370	Indian	OW	P	
UTE TRIBAL 15-22-55	22	050S	050W	4301332617	14921	Indian	OW	P	
UTE TRIBAL 8-25-55	25	050S	050W	4301332620	14365	Indian	OW	P	
UTE TRIBAL 4-20-54	20	050S	040W	4301332621	14518	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 6-20-54	20	050S	040W	4301332622	14382	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 5-22-54	22	050S	040W	4301332624	14547	Indian	OW	P	
UTE TRIBAL 3-30-54	30	050S	040W	4301332625	14364	Indian	OW	P	
UTE TRIBAL 3-10-54	10	050S	040W	4301332663	14414	Indian	OW	P	
UTE TRIBAL 11-5-54	5	050S	040W	4301332664	14415	Indian	OW	P	
UTE TRIBAL 15-32-54	32	050S	040W	4301332666	14460	Indian	OW	P	
UTE TRIBAL 8-31-55	31	050S	050W	4301332673	14407	Indian	OW	P	
UTE TRIBAL 3-35-54	35	050S	040W	4301332675	14656	Indian	OW	P	
UTE TRIBAL 2-30-55	30	050S	050W	4301332680	14427	Indian	OW	P	
UTE TRIBAL 9-17-54	17	050S	040W	4301332687	15309	Indian	OW	P	
UTE TRIBAL 13-31-54	31	050S	040W	4301332688	14517	Indian	OW	P	
UTE TRIBAL 14-19-54	19	050S	040W	4301332690	14546	Indian	OW	P	
UTE TRIBAL 16-19-54	19	050S	040W	4301332691	14491	Indian	OW	P	
UTE TRIBAL 13-32-54	32	050S	040W	4301332692	14490	Indian	OW	P	
UTE TRIBAL 11-14-55	14	050S	050W	4301332693	15136	Indian	OW	P	
UTE TRIBAL 8-28-55	28	050S	050W	4301332694	14574	Indian	OW	P	
FEDERAL 6-1-65	1	060S	050W	4301332699	15776	Federal	OW	P	
UTE TRIBAL 9-15-55	15	050S	050W	4301332701	14573	Indian	OW	P	
UTE TRIBAL 14-20-54	20	050S	040W	4301332702	14459	Indian	OW	P	
#1 DLB 12-15-56	15	050S	060W	4301332710	14943	Fee	GW	P	
UTE TRIBAL 12-19-54	19	050S	040W	4301332716	14627	Indian	OW	P	
UTE TRIBAL 10-19-54	19	050S	040W	4301332717	14628	Indian	OW	P	
UTE TRIBAL 16-30-54	30	050S	040W	4301332718	14604	Indian	OW	P	
UTE TRIBAL 11-12-55	12	050S	050W	4301332721	14605	Indian	OW	P	

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

NIelsen MARSING 13-14-56	14	050S	060W	4301332737	15060	Fee	OW	P	
TAYLOR HERRICK 10-22-56	22	050S	060W	4301332738	15058	Fee	OW	P	
UTE TRIBAL 16-20-54	20	050S	040W	4301332739	14671	Indian	OW	P	
UTE TRIBAL 10-20-54	20	050S	040W	4301332740	14691	Indian	OW	P	
UTE TRIBAL 4-28-54	28	050S	040W	4301332741	14672	Indian	OW	P	
UTE TRIBAL 13-33-54	33	050S	040W	4301332742	14736	Indian	OW	P	
UTE TRIBAL 15-31-54	31	050S	040W	4301332743	14690	Indian	OW	P	
UTE TRIBAL 8-30-54	30	050S	040W	4301332746	15583	Indian	OW	P	
UTE TRIBAL 10-25-55	25	050S	050W	4301332749	14758	Indian	OW	P	
UTE TRIBAL 14-25-55	25	050S	050W	4301332750	14798	Indian	OW	P	
UTE TRIBAL 3-36-55	36	050S	050W	4301332751	14842	Indian	OW	P	
UTE TRIBAL 16-16-55	16	050S	050W	4301332757	14865	Indian	OW	P	
UTE TRIBAL 3-21-55	21	050S	050W	4301332758	15112	Indian	OW	P	
UTE TRIBAL 16-25-55	25	050S	050W	4301332759	14821	Indian	OW	P	
UTE TRIBAL 1-36-55	36	050S	050W	4301332760	14822	Indian	OW	P	
UTE TRIBAL 7-22-54	22	050S	040W	4301332761	15661	Indian	OW	P	
UTE TRIBAL 2-31-54	31	050S	040W	4301332762	14845	Indian	OW	P	
UTE TRIBAL 2-28-54	28	050S	040W	4301332763	14723	Indian	OW	P	
UTE TRIBAL 10-28-54	28	050S	040W	4301332764	14722	Indian	OW	P	
UTE TRIBAL 12-28-54	28	050S	040W	4301332765	14701	Indian	OW	P	
UTE TRIBAL 8-28-54	28	050S	040W	4301332766	14777	Indian	OW	P	
UTE TRIBAL 4-31-54	31	050S	040W	4301332767	14494	Indian	OW	P	
UTE TRIBAL 15-33-54	33	050S	040W	4301332768	15210	Indian	OW	P	
UTE TRIBAL 12-25-55	25	050S	050W	4301332769	14799	Indian	OW	P	
UTE TRIBAL 16-24-54	24	050S	040W	4301332775	14762	Indian	OW	P	
UTE TRIBAL 14-25-54	25	050S	040W	4301332776	14753	Indian	OW	P	
UTE TRIBAL 8-25-54	25	050S	040W	4301332780	15280	Indian	OW	P	
UTE TRIBAL 9-35-54	35	050S	040W	4301332781	15535	Indian	OW	P	
MYRIN TRIBAL 14-19-55	19	050S	050W	4301332782	15184	Indian	OW	P	
UTE TRIBAL 6-30-55	30	050S	050W	4301332783	15163	Indian	OW	P	
MOON TRIBAL 4-23-54	23	050S	040W	4301332800	14985	Indian	OW	P	
MOON TRIBAL 5-27-54	27	050S	040W	4301332802	14984	Indian	OW	P	
UTE TRIBAL 2-32-54	32	050S	040W	4301332803	15151	Indian	OW	P	
UTE TRIBAL 15-35-54	35	050S	040W	4301332804	15185	Indian	OW	P	
UTE TRIBAL 5-35-54	35	050S	040W	4301332805	15485	Indian	OW	P	
UTE TRIBAL 13-35-54	35	050S	040W	4301332806	15292	Indian	OW	P	
UTE TRIBAL 11-35-54	35	050S	040W	4301332807	15317	Indian	OW	P	
UTE TRIBAL 8-19-54	19	050S	040W	4301332840	14946	Indian	OW	P	BRUNDAGE CANYON
UTE TRIBAL 13-20-55	20	050S	050W	4301332841	15097	Indian	OW	P	
UTE TRIBAL 16-22-54	22	050S	040W	4301332842	15015	Indian	OW	P	
MOON TRIBAL 6-23-54	23	050S	040W	4301332843	15113	Indian	OW	P	
UTE TRIBAL 11-26-54	26	050S	040W	4301332844	15233	Indian	OW	P	
MOON TRIBAL 11-27-54	27	050S	040W	4301332845	15135	Indian	OW	P	
MOON TRIBAL 15-27-54	27	050S	040W	4301332846	15115	Indian	OW	P	
UTE TRIBAL 10-31-54	31	050S	040W	4301332847	14956	Indian	OW	P	
ST TRIBAL 6-15-54	15	050S	040W	4301332848	16656	Indian	OW	P	
ST TRIBAL 2-15-54	15	050S	040W	4301332849	16959	Indian	OW	P	
ST TRIBAL 4-15-54	15	050S	040W	4301332850	17478	Indian	OW	P	
ST TRIBAL 8-15-54	15	050S	040W	4301332851	16279	Indian	OW	P	
UTE TRIBAL 11-25-54	25	050S	040W	4301332856	15430	Indian	OW	P	
UTE TRIBAL 3-30-55	30	050S	050W	4301332862	15340	Indian	OW	P	
UTE TRIBAL 7-19-55	19	050S	050W	4301332863	15279	Indian	OW	P	
UTE TRIBAL 8-19-55	19	050S	050W	4301332864	15241	Indian	OW	P	
UTE TRIBAL 6-19-54	19	050S	040W	4301332865	14947	Indian	OW	P	
UTE TRIBAL 12-20-54	20	050S	040W	4301332866	14924	Indian	OW	P	
UTE TRIBAL 3-21-54	21	050S	040W	4301332867	15554	Indian	OW	P	
UTE TRIBAL 2-26-54	26	050S	040W	4301332868	15231	Indian	OW	P	
UTE TRIBAL 8-31-54	31	050S	040W	4301332869	14970	Indian	OW	P	
UTE TRIBAL 8-32-54	32	050S	040W	4301332870	15152	Indian	OW	P	
UTE TRIBAL 4-33-54	33	050S	040W	4301332871	15040	Indian	OW	P	
UTE TRIBAL 6-33-54	33	050S	040W	4301332872	15059	Indian	OW	P	
UTE TRIBAL 9-22-54	22	050S	040W	4301332889	15607	Indian	OW	P	
UTE TRIBAL 5-26-54	26	050S	040W	4301332890	15268	Indian	OW	P	
UTE TRIBAL 13-26-54	26	050S	040W	4301332891	15287	Indian	OW	P	
UTE TRIBAL 6-28D-54	28	050S	040W	4301332892	15232	Indian	OW	P	
UTE TRIBAL 2-30D-54	30	050S	040W	4301332894	15298	Indian	OW	P	

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

UTE TRIBAL 4-32-54	32	050S	040W	4301332896	15555	Indian	OW	P	
UTE TRIBAL 6-32D-54	32	050S	040W	4301332897	15312	Indian	OW	P	
UTE TRIBAL 2-33D-54	33	050S	040W	4301332898	15271	Indian	OW	P	
UTE TRIBAL 12-32-54	32	050S	040W	4301332925	15503	Indian	OW	P	
UTE TRIBAL 16-32D-54	32	050S	040W	4301332926	16971	Indian	OW	P	
MOON TRIBAL 16-23-54	23	050S	040W	4301332927	15219	Indian	OW	P	
UTE TRIBAL 4-25-55	25	050S	050W	4301332928	15421	Indian	OW	P	
UTE TRIBAL 7-36-55	36	050S	050W	4301332929	15341	Indian	OW	P	
MOON TRIBAL 10-2-54	2	050S	040W	4301332931	15429	Indian	OW	P	
UTE TRIBAL 10-24-54	24	050S	040W	4301332932	15364	Indian	OW	P	
MYRIN TRIBAL 16-19-55	19	050S	050W	4301332934	15339	Indian	OW	P	
UTE TRIBAL 2-31-55	31	050S	050W	4301332935	15428	Indian	OW	P	
UTE TRIBAL 10-31-55	31	050S	050W	4301332936	15354	Indian	OW	P	
MOON TRIBAL 1-27-54	27	050S	040W	4301332937	15308	Indian	OW	P	
MOON TRIBAL 5-23-54	23	050S	040W	4301332938	15584	Indian	OW	P	
ST TRIBAL 7-18-54	18	050S	040W	4301332952	15724	Indian	OW	P	
ST TRIBAL 5-18-54	18	050S	040W	4301332953	15781	Indian	OW	P	
UTE TRIBAL 15-15-54	15	050S	040W	4301332971	15310	Indian	OW	P	
UTE TRIBAL 4-19-54	19	050S	040W	4301332972	15382	Indian	OW	P	
UTE TRIBAL 8-20-54	20	050S	040W	4301332973	15245	Indian	OW	P	
UTE TRIBAL 2-20-54	20	050S	040W	4301332974	15269	Indian	OW	P	
UTE TRIBAL 7-15-55	15	050S	050W	4301332976	15311	Indian	OW	P	
UTE TRIBAL 10-15-55	15	050S	050W	4301332977	15380	Indian	OW	P	
UTE TRIBAL 1-15-55	15	050S	050W	4301332978	15299	Indian	OW	P	
UTE TRIBAL 14-15-55	15	050S	050W	4301332979	15369	Indian	OW	P	
UTE TRIBAL 11-15-55	15	050S	050W	4301332980	15342	Indian	OW	P	
UTE TRIBAL 14-18-55	18	050S	050W	4301332984	15671	Indian	OW	P	
UTE TRIBAL 14-24-56	24	050S	060W	4301332988	15740	Indian	OW	P	
UTE TRIBAL 7-24-56	24	050S	060W	4301332989	15782	Indian	OW	P	
UTE TRIBAL 11-25-56	25	050S	060W	4301332990	15627	Indian	OW	P	
UTE TRIBAL 7-25-56	25	050S	060W	4301332991	15617	Indian	OW	P	
UTE TRIBAL 5-25-56	25	050S	060W	4301332992	15648	Indian	OW	P	
UTE TRIBAL 3-25-56	25	050S	060W	4301332993	15561	Indian	OW	P	
UTE TRIBAL 13-15D-54	15	050S	040W	4301333039	15368	Indian	OW	P	
UTE TRIBAL 16-28D-54	28	050S	040W	4301333041	15377	Indian	OW	P	
UTE TRIBAL 14-31D-54	31	050S	040W	4301333042	15419	Indian	OW	P	
UTE TRIBAL 4-22-55	22	050S	050W	4301333044	15381	Indian	OW	P	
UTE TRIBAL 2-23-55	23	050S	050W	4301333045	15416	Indian	OW	P	
UTE TRIBAL 16-23-55	23	050S	050W	4301333046	15211	Indian	OW	P	
UTE TRIBAL 9-35-55	35	050S	050W	4301333047	15378	Indian	OW	P	
UTE TRIBAL 7-35-55	35	050S	050W	4301333048	15367	Indian	OW	P	
UTE TRIBAL 15-36-55	36	050S	050W	4301333049	15379	Indian	OW	P	
UTE TRIBAL 10-12-55	12	050S	050W	4301333055	15618	Indian	OW	P	
UTE TRIBAL 5-13-54	13	050S	040W	4301333075	15873	Indian	OW	P	
UTE TRIBAL 16-29-54	29	050S	040W	4301333076	17074	Indian	OW	P	
UTE TRIBAL 12-18-54	18	050S	040W	4301333077	15575	Indian	OW	P	
UTE TRIBAL 8-33-54	33	050S	040W	4301333089	15398	Indian	OW	P	
UTE TRIBAL 12-33-54	33	050S	040W	4301333090	15417	Indian	OW	P	
UTE TRIBAL 16-33-54	33	050S	040W	4301333091	15397	Indian	OW	P	
UTE TRIBAL 10-33-54	33	050S	040W	4301333092	15418	Indian	OW	P	
UTE TRIBAL 14-33-54	33	050S	040W	4301333093	15399	Indian	OW	P	
UTE TRIBAL 2-14-54	14	050S	040W	4301333111	16832	Indian	OW	P	
UTE TRIBAL 14-14-54	14	050S	040W	4301333112	15440	Indian	OW	P	
UTE TRIBAL 13-21-54	21	050S	040W	4301333113	15471	Indian	OW	P	
UTE TRIBAL 11-21-54	21	050S	040W	4301333115	15470	Indian	OW	P	
UTE TRIBAL 11-22-54	22	050S	040W	4301333116	15662	Indian	OW	P	
UTE TRIBAL 2-21-55	21	050S	050W	4301333117	15582	Indian	OW	P	
UTE TRIBAL 4-28-55	28	050S	050W	4301333118	15506	Indian	OW	P	
UTE TRIBAL 8-29-55	29	050S	050W	4301333119	15507	Indian	OW	P	
UTE TRIBAL 6-29-55	29	050S	050W	4301333120	15504	Indian	OW	P	
TAYLOR FEE 13-22-56	22	050S	060W	4301333121	15525	Fee	OW	P	
WILCOX ELIASON 7-15-56	15	050S	060W	4301333122	15526	Fee	OW	P	
UTE TRIBAL 14-16-54	16	050S	040W	4301333123	15639	Indian	OW	P	
UTE TRIBAL 1-16-54	16	050S	040W	4301333128	15420	Indian	OW	P	
UTE TRIBAL 7-16-54	16	050S	040W	4301333130	15455	Indian	OW	P	
UTE TRIBAL 12-16-54	16	050S	040W	4301333131	15456	Indian	OW	P	

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

UTE TRIBAL 16-17-54	17	050S	040W	4301333132	15524	Indian	OW	P	
UTE TRIBAL 10-17-54	17	050S	040W	4301333133	15581	Indian	OW	P	
UTE TRIBAL 12-24D-55	24	050S	050W	4301333134	15567	Indian	OW	P	
WILCOX FEE 1-20-56	20	050S	060W	4301333150	15745	Fee	OW	P	
WILCOX FEE 15-16-56	16	050S	060W	4301333151	15527	Fee	OW	P	
NIELSEN FEE 13-11-56	11	050S	060W	4301333152	15600	Fee	OW	P	
UTE TRIBAL 2-29-54	29	050S	040W	4301333153	15919	Indian	OW	P	
UTE TRIBAL 14-29-54	29	050S	040W	4301333154	15831	Indian	OW	P	
UTE TRIBAL 10-29-54	29	050S	040W	4301333155	15847	Indian	OW	P	
UTE TRIBAL 10-24D-55	24	050S	050W	4301333156	15556	Indian	OW	P	
UTE TRIBAL 10-29D-55	29	050S	050W	4301333157	15505	Indian	OW	P	
UTE TRIBAL 6-29-54	29	050S	040W	4301333172	15846	Indian	OW	P	
UTE TRIBAL 12Q-25-55	25	050S	050W	4301333184	15744	Indian	OW	P	
UTE TRIBAL 3G-31-54	31	050S	040W	4301333185	15746	Indian	OW	P	
UTE TRIBAL 11-36-55	36	050S	050W	4301333186	15865	Indian	OW	P	
UTE TRIBAL 6-23D-55	23	050S	050W	4301333187	15996	Indian	OW	P	
UTE TRIBAL 8-14-54	14	050S	040W	4301333204	15656	Indian	OW	P	
UTE TRIBAL 10-14-54	14	050S	040W	4301333205	15680	Indian	OW	P	
UTE TRIBAL 11-15-54	15	050S	040W	4301333206	15643	Indian	OW	P	
UTE TRIBAL 9-16-54	16	050S	040W	4301333207	15660	Indian	OW	P	
UTE TRIBAL 3-22-54	22	050S	040W	4301333208	15640	Indian	OW	P	
UTE TRIBAL 15-13D-55	13	050S	050W	4301333212	15642	Indian	OW	P	
UTE TRIBAL 6-22D-55	22	050S	050W	4301333213	16831	Indian	OW	P	
UTE TRIBAL 11-36D-55	36	050S	050W	4301333214	15702	Indian	OW	P	
UTE TRIBAL 1-22D-54	22	050S	040W	4301333215	15641	Indian	OW	P	
BERRY TRIBAL 1-23-54	23	050S	040W	4301333216	15931	Indian	OW	P	
BERRY TRIBAL 15-23-54	23	050S	040W	4301333217	15932	Indian	OW	P	
UTE TRIBAL 9-36D-55	36	050S	050W	4301333239	15933	Indian	OW	P	
UTE TRIBAL 12-32-55	32	050S	050W	4301333266	15681	Indian	OW	P	
UTE TRIBAL 16-22D-55	22	050S	050W	4301333267	15703	Indian	OW	P	
UTE TRIBAL 11-13-55	13	050S	050W	4301333268	15692	Indian	OW	P	
UTE TRIBAL 7-14-55	14	050S	050W	4301333269	15693	Indian	OW	P	
UTE TRIBAL 4-14D-54	14	050S	040W	4301333270	15679	Indian	OW	P	
UTE TRIBAL 9S-19-54	19	050S	040W	4301333276	16153	Indian	OW	P	
UTE TRIBAL 14Q-28-54	28	050S	040W	4301333277	15818	Indian	OW	P	
UTE TRIBAL 14-28D-54	28	050S	040W	4301333278	15817	Indian	OW	P	
UTE TRIBAL 1-14D-55	14	050S	050W	4301333279	18408	Indian	OW	P	
UTE TRIBAL 10-18-54	18	050S	040W	4301333300	15747	Indian	OW	P	
UTE TRIBAL 5-21-54	21	050S	040W	4301333324	15748	Indian	OW	P	
UTE TRIBAL 6-31D-54	31	050S	040W	4301333325	16185	Indian	OW	P	
UTE TRIBAL 16-31D-54	31	050S	040W	4301333326	15800	Indian	OW	P	
UTE TRIBAL 16-13D-55	13	050S	050W	4301333327	15891	Indian	OW	P	
UTE TRIBAL 9-13D-55	13	050S	050W	4301333328	15892	Indian	OW	P	
UTE TRIBAL 15-21-55	21	050S	050W	4301333357	15791	Indian	OW	P	
UTE TRIBAL 10-23D-55	23	050S	050W	4301333358	15799	Indian	OW	P	
UTE TRIBAL 9-26D-55	26	050S	050W	4301333359	15853	Indian	OW	P	
UTE TRIBAL 10-26D-55	26	050S	050W	4301333360	15852	Indian	OW	P	
UTE TRIBAL 14-26D-55	26	050S	050W	4301333361	15938	Indian	OW	P	
UTE TRIBAL 15-26D-55	26	050S	050W	4301333362	15869	Indian	OW	P	
UTE TRIBAL 3-32D-55	32	050S	050W	4301333363	15936	Indian	OW	P	
UTE TRIBAL 13-14-54	14	050S	040W	4301333364	15790	Indian	OW	P	
MOON TRIBAL 7-27D-54	27	050S	040W	4301333365	15935	Indian	OW	P	
14-11-56 DLB	11	050S	060W	4301333378	15801	Fee	OW	P	
UTE TRIBAL 4-32-55	32	050S	050W	4301333379	15819	Indian	OW	P	
UTE TRIBAL 13H-16-55	16	050S	050W	4301333380	18357	Indian	OW	P	
BERRY TRIBAL 7-23-54	23	050S	040W	4301333381	15934	Indian	OW	P	
BERRY TRIBAL 9-34-54	34	050S	040W	4301333382	16024	Indian	OW	P	
BERRY TRIBAL 7-34-54	34	050S	040W	4301333383	16102	Indian	OW	P	
BERRY TRIBAL 4-34-54	34	050S	040W	4301333384	16588	Indian	OW	P	
FEDERAL 2-2-65	2	060S	050W	4301333385	16150	Federal	OW	P	
FEDERAL 10-3-65	3	060S	050W	4301333386	16297	Federal	OW	P	
FEDERAL 5-4-65	4	060S	050W	4301333387	17599	Federal	OW	P	
UTE TRIBAL 1A-29-54	29	050S	040W	4301333393	17075	Indian	OW	P	
BERRY TRIBAL 15-34-54	34	050S	040W	4301333411	16037	Indian	OW	P	
BERRY TRIBAL 8-23D-54	23	050S	040W	4301333417	16101	Indian	OW	P	
UTE TRIBAL 12-29D-55	29	050S	050W	4301333418	17307	Indian	OW	P	

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

UTE TRIBAL 8-24-55	24	050S	050W	4301333420	15997	Indian	OW	P
UTE TRIBAL 5-25D-55	25	050S	050W	4301333421	16589	Indian	OW	P
BERRY TRIBAL 10-34D-54	34	050S	040W	4301333422	16038	Indian	OW	P
1-15-56 DLB	15	050S	060W	4301333447	15854	Fee	OW	P
FEDERAL 5-3-64	3	060S	040W	4301333448	16098	Federal	OW	P
FEDERAL 8-1-64	1	060S	040W	4301333449	16152	Federal	OW	P
FEDERAL 5-4-64	4	060S	040W	4301333450	17851	Federal	OW	P
FEDERAL 11-10-65	10	060S	050W	4301333451	16281	Federal	OW	P
BERRY TRIBAL 16-34D-54	34	050S	040W	4301333464	16280	Indian	OW	P
BERRY TRIBAL 9-23-54	23	050S	040W	4301333465	16590	Indian	OW	P
UTE TRIBAL 6-26D-55	26	050S	050W	4301333476	16657	Indian	OW	P
UTE TRIBAL 7-26D-55	26	050S	050W	4301333477	16658	Indian	OW	P
UTE TRIBAL 11-26D-55	26	050S	050W	4301333478	16659	Indian	OW	P
UTE TRIBAL 14Q-30-54	30	050S	040W	4301333479	16151	Indian	OW	P
FEDERAL 5-6-65	6	060S	050W	4301333489	17852	Federal	OW	P
FEDERAL 16-5-65	5	060S	050W	4301333490	16833	Federal	OW	P
FEDERAL 6-11-65	11	060S	050W	4301333491	16335	Federal	OW	P
LC TRIBAL 14-2-56	2	050S	060W	4301333492	18358	Indian	OW	P
UTE TRIBAL 1-31-55	31	050S	050W	4301333501	17104	Indian	OW	P
UTE TRIBAL 9-31-55	31	050S	050W	4301333508	17103	Indian	OW	P
BERRY TRIBAL 11-34D-54	34	050S	040W	4301333529	16099	Indian	OW	P
LC TRIBAL 2-16D-56	16	050S	060W	4301333538	17305	Indian	OW	P
LC TRIBAL 4-16-56	16	050S	060W	4301333539	16272	Indian	OW	P
LC TRIBAL 3-17-56	17	050S	060W	4301333541	16459	Indian	OW	P
FEDERAL 10-2-65	2	060S	050W	4301333542	16181	Federal	OW	P
UTE TRIBAL 4-20D-55	20	050S	050W	4301333549	18075	Indian	OW	P
UTE TRIBAL 8-23D-55	23	050S	050W	4301333552	16662	Indian	OW	P
LC TRIBAL 8-28-46	28	040S	060W	4301333576	16155	Indian	OW	P
LC TRIBAL 7-3-56	3	050S	060W	4301333577	16379	Indian	OW	P
LC TRIBAL 3-5-56	5	050S	060W	4301333580	17082	Indian	OW	P
FEDERAL 8-2D-64	2	060S	040W	4301333581	16100	Federal	OW	P
LC TRIBAL 13H-3-56	3	050S	060W	4301333591	18129	Indian	OW	P
LC FEE 6-12-57	12	050S	070W	4301333593	17083	Fee	OW	P
UTE TRIBAL 4-26D-54	26	050S	040W	4301333595	16591	Indian	OW	P
LC TRIBAL 8-4-56	4	050S	060W	4301333605	17046	Indian	OW	P
LC TRIBAL 12H-6-56	6	050S	060W	4301333606	18037	Indian	OW	P
LC TRIBAL 7-7D-56	7	050S	060W	4301333607	18038	Indian	OW	P
LC TRIBAL 1-9-56	9	050S	060W	4301333608	16380	Indian	OW	P
UTE TRIBAL 5-14-54	14	050S	040W	4301333619	16945	Indian	OW	P
UTE TRIBAL 10-26D-54	26	050S	040W	4301333620	16663	Indian	OW	P
UTE TRIBAL 7-26D-54	26	050S	040W	4301333621	16664	Indian	OW	P
UTE TRIBAL 13-36D-55	36	050S	050W	4301333624	17744	Indian	OW	P
UTE TRIBAL 6-26D-54	26	050S	040W	4301333625	16619	Indian	OW	P
UTE TRIBAL 1-22D-55	22	050S	050W	4301333626	16777	Indian	OW	P
UTE TRIBAL 4-23D-55	23	050S	050W	4301333627	16818	Indian	OW	P
UTE TRIBAL 2-27D-55	27	050S	050W	4301333628	16746	Indian	OW	P
UTE TRIBAL 12-28D-55	28	050S	050W	4301333645	17999	Indian	OW	P
UTE TRIBAL 13-28D-55	28	050S	050W	4301333646	18000	Indian	OW	P
UTE TRIBAL 14-26D-54	26	050S	040W	4301333673	16299	Indian	OW	P
UTE FEE 7-13D-55	13	050S	050W	4301333674	18089	Fee	OW	P
UTE TRIBAL 9-20D-55	20	050S	050W	4301333675	17309	Indian	OW	P
LC TRIBAL 11-17-56	17	050S	060W	4301333677	17600	Indian	OW	P
UTE TRIBAL 1-26D-54	26	050S	040W	4301333680	16638	Indian	OW	P
UTE TRIBAL 3-26D-54	26	050S	040W	4301333681	16665	Indian	OW	P
UTE TRIBAL 8-26D-54	26	050S	040W	4301333682	17031	Indian	OW	P
UTE TRIBAL 10-27D-55	27	050S	050W	4301333683	16666	Indian	OW	P
UTE TRIBAL 14-27D-55	27	050S	050W	4301333684	16667	Indian	OW	P
UTE TRIBAL 12-21D-55	21	050S	050W	4301333694	16296	Indian	OW	P
UTE TRIBAL 5-21D-55	21	050S	050W	4301333706	16298	Indian	OW	P
UTE TRIBAL 2-29D-55	29	050S	050W	4301333714	16854	Indian	OW	P
UTE TRIBAL 7-29D-55	29	050S	050W	4301333715	16853	Indian	OW	P
UTE TRIBAL 13-22D-55	22	050S	050W	4301333716	16668	Indian	OW	P
UTE TRIBAL 14-22D-55	22	050S	050W	4301333717	16669	Indian	OW	P
UTE FEE 2-13-55	13	050S	050W	4301333720	18659	Indian	OW	P
UTE TRIBAL 7-22D-55	22	050S	050W	4301333721	16670	Indian	OW	P
UTE TRIBAL 10-22D-55	22	050S	050W	4301333722	16671	Indian	OW	P

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

UTE TRIBAL 3-29-55	29	050S	050W	4301333723	16857	Indian	OW	P	
BERRY TRIBAL 10-23D-54	23	050S	040W	4301333724	16592	Indian	OW	P	
BERRY TRIBAL 11-23D-54	23	050S	040W	4301333725	16672	Indian	OW	P	
UTE TRIBAL 4-24D-55	24	050S	050W	4301333726	16673	Indian	OW	P	
FEDERAL 6-6D-64	6	060S	040W	4301333745	17084	Federal	OW	P	
UTE TRIBAL 15-26D-54	26	050S	040W	4301333768	17450	Indian	OW	P	
UTE TRIBAL 1-14D-54	14	050S	040W	4301333769	17483	Indian	OW	P	
UTE TRIBAL 12-35D-55	35	050S	050W	4301333782	16856	Indian	OW	P	
UTE TRIBAL 11-35-55	35	050S	050W	4301333783	16855	Indian	OW	P	
UTE TRIBAL 1-28D-55	28	050S	050W	4301333784	16852	Indian	OW	P	
UTE TRIBAL 16-27D-55	27	050S	050W	4301333786	17800	Indian	OW	P	
UTE TRIBAL 9-28D-55	28	050S	050W	4301333787	16887	Indian	OW	P	
UTE TRIBAL 7-28D-55	28	050S	050W	4301333788	16886	Indian	OW	P	
UTE TRIBAL 11-32D-54	32	050S	040W	4301333793	17003	Indian	OW	P	
UTE TRIBAL 9-14D-54	14	050S	040W	4301333796	17482	Indian	OW	P	
UTE TRIBAL 4-27D-55	27	050S	050W	4301333797	16700	Indian	OW	P	
FOY TRIBAL 12H-33-55	33	050S	050W	4301333799	18232	Indian	OW	P	
UTE TRIBAL 9-32D-55	32	050S	050W	4301333800	18361	Indian	OW	P	
UTE TRIBAL 12-26D-54	26	050S	040W	4301333801	16639	Indian	OW	P	
UTE TRIBAL 8-26D-55	26	050S	050W	4301333859	17859	Indian	OW	P	
BERRY TRIBAL 2-34D-54	34	050S	040W	4301333867	17889	Indian	OW	P	
UTE TRIBAL 3-35D-55	35	050S	050W	4301333888	17421	Indian	OW	P	
UTE TRIBAL 10-32-54	32	050S	040W	4301333902	16819	Indian	OW	P	
UTE TRIBAL 12-31D-54	31	050S	040W	4301333907	17480	Indian	OW	P	
UTE TRIBAL 12-23D-55	23	050S	050W	4301333908	17814	Indian	OW	P	
UTE TRIBAL 14-20D-55	20	050S	050W	4301333909	18559	Indian	OW	P	
UTE TRIBAL 6-20D-55	20	050S	050W	4301333910	18481	Indian	OW	P	
UTE TRIBAL 12-20-55	20	050S	050W	4301333911	18520	Indian	OW	P	
UTE TRIBAL 14-24D-55	24	050S	050W	4301333912	16943	Indian	OW	P	
UTE TRIBAL 14-23D-55	23	050S	050W	4301333915	17457	Indian	OW	P	
ST TRIBAL 1-15D-54	15	050S	040W	4301333916	16889	Indian	OW	P	
ST TRIBAL 7-15D-54	15	050S	040W	4301333950	16972	Indian	OW	P	
ST TRIBAL 9-15D-54	15	050S	040W	4301333951	16973	Indian	OW	P	
UTE TRIBAL 15-35D-55	35	050S	050W	4301333954	17417	Indian	OW	P	
UTE TRIBAL 14-35D-55	35	050S	050W	4301333955	17416	Indian	OW	P	
UTE TRIBAL 16-26D-55	26	050S	050W	4301333965	17418	Indian	OW	P	
FEDERAL 1-2D-65	2	060S	050W	4301333966	16888	Federal	OW	P	
UTE TRIBAL 1-35D-55	35	050S	050W	4301333967	17420	Indian	OW	P	
UTE TRIBAL 10-36D-55	36	050S	050W	4301333968	17743	Indian	OW	P	
UTE TRIBAL 4-26D-55	26	050S	050W	4301333978	17455	Indian	OW	P	
UTE TRIBAL 2-26D-55	26	050S	050W	4301333979	17456	Indian	OW	P	
BERRY TRIBAL 14-23D-54	23	050S	040W	4301333989	17903	Indian	OW	P	
FEDERAL 3-2D-65	2	060S	050W	4301334001	16944	Federal	OW	P	
UTE TRIBAL 13-26D-55	26	050S	050W	4301334002	17481	Indian	OW	P	
FEDERAL 7-1D-65	1	060S	050W	4301334015	17775	Federal	OW	P	
FEDERAL 2-2D-64	2	060S	040W	4301334018	17086	Federal	OW	P	
FEDERAL 7-6D-64	6	060S	040W	4301334020	17085	Federal	OW	P	
UTE TRIBAL 6-35D-55	35	050S	050W	4301334028	17785	Indian	OW	P	
UTE TRIBAL 16-26-54	26	050S	040W	4301334042	17413	Indian	OW	P	
BERRY TRIBAL 13-23-54	23	050S	040W	4301334043	17100	Indian	OW	P	
UTE TRIBAL 11-28-55	28	050S	050W	4301334057	18001	Indian	OW	P	
UTE TRIBAL 8-27D-55	27	050S	050W	4301334058	17842	Indian	OW	P	
ST TRIBAL 3-15D-54	15	050S	040W	4301334059	17477	Indian	OW	P	
ST TRIBAL 5-15D-54	15	050S	040W	4301334060	17479	Indian	OW	P	
FEDERAL 7-11D-65	11	060S	050W	4301334061	17776	Federal	OW	P	
FEDERAL 7-3D-65	3	060S	050W	4301334065	17124	Federal	OW	P	
MOON TRIBAL 16-27D-54	27	050S	040W	4301334109	17414	Indian	OW	P	
UTE TRIBAL 15-22D-54	22	050S	040W	4301334116	17415	Indian	OW	P	
UTE TRIBAL 13-35D-55	35	050S	050W	4301334117	18442	Indian	OW	P	
UTE TRIBAL 12-26D-55	26	050S	050W	4301334118	17786	Indian	OW	P	
LC TRIBAL 13-16D-56	16	050S	060W	4301334282	17601	Indian	OW	P	
FEDERAL 11-6D-64	6	060S	040W	4301334284	17615	Federal	OW	P	
FEDERAL 14-6D-64	6	060S	040W	4301334285	17616	Federal	OW	P	
FEDERAL 2-6D-64	6	060S	040W	4301334286	17663	Federal	OW	P	
FEDERAL 3-5D-64	5	060S	040W	4301334287	17617	Federal	OW	P	
FEDERAL 6-5D-64	5	060S	040W	4301334288	17649	Federal	OW	P	

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

SFW TRIBAL 10-10D-54	10	050S	040W	4301334295	17564	Indian	OW	P	
SFW TRIBAL 9-10D-54	10	050S	040W	4301334296	17565	Indian	OW	P	
STATE TRIBAL 16-10-54	10	050S	040W	4301350245	17553	Indian	OW	P	
UTE TRIBAL 6-14D-55	14	050S	050W	4301350246	17602	Indian	OW	P	
SFW FEE 15-10-54	10	050S	040W	4301350247	17566	Fee	OW	P	
FEDERAL 5-5D-64	5	060S	040W	4301350259	17648	Federal	OW	P	
LC TRIBAL 6-22D-56	22	050S	060W	4301350260	17567	Indian	OW	P	
FEDERAL 12-6D-64	6	060S	040W	4301350261	17618	Federal	OW	P	
LC TRIBAL 4-27D-56	27	050S	060W	4301350262	17568	Indian	OW	P	
FEDERAL 4-5D-64	5	060S	040W	4301350263	17661	Federal	OW	P	
FEDERAL 1-6-64	6	060S	040W	4301350266	17662	Federal	OW	P	
FEDERAL 4-6D-64	6	060S	040W	4301350267	17651	Federal	OW	P	
FEDERAL 3-6D-64	6	060S	040W	4301350268	17650	Federal	OW	P	
FEDERAL 5-6D-64	6	060S	040W	4301350269	17652	Federal	OW	P	
FEDERAL 8-6D-64	6	060S	040W	4301350325	17664	Federal	OW	P	
FEDERAL 10-1D-65	1	060S	050W	4301350326	18027	Federal	OW	P	
FEDERAL 11-1D-65	1	060S	050W	4301350327	18039	Federal	OW	P	
FEDERAL 12-1D-65	1	060S	050W	4301350328	18040	Federal	OW	P	
FEDERAL 13-1D-65	1	060S	050W	4301350329	18042	Federal	OW	P	
FEDERAL 14-1D-65	1	060S	050W	4301350330	18041	Federal	OW	P	
FEDERAL 13-5D-64	5	060S	040W	4301350337	17714	Federal	OW	P	
FEDERAL 14-5D-64	5	060S	040W	4301350338	17715	Federal	OW	P	
FEDERAL 9-1D-65	1	060S	050W	4301350342	18026	Federal	OW	P	
FEDERAL 13-6D-64	6	060S	040W	4301350347	17619	Federal	OW	P	
FEDERAL 11-5D-64	5	060S	040W	4301350348	17690	Federal	OW	P	
FEDERAL 12-5D-64	5	060S	040W	4301350349	17713	Federal	OW	P	
FEDERAL 8-1D-65	1	060S	050W	4301350350	18025	Federal	OW	P	
UTE TRIBAL 3-14D-54	14	050S	040W	4301350389	17904	Indian	OW	P	
UTE TRIBAL 1-34D-55	34	050S	050W	4301350408	17931	Indian	OW	P	
UTE TRIBAL 7-14-54	14	050S	040W	4301350409	17924	Indian	OW	P	
UTE TRIBAL 8-21D-55	21	050S	050W	4301350435	17963	Indian	OW	P	
UTE TRIBAL 8-34D-55	34	050S	050W	4301350436	17952	Indian	OW	P	
UTE TRIBAL 5-16D-54	16	050S	040W	4301350475	17991	Indian	OW	P	
UTE TRIBAL 12-14D-55	14	050S	050W	4301350476	17973	Indian	OW	P	
UTE TRIBAL 8-15D-55	15	050S	050W	4301350477	17974	Indian	OW	P	
UTE TRIBAL 3-14-55	14	050S	050W	4301350478	18002	Indian	OW	P	
UTE TRIBAL 5-14-55	14	050S	050W	4301350479	18021	Indian	OW	P	
UTE TRIBAL 8-10D-54	10	050S	040W	4301350488	18099	Indian	OW	P	
UTE TRIBAL 7-34-55	34	050S	050W	4301350510	17949	Indian	OW	P	
FEDERAL 4-4D-65	4	060S	050W	4301350521	18557	Federal	OW	P	
FEDERAL 6-3D-64	3	060S	040W	4301350522	18073	Federal	OW	P	
FEDERAL 1-1D-64	1	060S	040W	4301350524	18088	Federal	OW	P	
FEDERAL 7-2D-65	2	060S	050W	4301350525	18100	Federal	OW	P	
BERRY TRIBAL 12-34D-54	34	050S	040W	4301350527	17998	Indian	OW	P	
FEDERAL 15-5D-65	5	060S	050W	4301350553	18537	Federal	OW	P	
FEDERAL 11-4D-64	4	060S	040W	4301350565	18043	Federal	OW	P	
FEDERAL 6-6D-65	6	060S	050W	4301350566	18521	Federal	OW	P	
LC TRIBAL 3-15D-56	15	050S	060W	4301350598	18097	Indian	OW	P	
LC TRIBAL 8-16D-56	16	050S	060W	4301350599	18161	Indian	OW	P	
LC FEE 16-16D-56	16	050S	060W	4301350601	18165	Fee	OW	P	
LC TRIBAL 10-16D-56	16	050S	060W	4301350602	18586	Indian	OW	P	
LC TRIBAL 15-22D-56	22	050S	060W	4301350606	18278	Indian	OW	P	
LC TRIBAL 5-23D-56	23	050S	060W	4301350625	18285	Indian	OW	P	
LC TRIBAL 5-14D-56	14	050S	060W	4301350661	18219	Indian	OW	P	
SFW FEE 14-10D-54	10	050S	040W	4301350686	18070	Fee	OW	P	
LC FEE 1-22D-56	22	050S	060W	4301350718	18101	Fee	OW	P	
FEDERAL 8-2D-65	2	060S	050W	4301350719	18614	Federal	OW	P	
FEDERAL 1-2D-64	2	060S	040W	4301350730	18585	Federal	OW	P	
FEDERAL 7-2D-64	2	060S	040W	4301350734	18584	Federal	OW	P	
FEDERAL 10-6D-64	6	060S	040W	4301350735	18162	Federal	OW	P	
FEDERAL 4-3D-64	3	060S	040W	4301350736	18621	Federal	OW	P	
FEDERAL 12-3D-64	3	060S	040W	4301350737	18620	Federal	OW	P	
LC TRIBAL 3-21D-56	21	050S	060W	4301350751	18462	Indian	OW	P	
LC TRIBAL 5-21D-56	21	050S	060W	4301350752	18286	Indian	OW	P	
FEDERAL 2-1D-65	1	060S	050W	4301350759	18172	Federal	OW	P	
FEDERAL 3-1D-65	1	060S	050W	4301350760	18173	Federal	OW	P	

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

FEDERAL 5-1D-65	1	060S	050W	4301350761	18174	Federal	OW	P	
FEDERAL 9-2D-65	2	060S	050W	4301350762	18245	Federal	OW	P	
FEDERAL 11-2D-65	2	060S	050W	4301350763	18589	Federal	OW	P	
FEDERAL 15-2D-65	2	060S	050W	4301350764	18590	Federal	OW	P	
LC TRIBAL 14-14D-56	14	050S	060W	4301350776	18287	Indian	OW	P	
LC FEE 2-20D-56	20	050S	060W	4301350777	18622	Fee	OW	P	
LC TRIBAL 12-22D-56	22	050S	060W	4301350780	18341	Indian	OW	P	
FEDERAL 3-4D-65	4	060S	050W	4301350782	18556	Federal	OW	P	
FEDERAL 6-4D-65	4	060S	050W	4301350783	19162	Federal	OW	P	
FEDERAL 12-4D-65	4	060S	050W	4301350784	19171	Federal	OW	P	
LC TRIBAL 14-15D-56	15	050S	060W	4301350834	18362	Indian	OW	P	
UTE TRIBAL 7I-21D-54	21	050S	040W	4301350852	18423	Indian	OW	P	BERRY PILOT EOR 246-02
UTE TRIBAL 8L-21D-54	21	050S	040W	4301350853	18423	Indian	OW	P	BERRY PILOT EOR 246-02
UTE TRIBAL 10S-21D-54	21	050S	040W	4301350854	18423	Indian	OW	P	BERRY PILOT EOR 246-02
UTE TRIBAL 11-11-54	11	050S	040W	4301350861	18775	Indian	OW	P	
LC TRIBAL 2-28D-56	28	050S	060W	4301350866	18592	Indian	OW	P	
LC FEE 8-28D-56	28	050S	060W	4301350867	18342	Fee	OW	P	
LC TRIBAL 6-27D-56	27	050S	060W	4301350868	18480	Indian	OW	P	
LC FEE 15-23D-56	23	050S	060W	4301350870	18410	Fee	OW	P	
LC TRIBAL 15-26-56	26	050S	060W	4301350871	18377	Indian	OW	P	
UTE TRIBAL 16-11-55	11	050S	050W	4301350888	18707	Indian	OW	P	
LC TRIBAL 2-5D-56	5	050S	060W	4301350925	18568	Indian	OW	P	
LC TRIBAL 2-9D-56	9	050S	060W	4301350926	18425	Indian	OW	P	
LC FEE 8-29-45	29	040S	050W	4301350928	18313	Fee	OW	P	
LC FEE 13-29-45	29	040S	050W	4301350929	18426	Fee	OW	P	
LC FEE 9-12D-57	12	050S	070W	4301350963	18541	Fee	OW	P	
LC FEE 1-22-57	22	050S	070W	4301350965	18558	Fee	OW	P	
LC TRIBAL 11-3D-56	3	050S	060W	4301350966	18464	Indian	OW	P	
LC TRIBAL 3-34-45	34	040S	050W	4301350976	18661	Indian	OW	P	
LC TRIBAL 9-10D-56	10	050S	060W	4301350987	18944	Indian	OW	P	
LC TRIBAL 10-9D-56	9	050S	060W	4301350990	18864	Indian	OW	P	
LC FEE 10-31D-45	31	040S	050W	4301350994	18443	Fee	OW	P	
VIEIRA TRIBAL 4-4-54	4	050S	040W	4301350997	18747	Indian	OW	P	
LC TRIBAL 10-21-56	21	050S	060W	4301350999	18439	Indian	OW	P	
FEDERAL 1-5D-64	5	060S	040W	4301351012	18720	Federal	OW	P	
FEDERAL 2-5D-64	5	060S	040W	4301351013	18723	Federal	OW	P	
FEDERAL 7-5D-64	5	060S	040W	4301351014	18722	Federal	OW	P	
FEDERAL 8-5D-64	5	060S	040W	4301351015	18721	Federal	OW	P	
MYRIN TRIBAL 15-10-55	10	050S	050W	4301351024	18771	Indian	OW	P	
LC TRIBAL 15-15D-56	15	050S	060W	4301351030	18440	Indian	OW	P	
LC TRIBAL 9-15D-56	15	050S	060W	4301351031	18441	Indian	OW	P	
LC TRIBAL 6-28-45	28	040S	050W	4301351034	18700	Indian	OW	P	
FEDERAL 1-12D-65	12	060S	050W	4301351055	18739	Federal	OW	P	
FEDERAL 8-12D-65	12	060S	050W	4301351056	18718	Federal	OW	P	
FEDERAL 2-12D-65	12	060S	050W	4301351057	18738	Federal	OW	P	
LC TRIBAL 15-8D-56	8	050S	060W	4301351060	18862	Indian	OW	P	
LC TRIBAL 8-22D-56	22	050S	060W	4301351069	19233	Indian	OW	P	
LC TRIBAL 9-17D-56	17	050S	060W	4301351070	18945	Indian	OW	P	
LC TRIBAL 7-27-45	27	040S	050W	4301351073	18685	Indian	OW	P	
LC TRIBAL 11-24-45	24	040S	050W	4301351076	18745	Indian	OW	P	
FEDERAL 3-12D-65	12	060S	050W	4301351093	18705	Federal	OW	P	
FEDERAL 4-12D-65	12	060S	050W	4301351094	18704	Federal	OW	P	
FEDERAL 5-12D-65	12	060S	050W	4301351095	18702	Federal	OW	P	
FEDERAL 6-12D-65	12	060S	050W	4301351096	18703	Federal	OW	P	
LC TRIBAL 9-8D-56	8	050S	060W	4301351112	18522	Indian	OW	P	
UTE TRIBAL 4-9-54	9	050S	040W	4301351126	19059	Indian	OW	P	
UTE TRIBAL 6-9-54	9	050S	040W	4301351127	19017	Indian	OW	P	
UTE TRIBAL 2-9-54	9	050S	040W	4301351128	18946	Indian	OW	P	
UTE TRIBAL 1-10-54	10	050S	040W	4301351129	18879	Indian	OW	P	
LC TRIBAL 8-30D-56	30	050S	060W	4301351131	18539	Indian	OW	P	
LC TRIBAL 16-30D-56	30	050S	060W	4301351132	18540	Indian	OW	P	
FEDERAL 1-1D-65	1	060S	050W	4301351142	18623	Federal	OW	P	
UTE TRIBAL 8-9-54	9	050S	040W	4301351143	18947	Indian	OW	P	
FEDERAL 15-1D-65	1	060S	050W	4301351175	18654	Federal	OW	P	
FEDERAL 16-1D-65	1	060S	050W	4301351176	18655	Federal	OW	P	
LC TRIBAL 11-29D-56	29	050S	060W	4301351183	18873	Indian	OW	P	

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

STATE TRIBAL 8-12-55	12	050S	050W	4301351188	18986	Indian	OW	P	
LC TRIBAL 11-20D-56	20	050S	060W	4301351189	18819	Indian	OW	P	
LC FEE 5-20D-56	20	050S	060W	4301351190	18818	Fee	OW	P	
LC FEE 9-19-56	19	050S	060W	4301351192	18596	Fee	OW	P	
LC TRIBAL 9-9D-56	9	050S	060W	4301351198	18595	Indian	OW	P	
FEDERAL 16-6-64	6	060S	040W	4301351217	18792	Federal	OW	P	
FEDERAL 9-6D-64	6	060S	040W	4301351218	18791	Federal	OW	P	
UTE TRIBAL 5-17-55	17	050S	050W	4301351220	18841	Indian	OW	P	
UTE TRIBAL 16-3-54	3	050S	040W	4301351226	18664	Indian	OW	P	
STATE TRIBAL 15-6-54	6	050S	040W	4301351227	18746	Indian	OW	P	
STATE TRIBAL 8-7-54	7	050S	040W	4301351228	18743	Indian	OW	P	
STATE TRIBAL 12-1-55	1	050S	050W	4301351229	18741	Indian	OW	P	
STATE TRIBAL 11-2-55	2	050S	050W	4301351230	18742	Indian	OW	P	
FEDERAL 1-11-65	11	060S	050W	4301351231	18689	Federal	OW	P	
FEDERAL 8-11D-65	11	060S	050W	4301351232	18688	Federal	OW	P	
FEDERAL 2-11D-65	11	060S	050W	4301351233	18690	Federal	OW	P	
STATE TRIBAL 12-3-55	3	050S	050W	4301351236	18744	Indian	OW	P	
UTE TRIBAL 11-4-55	4	050S	050W	4301351237	18663	Indian	OW	P	
UTE TRIBAL 4-9-55	9	050S	050W	4301351238	18796	Indian	OW	P	
UTE TRIBAL 15-5-55	5	050S	050W	4301351239	18740	Indian	OW	P	
UTE FEE 9-9-54	9	050S	040W	4301351259	18642	Fee	OW	P	
LC TRIBAL 4-29-45	29	040S	050W	4301351260	18719	Indian	OW	P	
UTE FEE 14-9D-54	9	050S	040W	4301351271	18684	Fee	OW	P	
UTE FEE 15-9D-54	9	050S	040W	4301351272	18687	Fee	OW	P	
LC FEE 10-28D-56	28	050S	060W	4301351288	18591	Fee	OW	P	
UTE TRIBAL 8-16D-54	16	050S	040W	4301351295	19003	Indian	OW	P	
FEE TRIBAL 4-5-54	5	050S	040W	4301351303	19187	Indian	OW	P	
LC TRIBAL 1-26-56	26	050S	060W	4301351306	18816	Indian	OW	P	
UTE TRIBAL 6-16D-54	16	050S	040W	4301351307	19060	Indian	OW	P	
LC TRIBAL 7-22D-56	22	050S	060W	4301351308	18795	Indian	OW	P	
LC TRIBAL 9-22D-56	22	050S	060W	4301351309	18794	Indian	OW	P	
LC TRIBAL 9-32D-56	32	050S	060W	4301351316	19228	Indian	OW	P	
LC TRIBAL 7-26D-56	26	050S	060W	4301351319	18817	Indian	OW	P	
LC FEE 8-6D-56	6	050S	060W	4301351342	18657	Fee	OW	P	
LC FEE 10-29D-45	29	040S	050W	4301351343	18850	Fee	OW	P	
LC TRIBAL 1-7D-56	7	050S	060W	4301351344	18774	Indian	OW	P	
LC TRIBAL 9-7D-56	7	050S	060W	4301351346	18773	Indian	OW	P	
LC TRIBAL 11-10D-56	10	050S	060W	4301351369	18840	Indian	OW	P	
LC FEE 1-31D-45	31	040S	050W	4301351371	18686	Fee	OW	P	
LC TRIBAL 14-21D-56	21	050S	060W	4301351384	18877	Indian	OW	P	
LC TRIBAL 4-22D-56	22	050S	060W	4301351385	18878	Indian	OW	P	
LC TRIBAL 8-21D-56	21	050S	060W	4301351392	18874	Indian	OW	P	
UTE TRIBAL 1-17-55	17	050S	050W	4301351393	18848	Indian	OW	P	
LC TRIBAL 4-33D-45	33	040S	050W	4301351401	18853	Indian	OW	P	
LC TRIBAL 16-21D-56	21	050S	060W	4301351407	18875	Indian	OW	P	
UTE TRIBAL 2-10D-54	10	050S	040W	4301351411	19172	Indian	OW	P	
UTE TRIBAL 4-10D-54	10	050S	040W	4301351414	19069	Indian	OW	P	
LC TRIBAL 2-21D-56	16	050S	060W	4301351418	19252	Indian	OW	P	
LC TRIBAL 1-23D-45	23	040S	050W	4301351425	18855	Indian	OW	P	
LC TRIBAL 2-28D-45	28	040S	050W	4301351429	18701	Indian	OW	P	
LC TRIBAL 9-28D-45	28	040S	050W	4301351430	18656	Indian	OW	P	
LC TRIBAL 1-29-56	29	050S	060W	4301351442	18876	Indian	OW	P	
LC FEE 1-1-56	1	050S	060W	4301351458	18829	Fee	OW	P	
LC Tribal 12-32-45	32	040S	050W	4301351465	18772	Indian	OW	P	
UTE TRIBAL 2-5-54	5	050S	040W	4301351520	18880	Indian	OW	P	
LC Tribal 3-32D-45	32	040S	050W	4301351561	18842	Indian	OW	P	
LC TRIBAL 5-15D-56	15	050S	060W	4301351562	19253	Indian	OW	P	
LC FEE 16-36-56	36	050S	060W	4301351611	19096	Fee	OW	P	
LC TRIBAL 15-34-56	34	050S	060W	4301351647	18962	Indian	OW	P	
LC TRIBAL 1-34D-56	34	050S	060W	4301351660	18988	Indian	OW	P	
LC FEE 13-23-56	23	050S	060W	4301351706	18994	Fee	OW	P	
LC FEE 11-23D-56	23	050S	060W	4301351707	18995	Fee	OW	P	
LC TRIBAL 3-33-56	33	050S	060W	4301351711	19242	Indian	OW	P	
LC FEE 11-29D-45	29	040S	050W	4301351743	19188	Fee	OW	P	
LC FEE 4-28D-45	29	040S	050W	4301351745	18849	Fee	OW	P	
CC Fee 7R-28-38	28	030S	080W	4301351852	18863	Fee	OW	P	

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

FEDERAL 6-7-64	7	060S	040W	4301351915	19117	Federal	OW	P	
FEDERAL 3-7D-64	7	060S	040W	4301351916	19115	Federal	OW	P	
FEDERAL 4-7D-64	7	060S	040W	4301351917	19110	Federal	OW	P	
FEDERAL 5-7D-64	7	060S	040W	4301351918	19111	Federal	OW	P	
FEDERAL 2-7-64	7	060S	040W	4301351919	19139	Federal	OW	P	
FEDERAL 1-7D-64	7	060S	040W	4301351920	19140	Federal	OW	P	
FEDERAL 12-7D-64	7	060S	040W	4301351924	19025	Federal	OW	P	
FEDERAL 11-7D-64	7	060S	040W	4301351925	19039	Federal	OW	P	
FEDERAL 13-7D-64	7	060S	040W	4301351926	19026	Federal	OW	P	
FEDERAL 14-7D-64	7	060S	040W	4301351927	19040	Federal	OW	P	
FEDERAL 7-7D-64	7	060S	040W	4301351933	19141	Federal	OW	P	
FEDERAL 8-7D-64	7	060S	040W	4301351934	19142	Federal	OW	P	
FEDERAL 9-7D-64	7	060S	040W	4301351935	19143	Federal	OW	P	
FEDERAL 10-7D-64	7	060S	040W	4301351936	19144	Federal	OW	P	
ABBOTT FEE 2-6D-54	6	050S	040W	4301351949	18974	Fee	OW	P	
ABBOTT FEE 8-6D-54	6	050S	040W	4301351950	18964	Fee	OW	P	
ABBOTT FEE 4-6-54	6	050S	040W	4301351952	18965	Fee	OW	P	
Federal 15-12D-65	12	060S	050W	4301351992	19051	Federal	OW	P	
Federal 10-12D-65	12	060S	050W	4301351999	19052	Federal	OW	P	
Federal 9-12D-65	12	060S	050W	4301352000	19053	Federal	OW	P	
Federal 16-12D-65	12	060S	050W	4301352003	19054	Federal	OW	P	
Federal 1-6D-65	6	060S	050W	4301352012	19189	Federal	OW	P	
Federal 3-6D-65	6	060S	050W	4301352014	19190	Federal	OW	P	
Federal 2-6-65	6	060S	050W	4301352017	19191	Federal	OW	P	
Federal 7-6D-65	6	060S	050W	4301352018	19192	Federal	OW	P	
Federal 16-11D-65	11	060S	050W	4301352045	19070	Federal	OW	P	
Federal 15-11D-65	11	060S	050W	4301352046	19076	Federal	OW	P	
Federal 10-11D-65	11	060S	050W	4301352047	19077	Federal	OW	P	
Federal 9-11D-65	11	060S	050W	4301352048	19071	Federal	OW	P	
Federal 11-12D-65	12	060S	050W	4301352049	19121	Federal	OW	P	
Federal 12-12D-65	12	060S	050W	4301352050	19122	Federal	OW	P	
Federal 13-12D-65	12	060S	050W	4301352052	19123	Federal	OW	P	
Federal 14-12D-65	12	060S	050W	4301352053	19124	Federal	OW	P	
LC Tribal 12-28D-45	28	040S	050W	4301352089	19378	Indian	OW	P	
LC Tribal 2-32D-45	32	040S	050W	4301352113	19348	Indian	OW	P	
LC Tribal 16-29D-45	32	040S	050W	4301352114	19349	Indian	OW	P	
Vieira Tribal 3-4D-54	4	050S	040W	4301352145	19210	Indian	OW	P	
Vieira Tribal 5-4D-54	4	050S	040W	4301352146	19193	Indian	OW	P	
Vieira Tribal 6-4D-54	4	050S	040W	4301352147	19216	Indian	OW	P	
Lamplugh Tribal 6-3D-54	3	050S	040W	4301352148	19289	Indian	OW	P	
Lamplugh Tribal 5-3D-54	3	050S	040W	4301352149	19290	Indian	GW	P	
Lamplugh Tribal 4-3D-54	3	050S	040W	4301352150	19291	Indian	OW	P	
Lamplugh Tribal 3-3D-54	3	050S	040W	4301352151	19292	Indian	OW	P	
UTE Tribal 6-35D-54	35	050S	040W	4301352158	19254	Indian	GW	P	
UTE Tribal 4-35D-54	35	050S	040W	4301352159	19255	Indian	GW	P	
Heiner Tribal 3-11D-54	11	050S	040W	4301352165	19194	Indian	OW	P	
Heiner Tribal 4-11-54	11	050S	040W	4301352166	19195	Indian	OW	P	
Heiner Tribal 5-11D-54	11	050S	040W	4301352167	19196	Indian	OW	P	
Conolly Tribal 1-11D-54	11	050S	040W	4301352168	19270	Indian	OW	P	
Conolly Tribal 2-11D-54	11	050S	040W	4301352169	19197	Indian	OW	P	
Conolly Tribal 7-11D-54	11	050S	040W	4301352170	19280	Indian	OW	P	
Conolly Tribal 8-11D-54	11	050S	040W	4301352171	19281	Indian	OW	P	
Casper Tribal 1-5D-54	5	050S	040W	4301352180	19198	Indian	OW	P	
Fee Tribal 6-5D-54	5	050S	040W	4301352181	19199	Indian	OW	P	
Fee Tribal 5-5D-54	5	050S	040W	4301352182	19200	Indian	OW	P	
Fee Tribal 3-5D-54	5	050S	040W	4301352184	19201	Indian	OW	P	
Casper Tribal 7-5D-54	5	050S	040W	4301352185	19202	Indian	OW	P	
UTE Tribal 10-35D-54	35	050S	040W	4301352198	19320	Indian	OW	P	
UTE Tribal 14-35D-54	35	050S	040W	4301352199	19311	Indian	GW	P	
UTE Tribal 12-35D-54	35	050S	040W	4301352200	19312	Indian	OW	P	
UTE Tribal 16-35D-54	35	050S	040W	4301352230	19321	Indian	OW	P	
Evans Tribal 1-3-54	3	050S	040W	4301352234	19264	Indian	OW	P	
Evans Tribal 2-3D-54	3	050S	040W	4301352235	19265	Indian	OW	P	
Evans Tribal 7-3D-54	3	050S	040W	4301352236	19256	Indian	OW	P	
Evans Tribal 8-3D-54	3	050S	040W	4301352237	19257	Indian	OW	P	
Ute Tribal 9-3D-54	3	050S	040W	4301352249	19236	Indian	OW	P	

Berry Petroleum Company, LLC (N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

Ute Tribal 15-3D-54	3	050S	040W	4301352250	19237	Indian	OW	P	
Ute Tribal 10-3-54	3	050S	040W	4301352251	19238	Indian	OW	P	
Ute Tribal 14-3D-54	3	050S	040W	4301352298	19258	Indian	OW	P	
Ute Tribal 12-3D-54	3	050S	040W	4301352299	19259	Indian	OW	P	
Ute Tribal 11-3D-54	3	050S	040W	4301352300	19260	Indian	OW	P	
Ute Tribal 16-4D-54	4	050S	040W	4301352302	19350	Indian	OW	P	
Ute Tribal 15-4D-54	4	050S	040W	4301352303	19293	Indian	OW	P	
Ute Tribal 9-4D-54	4	050S	040W	4301352305	19304	Indian	OW	P	
Ute Tribal 10-4D-54	4	050S	040W	4301352307	19294	Indian	OW	P	
UTE Tribal 2-35D-54	35	050S	040W	4301352319	19322	Indian	OW	P	
UTE Tribal 8-35D-54	35	050S	040W	4301352320	19323	Indian	OW	P	
Abbott Fee 5-6D-54	6	050S	040W	4301352326	19351	Fee	OW	P	
Ute Tribal 6-11D-54	11	050S	040W	4301352330	19243	Indian	OW	P	
Ute Tribal 12-11D-54	11	050S	040W	4301352331	19244	Indian	OW	P	
Ute Tribal 14-11D-54	11	050S	040W	4301352332	19245	Indian	OW	P	
Ute Tribal 11-4D-54	4	050S	040W	4301352343	19305	Indian	OW	P	
Ute Tribal 12-4D-54	4	050S	040W	4301352344	19352	Indian	OW	P	
Ute Tribal 13-4D-54	4	050S	040W	4301352345	19353	Indian	OW	P	
Ute Tribal 14-4D-54	4	050S	040W	4301352346	19306	Indian	OW	P	
Ute Tribal 16-5D-54	5	050S	040W	4301352545	99999	Indian	OW	P	
Ute Tribal 15-5D-54	5	050S	040W	4301352546	99999	Indian	OW	P	
Ute Tribal 10-5D-54	5	050S	040W	4301352547	99999	Indian	OW	P	
Ute Tribal 8-5D-54	5	050S	040W	4301352548	99999	Indian	OW	P	
SCOFIELD-THORPE 26-31	26	120S	070E	4300730987	15218	Fee	D	PA	
SCOFIELD-THORPE 26-43	26	120S	070E	4300730990	14922	Fee	D	PA	
SCOFIELD CHRISTIANSEN 8-23	8	120S	070E	4300730999	15172	Fee	D	PA	
CC FEE 7-28-38	28	030S	080W	4301350887	18288	Fee	D	PA	
CC FEE 8-9-37	9	030S	070W	4301350896	18660	Fee	D	PA	
ST LOST CREEK 32-44	32	110S	070E	4304930023	14450	State	D	PA	
SCOFIELD THORPE 22-41X RIG SKID	22	120S	070E	4300730890	13719	Fee	GW	S	
SCOFIELD-THORPE 35-13	35	120S	070E	4300730991	14846	Fee	GW	S	
SCOFIELD-THORPE 23-31	23	120S	070E	4300731001	14923	Fee	GW	S	
NUTTERS RIDGE FED 5-1	5	060S	040W	4301330403	8231	Federal	OW	S	
WIRE FENCE CYN FED 15-1	15	060S	050W	4301330404	8233	Federal	GW	S	
R FORK ANTELOPE CYN FED 25-1	25	060S	050W	4301330406	8234	Federal	OW	S	
WOLF HOLLOW 22-1	22	060S	050W	4301330425	10370	Federal	GW	S	
ANTELOPE RIDGE 24-1	24	060S	050W	4301330426	10371	Federal	OW	S	
B C UTE TRIBAL 8-21	21	050S	040W	4301330829	8414	Indian	OW	S	BERRY PILOT EOR 246-02
Z and T UTE TRIBAL 10-21	21	050S	040W	4301331283	11133	Indian	GW	S	BERRY PILOT EOR 246-02
Z and T UTE TRIBAL 12-22	22	050S	040W	4301331311	11421	Indian	OW	S	
UTE TRIBAL 15-17	17	050S	040W	4301331649	11956	Indian	OW	S	
UTE TRIBAL 7-30	30	050S	040W	4301332167	12945	Indian	OW	S	
UTE TRIBAL 8-35-55	35	050S	050W	4301332267	13571	Indian	OW	S	
UTE TRIBAL 10-16-55	16	050S	050W	4301332345	13693	Indian	OW	S	
FOY TRIBAL 11-34-55	34	050S	050W	4301332351	13648	Indian	OW	S	
UTE TRIBAL 13-30-54	30	050S	040W	4301332409	13968	Indian	OW	S	
UTE TRIBAL 3-33-54	33	050S	040W	4301332412	13938	Indian	OW	S	
UTE TRIBAL 1-20-55	20	050S	050W	4301332414	14548	Indian	OW	S	
UTE TRIBAL 11-30-54	30	050S	040W	4301332512	13982	Indian	OW	S	
UTE TRIBAL 2-24-54	24	050S	040W	4301332569	14314	Indian	OW	S	
UTE TRIBAL 10-14-55	14	050S	050W	4301332601	14331	Indian	OW	S	
MOON TRIBAL 3-27-54	27	050S	040W	4301332613	14416	Indian	OW	S	
UTE TRIBAL 7-21-54	21	050S	040W	4301332623	14383	Indian	OW	S	BERRY PILOT EOR 246-02
UTE TRIBAL 16-24-55	24	050S	050W	4301332672	14384	Indian	GW	S	
UTE TRIBAL 7-35-54	35	050S	040W	4301332774	15019	Indian	OW	S	
UTE TRIBAL 16-25-54	25	050S	040W	4301332779	15078	Indian	OW	S	
MOON TRIBAL 13-27-54	27	050S	040W	4301332801	15057	Indian	OW	S	
UTE TRIBAL 15-15-55	15	050S	050W	4301332855	15114	Indian	OW	S	
UTE TRIBAL 5-36-55	36	050S	050W	4301332930	15301	Indian	OW	S	
UTE TRIBAL 8-24-54	24	050S	040W	4301332933	15402	Indian	OW	S	
UTE TRIBAL 12-15-55	15	050S	050W	4301332981	15348	Indian	OW	S	
UTE TRIBAL 9-21-54	21	050S	040W	4301333040	15360	Indian	OW	S	BERRY PILOT EOR 246-02
UTE TRIBAL 15-21-54	21	050S	040W	4301333114	15441	Indian	OW	S	BERRY PILOT EOR 246-02
UTE TRIBAL 10-16-54	16	050S	040W	4301333129	15454	Indian	OW	S	
TAYLOR FEE 7-14-56	14	050S	060W	4301333140	15601	Fee	OW	S	
UTE TRIBAL 9S-25-55	25	050S	050W	4301333245	15962	Indian	OW	S	

Berry Petroleum Company, LLC N4075) to Linn Operating, Inc. (N4115)
Effective June 1, 2014

UTE TRIBAL 9-5-54	5	050S	040W	4301351111	18909	Indian	OW	S	
ABBOTT FEE 6-6-54	6	050S	040W	4301351948	18963	Fee	OW	S	